



Mining dept.





CONCENTRATING ORES BY FLOTATION

BEING A DESCRIPTION AND HISTORY OF A
RECENT METALLURGICAL DEVELOPMENT, TO-
GETHER WITH A SUMMARY OF PATENTS AND
LITIGATION,

BY

THEODORE J. HOOVER

*A.B., Leland Stanford Jr. University,
Member Institution of Mining and Metallurgy,
Member Société Belge des Ingenieurs et des Industriels,
Associate Member of American Institute of Mining Engineers.*



THE MINING MAGAZINE

SALISBURY HOUSE, LONDON, E.C.

AGENTS IN U.S.A. :

MINING AND SCIENTIFIC PRESS

420, MARKET STREET, SAN FRANCISCO

1912

TN 523

1+6

cop. 2

MINING DEPT.

Mining dept.

TO THE
MINING DEPT.



To the Teachers of Science in Leland Stanford Jr. University
who gave me the desire to know and to learn.

CONTENTS.

CHAPTER I.

Historical Sketch—Position of the Processes in the Art of Metallurgy—Inventory—Development—Haynes—Bradford—Everson—Robson & Crowder—Elmore (Old Process)—Van Meter—Potter-Delprat—Froment—Minerals Separation—Goyder & Laughton—Wolfe—Elmore (New Vacuum Process)—De Bavay—Gillies—Macquisten—Murex—Zinc Corporation—Hyde.

CHAPTER II.

Patents—Expired Patents—Unexpired Patents.

CHAPTER III.

Litigation—Decided Cases—Elmore v. Van Meter—Sulman & Picard v. Wolf—De Bavay v. Macquisten—Potter v. The Broken Hill Proprietary Co., Ltd.—Ore Concentration Co., Ltd., v. Webster and Others—Elmore v. Minerals Separation, Ltd.—Minerals Separation, Ltd., v. Norris—Minerals Separation, Ltd., v. Potter—British Ore Concentration Syndicate, Ltd., and Alexander Stanley Elmore v. The Minerals Separation, Ltd. Undecided Cases: Elmore v. The Sulphide Corporation, Ltd.—Potter v. The Sulphide Corporation, Ltd.—Minerals Separation, Ltd., v. De Bavay—Minerals Separation, Ltd., v. Hyde.

CHAPTER IV.

Theories—Surface Tension—Adhesion—Bubbles—Commercial Effectiveness—Soluble Frothing Agents—Coagulation.

CHAPTER V.

Tests—Experiments—Apparatus—Curves—Potter—Delprat—De Bavay—Macquisten—Elmore—Gasification—Deleterious Substances—Problems for Research.

CHAPTER VI.

The Potter-Delprat Process—Apparatus—Application—Working Costs—Recovery.

CHAPTER VII.

The De Bavay Process—Apparatus—Recovery—Application.

CHAPTER VIII.

The Elmore Vacuum Flotation Process—Apparatus—Working Costs—Application.

CHAPTER IX.

The Minerals Separation Process—Apparatus—Application—Recovery.

CHAPTER X.

Other Flotation Processes—Macquisten—Murex—Sanders—Horwood—Hyde.

CHAPTER XI.

Economics—Limitations—Separation of Sulphides—Combinations—Slime—Magnitude of Operations—Advantages—Broken Hill—Royalties—Costs—Conclusions.

CHAPTER XII.

Bibliography.

PREFACE.

This book is intended as an interim report of progress in a rapidly developing art. It is put forward in the hope that it may prevent duplication of labour on the part of ambitious inventors, and that it may give engineers not already familiar with the subject a starting point in the application of a new method of turning ores to account.

My debt to the labour and assistance of others can hardly be acknowledged adequately. To the directors of Minerals Separation, Ltd., cordial thanks are due for permission to publish much information collected during four years while acting as their general manager and consulting engineer. Although this permission is kindly granted, they are not necessarily in agreement with all the opinions expressed, and, in fact, quite properly oppose some of the views set forth.

To H. Livingstone Sulman and Hugh F. K. Picard, of the firm of Sulman & Picard, I am indebted for many ideas absorbed from them through three years of pleasant professional association (during which time they were consulting metallurgists to the above company). They have in preparation a book on the 'Theories of Concentration Processes Involving Surface Tension,' which will be a work of high scientific merit. I have endeavoured, I hope successfully, not to trespass on any new and unpublished ground, the announcement of which rightfully belongs to them; further, it is not my desire to present the subject in so profound a manner as they will do, deeming it of considerably more use to engineers to leave the discussion of the mathematical and physical laws involved for another occasion.

To the members of my former staff and others, Deane P. Mitchell, James M. Hyde, James Hebbard, E. J. Horwood, Henry Lavers, Edward H. Nutter, George W. Thompson, H. H. Greenway, A. Howard Higgins, George A. Chapman, A. Sydney Stevens, E. Ray Wilkinson, Alfred K. Burn, A. C. Howard, George C. Klug, C. J. Hylton, John Leechman, F. Glynn Price, and E. E. Wood, I am indebted to an extent that the mere mention of their names but scantily requites.

The files of the current technical journals and financial papers have been drawn upon with a free hand; these receive individual acknowledgment in the bibliography.

THEODORE J. HOOVER.

London, *July* 4, 1912.

CONCENTRATING ORES BY FLOTATION.

CHAPTER I.

HISTORICAL SKETCH.

The ores of the base metals when taken from the earth contain the valuable portion in chemical combination, generally with sulphur, in the form of particles of metallic sulphide, mixed with a large quantity of worthless rock. The ore is first crushed to a suitable degree of fineness, in order to free the sulphide particles from the adhering gangue, and the crushed mass is then subjected to mechanical operations with a view to separating all the sulphide particles into one pile, and all the worthless gangue into another pile. The sulphides are then smelted to recover the metals. The oldest method of accomplishing this separation is by mixing the crushed ore with sufficient water to form a freely-flowing pulp and then subjecting the pulp to a shaking, throwing, and flowing motion, on suitable machines, whereby the sulphide particles, being much heavier than the gangue, travel faster and farther than the gangue, and are diverted at the proper time and place to effect a separation. This method is ancient, and was the only one known for hundreds of years.

A second method, introduced not long ago, made use of the magnetic qualities of the valuable minerals. These in general have a stronger magnetic permeability than the gangue, and if the ore is suitably subjected to the influence of powerful magnets, the valuable mineral particles can thereby be separated from the worthless gangue.

These two methods have limitations as to their usefulness, and these limitations have been a constant spur to metallurgists, urging them to the discovery of new modes of treatment.

The knowledge that substances heavier than water would, under suitable conditions, float on its surface is not at all new, the best known example being that of a greased needle carefully placed on water. It has been known also for many years that some heavy substances will float on the surface of water with more certainty than others, and the principles involved in this fact formed the basis of a third method of separating mineral sulphides from gangue as soon as it was recognized that the sulphides would float with greater facility than the gangue. The successful concentration of ores by causing the metallic sulphides to float at the surface of a liquid, and the gangue or waste rock to sink within, with entire disregard of relative specific gravities or magnetic qualities, has now not only overcome the suspicious novelty of its earlier phases, but has an established and growing position in the metallurgy of the base metals. The progress of the practical application of this principle has been so great during the past ten years as to place it now among the sure expedients of the metallurgist. To the minds of those who have had occasion to apply the process it seems almost as great an advance in the dressing of base-metal ores as the cyanide process proved to be in the recovery of the precious metals. In the recovery of zinc sulphides, especially from the by-products of lead milling, and also of finely disseminated copper sulphides from silicious gangues, it has already a wide field in instances where other methods were of imperfect application, and the range of its application is daily being widened.

A new metallurgical process never springs fully developed from the brain of one person, but is the result of patient investigation, application, and improvement by many minds, during many years. Metallurgical advances can best be likened to the construction of a pyramid by the constant addition of material. The erection of such structures can never be credited to a single person. The first stones are usually laid by those who had an imperfect vision of the structure that would arise, and while many builders come into prominence from year to year, many stones are laid by unknown hands. No builder need flatter himself he has completed the structure by placing a peak stone in place, for while he is in the very act, it is quite likely an ambitious newcomer has begun a dozen new courses of masonry at the base of the pyramid. Unfortunately, besides the question of individual credit, there also enters the more serious one of ownership to

parts of the structure. Constructive work may be entirely suspended while the courts adjudicate the rights of rival claimants; the completion of the structure is delayed; the time and means of the builders are wasted; and the needs of the industry suffer. The names of those who are known to have helped in this case are Haynes, Tunbridge, Miss Everson, Hebron, Bradford, Dodé, Sutton, Robson, Crowder, the Elmore brothers, Potter, Delprat, Van Meter, Boss, Haultain, Stovel, Froment, Scammell, Cattermole, Goyder, Laughton, Wolf, Sulman, Picard, Ballot, De Bavay, Darling, Gillies, Kirby, Macquisten, Sanders, Schwarz, Chapman, Kendall, Latimer, Hoover, Norris, Higgins, Lockwood, Samuel, Greenway, Horwood, Wentworth, Lavers, Nutter, Hyde, Hockley, Rouse, Maleczek, Allen, Wynne, Dick, Ruthenburg, McCourt, Orr, and Good.

Tardy justice demands that among those who builded better than they knew, the name of Carrie J. Everson, an American school-teacher, and an assayer and chemist of ability, should be specially mentioned, because she discovered and enunciated the main and fundamental principles upon which all subsequent work has been based.

The development of this important department of metallurgy can be divided roughly into three stages. During the first of these, 1860 to 1902, there were brought forward at least a dozen methods for causing sulphides to float on an ore-pulp, and these methods fell into two principal classes, although there were even then some patents which could not properly be placed in either class :—

- (1). Those depending on the selective action of oily substances for sulphide particles to entrap the sulphides, and the buoyancy of the oily substance to effect flotation.
- (2). Those depending on the selective action of gas for sulphide particles, and which under certain conditions endowed the particles with a gaseous envelope, and so induced flotation.

Neither of these ideas when used independently produced entirely satisfactory results, although they were not without some commercial profit.

The second stage, from 1902 to 1907, was marked by a practical advance when the idea was developed of endowing the particles with an oily coating in an acid solution, thus increasing their affinity for the gaseous envelope. This combination of the two

fundamental ideas of the preliminary stage has made it possible to secure a high degree of flotation among many sulphides. These two stages belong primarily to the inventor, the so-called unpractical man.

The third stage, 1907 to 1912, in which we now are, is the stage of the engineer : the commercial application of the idea. Suitable mechanical devices had to be invented to produce the proper mixture of gases, liquids, and solids, and to entrap the concentrate when afloat. This stage has now reached so practical a development as to find widespread commercial application.

The different processes have been developed along several lines parallel to each other, so that it is difficult to discuss them as a whole chronologically. They will, therefore, be considered separately in the order of their first appearance.

HAYNES.

William Haynes in 1860 invented a process for separating mineral sulphides from the gangue or rocky constituent of an ore by the use of oily, gummy, or bituminous matter. This was not a 'flotation' process, but must be considered the pioneer movement in that direction, as Haynes recognized the fact, all important in later developments, that oily substances have a greater affinity for sulphides and metals than they have for oxides and earthy substances. No commercial application of this invention is known to have been attempted.

BRADFORD.

Hezekiah Bradford, in 1886, invented a process of concentration based on 'surface tension' factors, but no commercial application of the idea is known to have resulted. His patent is an important and interesting one, because the flotation of sulphide particles on the surface of a liquid at rest is clearly set forth.

EVERSON.

Carrie J. Everson, in 1885, invented a process for separating the sulphides in an ore from the gangue. She made use of the selective action of the oil for sulphides, discovered by Haynes, but she also carried the idea two steps further. She discovered—(1) that acid, added in small quantity to the pulp, greatly increased the selective action of the oil ; and (2) that the oiled mineral could be separated from the gangue by giving the mass thorough agitation, and allowing the sulphides and the oil to float to the surface, while the

gangue escaped at the bottom of the vessel. The amount of oil used is variously stated in certain experiments as 6%, 12%, and 20%; the amount of acid was less than 1%. It is worthy of note that none of the quantities of oil specified are sufficient to effect the flotation of the sulphide contents of the ore by the buoyancy of the oil alone, and the flotation must, therefore, have been effected by some other means. The new principles disclosed in this patent were that acid increases the selective action of the oil, and that minerals can be separated from each other by allowing some to float and others to sink. Miss Everson stumbled across the idea quite accidentally.¹ Some sacks in which concentrate had been shipped to her brother's assay-office at Denver had become greasy, and in the process of washing the sacks, the germ of the idea of oil-flotation came under her observation. Attention should be directed to the fact that this invention is strictly feminine in its origin. No masculine assayer probably ever did or ever will launder sample-sacks or ore-bags; when they have reached the condition in which they need washing and where simple shaking does not make them available for further use, they are discarded. When she had the greasy concentrate-sacks in the wash-tub and gave them such agitation as was incident to the operation of washing, it only required the customary acuteness of observation of the Western lady school-teacher to grasp the essential facts of sulphide flotation. This process was tried on a fairly large scale at Baker City, Oregon, in 1889, and also near Denver in the same year. A capitalist by the name of Thomas F. Crilley financed the undertaking. In the process as tried at Baker City, under the name of the Crilley & Everson process, the ore was crushed to 50-mesh, weighed, and roughly mixed with a thick black oil. Boiling water, containing enough acid to give it a tart taste, was then added to the ore.² A thick scum of mineral and oil rose to the surface, and was skimmed off,³ leaving the gangue at the bottom of the vessel.⁴ This process was improved in 1892 by Hebron and Everson, whereby they combined pulverized ore with a buoy-stock in a dry state and then applied the prepared ore to a stratifying apparatus into which air

¹ *Financial Times*, March 3, 1902.

² *Eng. & Min. Jour.*, Nov. 15, 1890, p. 581.

³ *The Denver News*, Nov. 2, 1889, quotes a description from the *Herald-Democrat*.

⁴ *Alta Californian*, Dec. 2, 1889.

could be introduced for the purpose of producing effervescence.

The newspaper accounts of the attempts to apply this idea give one a strong impression that if the invention had been a less startling innovation it would probably have received more attention from engineers and metallurgists and the development of the idea would probably in that case have taken place many years before it did. The competition for ores and products was also less keen at this time than later and there was therefore not the incentive there is today to turn refractory ores to account.

No further definite commercial advance was made, and nothing more was heard of concentration by flotation until 1894.

ROBSON & CROWDER.

In 1894 Robson & Crowder invented a process for separating sulphides from gangue ; they made use of the idea of oil-selection, but they did not recognize the benefit of acid in increasing this selective action, as Everson had done. Their invention differed from former similar ones in that they used but little water ; they say, 25 to 30%. They mixed the ore and water in a vessel having a suitable agitator, added the oil at the bottom of the vessel during agitation, and allowed it to overflow. Presumably, after a time, the oil had selected and carried over all the sulphides, leaving the gangue, mixed with oil and water, in the bottom of the vessel, from which it could be drawn off. The process was tried at the Glasdir mine in Wales, on a fairly large scale. This mine was the place where Elmore later developed his idea of oil-flotation. In April, 1896, James Brothers made a careful examination of the plant and process for a client, and reported that the process was worthy of development, as it seemed adapted to a large class of ores at that time untreatable by other processes. Nothing material came of this effort, however, and the idea lay dormant until 1898, when F. E. Elmore advanced it apace.

ELMORE (OLD PROCESS).

Francis E. Elmore, in 1898, invented a concentration process that involved the idea of oil selection and the idea of flotation in a freely flowing acid pulp. He mixed the ore with several times its weight of water, and an equal, or several times greater weight of oil in a revolving drum,* so constructed and operated as to

**Trans. I.M. & M.*, Vol. VIII., p. 379-395, Chas. M. Rolker.

give a mixing effect without breaking up or emulsifying the oil, which was added with the ore. He did not mention the amount of oil used, but from the fact that he described in his patent a pump for the oil and a centrifugal apparatus for separating the concentrate from the oil, it is inferred that the amount of oil used was considerable. After thus gently mixing, the mass was allowed to run into a spitzkasten, where the oil carried the sulphides to the surface, and the gangue and the water were removed from the bottom. This invention marks a decided advancement in flotation-concentration, and was put into operation in a workmanlike manner.

The process had commercial application on a large scale. It was in the hands of capable engineers, who were not oblivious to its imperfections, and who appreciated that no one process is ever a cure for all the troubles incidental to the treatment of ores. They tried consistently to adapt the process to suitable ores, and where they made mistakes these were only such as must be made when development along new lines is attempted. This process was the first of the kind to approach commercial success, and it was a commercial success in many places; but further improvements in flotation concentration have rendered the method obsolete.

The process was tried by the Boston Consolidated Co., Cape Copper Co., and Namaqua Copper Co.¹ The United States rights were² purchased by Charles Butters, who tried it on the ore of the Mammoth Mining Co., Utah.³ Companies were organized in Canada,⁴ Great Britain, Sweden, Australia,⁵ and plants were built in Norway, England, and in British Columbia on the Le Roi mine. The Le Roi plant had a long series of vicissitudes, and was finally closed down.⁶ Plants were built at Tywarnhaile⁷ in Cornwall, at the Sygun mine in Wales,⁸ and at the St. David's mine in Wales.⁹ In 1903,¹⁰ the firms of S. Neumann & Co. and

1 *Eng. & Min. Jour.*, Sept. 1, 1900, p. 241.

2 *Eng. & Min. Jour.*, Dec. 8, 1900, p. 661.

3 *Eng. & Min. Jour.*, June 29, 1901, p. 836.

4 *Eng. & Min. Jour.*, July 5, 1902, p. 308.

5 *Mineral Industry*, Vol. XI., p. 656.

6 *Eng. & Min. Jour.*, Jan. 5, 1905, p. 160.

7 *Mineral Industry*, Vol. XI., p. 698-707.

8 *Eng. & Min. Jour.*, Jan. 17, 1903, p. 134.

9 *Eng. & Min. Jour.*, Feb. 14, 1903, p. 262.

10 *Eng. & Min. Jour.*, July 25, 1903, p. 136.

Wernher, Beit & Co. purchased a quarter interest in the rights for the whole world, and prepared to push the development and application of the process. The year 1905 may be said to close the activities of the old Elmore process, as most of the plants were either closed down entirely or modified for what is now known as the Elmore vacuum process.

VAN METER AND BOSS.

James W. Van Meter and Martin P. Boss in 1902 invented an oil process, which was installed¹ at the Santa Barbara mine and also by the Alvimina Mining Co., both in Peru. This process was similar to the Everson process and the old Elmore process in its main principles, but the apparatus was somewhat different. Though the published results were good, the process has disappeared from the field of concentration in consequence of further developments.

POTTER-DELPAT.

Charles V. Potter in 1902 invented a process of mineral flotation wherein the flotation was accomplished in a 1 to 10% solution of acid. He added one ton of this solution to one ton of ore, agitated freely, and applied heat. As the temperature of the pulp increased, the heat caused the sulphides to rise to the surface, from which they were allowed to flow continuously or were skimmed off. Potter did not mention the use of any gas, but it is clear that he had in view a surface-tension process. In 1902 there had been rumours at Broken Hill² that a new process along radically new lines had been discovered at the Proprietary mine. This was especially interesting, as there were in the district several million tons of crushed material that had hitherto defied treatment. The rumour proved to be true, and later was announced as the Delprat or salt-cake process. The priority of patent, however, fell to Charles V. Potter, who had been working on similar lines to Guillaume D. Delprat. Potter used an acid liquor to effect flotation, while Delprat accomplished the same result in the same way with acid salt-cake solution. The effect of the acid or salt-cake is to generate bubbles of gas, which selectively adhere to the sulphides and float them. Potter and Delprat invented improvements from time to time subsequently, and their most recent patents indicate that the owners of these processes appre-

¹ *Pacific Coast Miner*, May 30, 1903, p. 391.

² *Ann. Rep. Dept. of Mines*, N.S.W., 1902, p. 69.

ciate that a small quantity of oil is of decided advantage to flotation. The Potter process received its chief application at the Block 14 mine at Broken Hill, in 1905 and 1906, where it had a measure of success on sharp sand, the attempt to treat slime being attended with many difficulties; the plant is now dismantled. It was also tried at the Zinc Corporation's plant, where it was pronounced a failure. The Delprat process is installed at the Broken Hill Proprietary mine, where it is a decided success, and produces about 80,000 tons of zinc concentrate per year. This plant is the third largest flotation-concentration plant in the world, treating about 1,000 tons per day, and it is a pity that a policy of secrecy as to its later developments is thought necessary. The Potter and Delprat interests soon became involved in litigation, ending in a compromise, so that the process is now generally described as the Potter-Delprat.

FROMENT.

In 1901 Alcide Froment, of Traversella, Italy, discovered that when a sulphide ore is agitated in water in the presence of a small quantity of oil and sulphuric acid, the sulphide particles become oiled and attach themselves to and are floated by gas bubbles. He recommended adding a small amount of calcite to ores when needed. This discovery is of the greatest importance, as the successful development of oil-flotation processes has been based principally upon making use of the fact that oiled sulphide particles readily attach themselves to, and are floated by, gas bubbles. Minerals Separation Ltd. bought this patent in November, 1903.

MINERALS SEPARATION,

In 1903 a company was organized by John Ballot, J. H. Curle, W. W. Webster, S. Gregory, H. L. Sulman, and H. F. K. Picard, all of whom had for many years been interested in ore-treatment problems. The original purpose of this company—Minerals Separation, Ltd.—was to acquire and operate the Cattermole patents. Soon after organizing, they purchased the Froment patents, and from time to time since then they have invented improvements and additions. Their present processes are based on surface-tension phenomena, accelerated by means of the addition to the pulp of very small quantities of oil and of air in a fine state of subdivision, the purpose of the oil being to coat the

sulphides with a thin film of oil, and the purpose of the air being to adhere to the oiled mineral particles, and to raise them to the surface in the form of a froth.

The Cattermole invention was a process of ore concentration in which use was made of the idea of oil selection. He added to a freely flowing pulp from 4 to 6% of oil in proportion to the sulphide contents and also to the pulp, 2% of soap, the amount depending on the metallic contents of the ore, the object being to produce granules of sulphides of a definite size, or in other words, coagulation of the sulphides. For slimy ores he added a portion of coarser sulphide particles to serve as nuclei for the formation of granules, and effected the separation by an upcast current of water, taking the gangue off the top and the granules at the bottom. Another of this company's inventions was by Sulman & Picard in 1903, a process of oil concentration in which they introduced bubbles of air or other gas, and also oil in the form of a spray, into the freely flowing acidulated pulp. This invention follows Froment and Cattermole in its main lines, but is novel in the methods of introducing the oil, and in the method of the introduction of air into the slightly oiled pulp. The best development of this series was the introduction, in 1905, of a method which I am informed by their solicitor has recently been denominated by the Minerals Separation, Ltd., as the 'agitation-froth process,' a method of flotation in which an extremely small amount of oil, less than 0.1%, was added to a freely flowing pulp, followed by violent agitation for from 1 to 10 minutes. Innumerable small bubbles of air were thus mechanically included in the pulp, which joined the oil-coated mineral particles by means of the surface tension of bubbles, and floated them in the form of a froth, which was separated in a spitzkasten. The tailing from the spitzkasten was then exposed to the air as it flowed over an inclined surface, and any oiled mineral that had escaped coming in contact with air-bubbles there took up its proper air-film and floated as a film on a second spitzkasten. Other improvements in this company's method and apparatus have been made from time to time, the most important of which was the Hoover apparatus.

The first plant using this process was erected in Australia, on the Central mine at Broken Hill, to treat an accumulation of zinkiferous tailing from the Sulphide Corporation's lead-concentrating mill. It had a capacity of 400 tons per day. This plant



HISTORICAL SKETCH.

ran two years with an average of 72 per cent. recovery of the zinc in the form of a high-grade concentrate. The Sulphide Corporation then built a second plant, as part of a new concentrating mill, to take the current tailing from the lead concentrators, and thus has a complete mill, turning out lead concentrate by ordinary tables, and zinc concentrate by the Minerals Separation process in one continuous operation. This plant has a capacity of 900 tons per day. The Minerals Separation, Ltd., purchased the remainder of the Central mine's accumulated zinkiferous mill-tailing, and erected a third plant for the treatment of this material by their own process. This plant had a capacity of 900 tons per day. When the two last-mentioned plants were in successful operation the first plant was abandoned, being antiquated by virtue of later improvements. A fourth plant for the use of this process on an accumulation of zinkiferous and plumbiferous slime from the Block 10 and Central mines was then erected. Nearly all this material was fine enough to pass a 100-mesh screen. No difficulty was encountered in producing a pure mixed lead and zinc sulphide from this material, but the smelting of the concentrate presented such difficulty that the operation of the plant was discontinued. Recent developments in both the art of smelting zinkiferous concentrate and also in the methods of flotation-concentration warrant the belief that this slime-plant can now operate at a profit.

This process was, among others, tried by the Zinc Corporation in its early struggles, but for some reason it was impossible to get the results that were being obtained on the Central mine. Thereupon the process was discarded in 1907 in favour of the Elmore vacuum process, which was in use profitably for two years. Then in 1910, owing to the exhaustion of the material treatable by this process and to decided improvements in the apparatus for the Minerals Separation process, the Elmore process was discarded and the Minerals Separation process installed.

This process was tried in South Russia, at the Caucasus Copper mine, on a small scale, but although the trials were favourable, the company did not see fit to give it an extended application.

A unit having a capacity of 250 tons per day was installed at the Great Fitzroy mine, Queensland, and after extended trials and being several times re-modelled, now seems in a fair way toward commercial success.

On the Orijarvi* mine, in Finland, a small unit of this process was installed, but is not now in use.

**Eng. & Min. Jour.*, Vol. xci., 1911, p. 759.

A small plant was also built at the Emu Works, Swansea, for a trial of the San Francisco del Oro ore, but the attempt was not a commercial success, because of the excessive acid consumption. Recent developments indicate that possibly this ore can be treated by the use of sodium bisulphate and other reagents.

The Junction North mine, at Broken Hill, is installing a plant designed to treat slime mixed with crushed crude ore from the mine.

A large plant has recently been erected on the Braden copper mine for the treatment of a copper ore which had hitherto given considerable trouble. The plant is a large one and the results are excellent.

GOYDER & LAUGHTON.

Goyder & Laughton, in 1903, invented a machine which employed Potter's idea of adding the ore to an acid solution. They were the first to disclose the principle governing Potter's and Delprat's acid-flotation processes, namely, that the action of the acid on the ore generated gas-bubbles to which the sulphide particles attached themselves and were floated to the surface. One of the difficulties of the acid-flotation process was that the bubbles broke on reaching the surface, and the mineral particles sank again, that is, the surface tension was not strong enough to hold them up under the conditions to which the particles were exposed for flotation. This invention not only seeks to obviate a bad feature of the acid-flotation process, but in a measure takes advantage of it. The machine was tried in several plants at Broken Hill, but is not now in use.

WOLF.

Jacob D. Wolf, in 1903, invented a method of applying the principles of flotation. He used sulpho-chlorinated oil, or any other oil, and aimed to secure a high degree of mineral extraction with a low grade of concentrate in the first step, and by washing the concentrate with hot water in a suitable vessel to increase the grade of concentrate in the second step. As another feature in his process, air or steam was blown into the tailing, which raised to the surface globules of lost oil, with sulphides adhering thereto, thus increasing the percentage of extraction. This patent contains several ingenious devices, but no practical application of the invention has so far been made.

ELMORE (NEW VACUUM PROCESS).

In 1904, Francis E. Elmore took out a patent for an apparatus and process wherein he secured flotation in the form of a mineral froth by the addition of a small quantity of oil, and by the liberation of the air in the pulp in a fine state of subdivision, the liberation of the air being accomplished by subjecting the freely flowing pulp to a vacuum, and by heating, whereupon the air which is dissolved in the pulp, amounting to 2.2% by volume, at normal temperature and pressure, is released and attaches itself to the slightly oiled mineral particles, raising them to the surface. This process is performed in a machine of rather complicated design, having a capacity of 20 to 50 tons per day, depending on the nature of the ore. A battery of these is operated with comparative ease after the men have become accustomed to the different adjustments. This process had its most noted application at Sulitelma in Norway, and also at the Zinc Corporation's plant* at Broken Hill, where it proved a decided success. This last-mentioned plant had 16 units in operation, producing 75,000 tons of concentrate per year. The concentrate was re-treated by burning off the oil and then passing it over Wilfley tables to remove some of the lead. This process has been replaced by the Minerals Separation process.† The British Broken Hill Proprietary mine has a battery of 10 vacuum machines in operation.

The Elmore vacuum process has also been installed at Dolcoath, Ramsley, and Dolgelly, in Great Britain,‡ at the Garpensberg, Traag, Hadeland, Sulitelma, Telemarken, and Saxberget mines in Scandinavia, and at the Edmundian mine in Africa. It has been installed, but it is not working at the present time, at the Pinnacles mine and the Cobar gold mines in New South Wales, the Namaqua copper mine in South Africa, the Caucasus copper mine in Russia, at the Avino mine in Mexico, and elsewhere.

DE BAVAY.

Auguste J. F. De Bavay, in 1904, invented a flotation process in which a thin film of freely-flowing pulp was brought to the surface of a vessel of water where advantage was taken of the surface

**Eng. & Min. Jour.*, Vol. LXXXVIII., June 1, 1909, p. 205.

†*Eng. & Min. Jour.*, Vol. XCI., June 1, 1911, p. 1,198.

‡*Eng. & Min. Jour.*, Vol. LXXXIII., June 1, 1907, p. 1,037.

tension of the liquid, and the sulphide floated. He further points out that if the surface of the sulphide particles is coated with a film of carbonate from weathering, this is detrimental to the process, and should be removed by soaking the ore in a weak solution of carbonate of ammonia, or by passing carbonic acid gas through the pulverized wet ore, or by friction.

His process was installed at the Broken Hill North mine in 1905, and was there a success. His plant and methods have undergone many changes, and he is now using a small quantity of oil to enhance the extraction. He first washes the tailing free from slime, and then adds a small amount of oil to the clean sand, with agitation, and separates the scum or film of mineral sulphides in a spitzkasten. A new mill having a capacity of 1,600 tons per day was started in 1910 on the dumps from the Block 10 mine, combined with the current slime-free tailing of the North and South mines. This is the largest flotation-concentration plant. The venture was brought out as the Amalgamated Zinc (De Bavay's) Ltd., which corporation also owned the exclusive right to use this process at Broken Hill, the patent rights for the rest of the world being retained by the De Bavay Treatment Co. These companies have not published any comprehensible statements of cost and treatment, and little is known about the methods they use.

GILLIES.

In 1906, James H. Gillies' patents were applied on a commercial scale at the Block 10 mine, Broken Hill, N.S.W. Gillies' apparatus seems to be unique; his processes were based on the principles of Potter and Delprat, but later he made use of the principles described in the Minerals Separation patents. The plant was a failure economically, and has been abandoned.

MACQUISTEN.

Arthur P. S. Macquisten, in 1904, invented a process and a tube apparatus therefor which made use of the surface tension of liquids for separating minerals, whereby some floated and others sank. His apparatus is new and important, but works on the old and well known principle of surface tension. In 1906 this was applied on a working scale in the Adelaide Reduction Works, at Golconda, Nevada. The process, like all the flotation processes except the Minerals Separation and Potter-Delprat, has

difficulty in handling slime.* The plant consists of 100 tubes, and the capacity is 125 tons per day. The latest development of this idea is the introduction of oil to the process, thus bringing it pretty much on a par with all the others as to the principles involved.

In 1911, the Federal Mining & Smelting Co. installed 119 of these tubes at the Morning mill at Mullen, Idaho, for the treatment of a middling product containing blende, galena, siderite, and quartz, but the results are not entirely satisfactory. The capacity is about 150 tons per day.

MUREX.

Lockwood & Samuel, in 1908, invented a process for making sulphide particles more magnetic by utilizing the selective action of oil, and in 1909 described a method of increasing the selective action of oil by treating it with various soluble salts; also a process where magnetic or magnetizable substances are added to an ore-pulp, the whole being then treated with an oil to cause the sulphides and the magnetic particles to adhere together, and then removing them from the pulp by means of a magnet. Although this is not a flotation process, it makes use of some of the principles involved, and is in some respects similar. Two units have been installed and are successfully working at Cordoba, in Spain. A plant erected at Broken Hill on the Block 14 mine has, however, had many vicissitudes; it has been closed down as unadapted for the work, and moved recently to the Amalgamated Zinc works.

Plants have been sent to Bolivia to a mine belonging to Aramayo, Francke, & Co., and to the Malines mine in France.

ZINC CORPORATION.

This is a company organized in 1905 to work the accumulation of zinky tailing in the Broken Hill district. The company purchased in all more than 4,000,000 tons of tailing and slime from different mines in the district.

The company did not own any process, but the history of the company has been so closely allied to the development of this branch of the art that it is quite proper to give a brief sketch of it. The company first tried the Potter process. A plant was built in 1905 at the British Broken Hill Proprietary

**Mineral Industry*, Vol. xv., p. 776.

mine, and was intended to have a capacity of 400 tons per day. After extended trials and expensive alterations, the Potter idea was abandoned as not practical.

In 1907 this plant was entirely re-modelled to install the Minerals Separation process. This process had been used for some time satisfactorily on the Central mine near by, but in the Zinc Corporation plant this process was also abandoned as not satisfactory.

Extended trials had been made in the meantime, under the management of D. P. Mitchell, with the new Elmore vacuum-concentration process. These trials had been most successful. It was decided, therefore, to move the scene of operations and build a new mill where better crushing facilities could be provided. This mill was built in 1907 and 1908 near the southern end of the Broken Hill district, and 16 Elmore units were installed. This process was a success, and ran for two years at a handsome profit.

Then, in 1910, owing to improvements in the apparatus for the Minerals Separation process, and owing also to the depletion of supplies of material suitable to the Elmore process, the Minerals Separation process was again adopted. The Elmore units were taken out and the Minerals Separation process has now been operating on both sand and slime at a good profit for nearly two years.

The most recent step in the history of the Zinc Corporation is the amalgamation of that corporation with the Broken Hill South Blocks, Ltd., which gives the combined business, besides the excellent equipment of the Zinc Corporation and the enormous tonnage of purchased tailing, the advantage of the continuous supply of ore from the South Blocks mine.

HYDE.

In 1911 James M. Hyde invented and patented a flotation process in which a small amount of sulphuric acid, with or without the use of copperas (iron sulphate), is used to give the slimy portion of the ore a preliminary coagulation before bringing it to the flotation machine, and in which the sulphides, after agitation, are floated off rapidly and as completely as possible, with a considerable overflow of freely-flowing water, thereby producing an impure concentrate which is re-treated in a second machine, from which only high-grade concentrate is taken off, with no freely-flowing water. The

process has been adopted by the Butte & Superior Copper Company of Butte, Montana, in their new 500-ton zinc mill which is shortly to be increased to a capacity of 1,000 tons per day. The process is giving highly satisfactory results. This is the first attempt to use a flotation process on a large scale in the United States.

The recent amalgamation of the patent interests of the Amalgamated Zinc, Ltd., and the Minerals Separation, Ltd., in Australia, is a step in the right direction, as it will stop litigation already begun, and prevent more that was threatened. The De Bavay patent rights for the rest of the world are now owned by Minerals Separation, Ltd. The patents now included under the one group are those of Froment, Potter, Delprat, Cattermole, Sulman, Picard, Ballot, De Bavay, Goyder, Laughton, Higgins, Greenway, Chapman, Lavers, Nutter, and Hoover.

A much clearer idea of the evolution of the processes can be secured from a summary of the patents in chronological order, which is given in the next chapter. Some repetition will be necessary, but the history of metallurgical devices is largely a recital of alterations and experiments.

CHAPTER II.

PATENTS.

In this analysis the intention is to set forth the flotation patents as they appeared from time to time, from 1860 to 1912, and to paraphrase and explain the meaning of them in language somewhat simpler than the legal phraseology of the patent. As the development of these processes has taken place mainly in Great Britain and the Colonies, the records of the English Patent Office have been followed as to dates, although those of the United States and other countries present some exception to strict chronology.

A careful search of the records of the patent offices of Great Britain and the United States reveals nothing prior to the year 1860 that in any way bears upon the subject of concentration by flotation.

EXPIRED PATENTS.

WILLIAM HAYNES, in British patent No. 488, February 23, 1860, described a process for separating mineral sulphides from the gangue or rocky constituent of an ore by the use of oily, gummy, or bituminous matter. This was not a flotation process, but must be considered the pioneer movement in that direction. The process described in the patent is as follows :

1. The ore is ground to the requisite fineness.
2. An agent, which may be a fat or an oil, alone or in combination with other things, is added to the crushed ore in the proportion of one part of agent to five or nine of ore.
3. The agent and ore are mixed or agitated in a proper machine.
4. Sufficient water, preferably warm, to cover the whole is added to the agitated and mixed mass.
5. The water and mixed mass of ore and agent are passed through a proper triturating machine, by which operation the combined sulphides and agent alone remain in union, while the earthy matter or gangue of the ore sinks to the bottom of the water.

The central idea of this invention is the separation in a triturating machine of sulphides from gangue by means of the selective adhesion of oils for sulphides.

JOHN TUNBRIDGE, in United States patent No. 228,004, Nov. 4, 1879, described a process for recovering finely comminuted metal held in suspension in water by the use of soap or a saponaceous compound. This patent is just nearly enough related to the subject matter of this discussion to be mentioned for the sake of completeness.

HEZEKIAH BRADFORD, in United States patent No. 345,951, June 22, 1885, described a process for separating sulphides from gangue by what is clearly the first well defined surface-tension flotation process.

For the treatment of wet tailing from tables, vanners, and jigs, one method is described, but for the treatment of dry crushed ore it is specified that the dry ore is to be sprinkled on the surface of water with as little concussion as possible, and from this point the treatment is obviously the same as with wet tailing.

In its simplest form the apparatus prescribed takes the tailing, mixed with water from some previous operation, at a point say *b* (Fig. 1), which may be a moving portion of a shaking table. By means of an adjustable lip *b'*, the pulp is transferred to an inclined plane *a*, in passing over which the sulphide particles become exposed to the air, and the force of the surface tension of the




FIG. 1.—Bradford Apparatus.

liquid acting on these sulphide particles causes them to float on the surface of the liquid in the receptacle *D*, while the gangue, which remains wetted throughout the operation, sinks in receptacle *D*, and is removed at *K*. The sulphides, on the other hand,

which are floating at the surface of receptacle *D*, float across the receptacle to the lip *I*, and plunge into the liquid contained in receptacle *L*. The baffles *l* arrest the fall of the sulphides and assist them to become wetted, so that the force of surface tension no longer acts on them, and they sink quietly to the bottom of receptacle *M* and are removed at 20, while the superfluous water passes over the lip *N*.

The central idea of this invention is the separation of sulphides from gangue by flotation of the sulphides at the surface of a freely flowing ore-pulp through the action of the force of surface tension of the liquid.

CARRIE J. EVERSON, in United States patent No. 348,157, Aug. 29, 1885, described a process for separating the sulphides in an ore from the gangue. The patent describes two distinct processes, the first of which is analogous to that of Haynes. The main improvement made by this first Everson process over that of Haynes is the discovery that acids increase the selective adhesion of oils for sulphide particles.

The second method Everson described is a flotation process pure and simple, and is of interest :—

- (1). The oil should desirably be first mixed with the ore.
- (2). Water containing a suitable amount of free acid in quantity ample for the operation to follow is added to the mixed ore and oil.
- (3). Thorough agitation of the mass.
- (4). Removal of the concentrate by flotation and a constant overflow of water from the washing-out vessel.
- (5). The gangue being heavier, the inventor says, than the mixed oil and sulphides, sinks to the bottom of the washing-out vessel and can be removed there.

The central idea of this invention is the separation of sulphides from gangue by flotation of the sulphides at the surface of the liquid in a vessel, this flotation being accomplished through the agency of the forces brought to bear on the ore-pulp by the addition of oil and acid, and by thorough agitation.

EDWARD DODÉ, in British patent No. 14,357, Sept. 11, 1889, described a process that refers to the separation of metallic gold, silver, etc., from other metals by first dissolving them in acid solution and then treating them with oily substances. The patent is just nearly enough related to the subject matter of this discussion to be mentioned for the sake of completeness.

HEBRON & EVERSON, in United States patent No. 471,174, Sept. 1, 1891, described a process wherein they mixed a 'buoy-stock' with the ore. This process is in the main similar to Everson's, and has some remarkable affinities with Bradford's, but there is some radical departure from previous patents.

The essential feature of the invention consists in submitting the ore and the buoy-stock to a rubbing movement so that the particles of buoyant material are pressed into the cavities and pores of the mineral and made to adhere to the rough and irregular surfaces thereof, so that the joined mineral and buoyant material are of less specific gravity than the rock particles of the ore.

CHARLES B. HEBRON, in United States patent No. 474,829, July 22, 1891, describes an improvement to the Hebron & Everson invention, which consists in subjecting the mixed ore and 'buoy-stock' to a vacuum and heat, thus greatly increasing the efficiency of the 'buoy-stock.' This patent is built upon the foregoing one, but emphasizes two important points:

(1). The buoyant material is more advantageously added to the ore hot, in a vacuum, as in that case the buoyant material comes into closer union and is more intimately joined to the metallic or sulphide particles.

(2). After the buoyant material has been mixed with the ore in a vacuum, the ore must be thoroughly aerated by blowing air through the mass.

The prepared ore was then submitted to a flotation treatment, substantially the same as that described in Hebron & Everson, where the addition of air to the operation and effervescence of the liquid are recommended.

EDGAR A. HOCKLEY, in United States patent No. 466,753, Jan. 5, 1892, described an invention whereby particles of metal or mineral may be recovered by flotation aided by the introduction of air.

ALBION M. ROUSE, in United States patent No. 469,599, Feb. 23, 1892, described a method of creating a froth or foam of matter foreign to water and the recovery thereof.

MALECZEK, in New South Wales patent No. 3823, of the year 1892, described a frothing process, wherein as a result of treating the ore with salt solution in hot oil the sulphides were floated to the surface, presumably through the agency of air or other bubbles, and floated as a froth.

JOSEPH WILLIAM SUTTON, in British patent No. 24,144, Dec.

31, 1892, described a process for recovering gold from its solution by means of flotation with oils in an acidified liquor. This patent is just nearly enough related to the subject matter of this discussion to be mentioned for the sake of completeness.

JOSEPH WILLIAM SUTTON, in United States patent No. 521,899, Dec. 28, 1892, duplicated his British patent No. 24,144, Dec. 31, 1892.

HENRY LIVINGSTONE SULMAN, in British patent No. 24,939, Dec. 28, 1893, described a process for preventing the loss of 'float' gold in milling operations, by adding certain substances that cause it to sink by diminishing the surface-tension of the liquid. This patent is just nearly enough related to the subject matter of this discussion to be mentioned for the sake of completeness.

ROBSON & CROWDER, in British patent No. 427, Jan. 8, 1894, described a process for separating sulphides from gangue. This invention made use of the idea that oils have a selective adhesion for sulphides, but it differs from the previous inventions in that no acid and no air was used in the operation.

(1). The crushed ore, if not already in a proper state, was first moistened with water.

(2). The moistened ore was then mixed with a large volume of oil with constant stirring and the continuous addition of oil.

(3). The sulphide particles were thereby floated away over the lip of the vessel by the constant overflow of oil.

This process does not seem to be much of an advance in the art. There have been some recent patents of a similar kind describing processes for separating mixed sulphides, but they are of doubtful utility. As this patent departs from the progressive line of development indicated by previous patents, and also because the line it takes has come to no commercial application, it is not necessary to consider it further, but it is here mentioned for the sake of completeness.

JOHN HENRY MCCOY, in United States patent No. 577,825, Feb. 11, 1895, described an invention for introducing air into a pointed box, for the purpose of separating particles. This is not a flotation process, but is mentioned for the sake of completeness.

UNEXPIRED PATENTS.

FRANCIS EDWARD ELMORE, in British patent No. 21,948, Oct. 18, 1898, described a flotation process that involved the idea of

oil-selection and the idea of oil-buoyancy flotation. He mixed the ore with several times its weight of water, and an equal or several times greater weight of oil in a revolving drum, so constructed and operated as to give a mixing effect without breaking up or emulsifying the oil, which was added with the ore. After thus gently mixing, the mass was allowed to run into a spitzkasten, where the oil carried the sulphides to the surface, and the gangue and water were removed from the bottom. This patent marks a decided advancement in flotation-concentration; it was the first process of the kind to approach commercial success.

FRANCIS EDWARD ELMORE, in United States patent No. 653,340, April 10, 1899, duplicated in the main his apparatus in the British patent just described.

FRANCIS EDWARD ELMORE, in United States patent No. 676,679, April 10, 1899, duplicated his process described in British patent No. 21,948, Oct. 18, 1898.

ALEXANDER STANLEY ELMORE, in British patent No. 6,519, Mar. 28, 1901, described a method of increasing the selective action of oil by adding acid to the pulp.

ALEXANDER STANLEY ELMORE, in United States patent No. 689,070, April 13, 1901, duplicated the process described in British patent No. 6,519, Mar. 28, 1901.

EDMUND L. VAN DER NAILLEN, in United States patent No. 737,533, June 20, 1901, described an apparatus for ore concentration having a horizontal section decreasing in area upward. This patent is of limited interest.

JOHN KLEIN, in United States patent No. 696,739, July 12, 1901, described a machine to which air was introduced for the purpose of carrying a portion of the ore off the top of the liquid and allowing the balance to sink. This is a patent of limited interest in this discussion.

ALEXANDER STANLEY ELMORE, in British patent No. 15,526, July 31, 1901, described two forms of apparatus for conducting the processes previously patented by Francis E. Elmore. One form was designed to effect the separation of sulphides from the gangue by oil-buoyancy flotation, and differs little in principle from the apparatus described by Francis E. Elmore in his original patent. The other form of apparatus described is intended to effect the separation by a sort of oil-amalgamation, in which the oiled pulp flowed under and in contact with an oiled or greased canvas belt, which carried the oil and oiled mineral out of the

pulp. This patent is of interest in that the latter process therein described is extensively used at Kimberley, in South Africa, to separate diamonds from the 'blue ground.'

ALEXANDER STANLEY ELMORE, in United States patent No. 692,643, Aug. 8, 1901, duplicated the apparatus described in British patent No. 6,519, Mar. 28, 1901.

ALEXANDER STANLEY ELMORE, in United States patent No. 703,905, Aug. 8, 1901, duplicated British patent No. 15,526, July 31, 1901.

CHARLES VINCENT POTTER, in United States patent No. 776,145, Jan. 14, 1902, duplicated his British patent No. 1,146, Jan. 15, 1902.

CHARLES VINCENT POTTER, in British patent No. 1,146, Jan. 15, 1902, described a process of mineral flotation wherein the flotation was accomplished in a 1 to 10% acid solution. He added one ton of this solution to one ton of ore, agitated freely, and applied heat. As the temperature of the pulp increased, the heat caused, he says, the sulphides to rise to the surface, from which they were allowed to flow continuously or were skimmed. This patent deserves honourable mention, as it led to the recent decided development in flotation methods. Potter did not mention the use of any gas, but it is clear that he had in view a gas-bubble process.

HAULTAIN & STOVEL, in British patent No. 9,521, April 24, 1902, described a machine of the familiar Frue-vanner type, in which the concentrating belt was made of canvas, and was coated with a layer of thick oil. They thus took advantage of the well known specific gravity separation, and combined with it the principles of oil-selection. They separated the concentrate from the oil in hot water, when the oil, becoming fluid, rose to the surface, and the sulphides remained at the bottom.

CHARLES W. MERRILL, in United States patent No. 728,487, May 12, 1902, described a concentrating apparatus with a horizontal section decreasing upward. This patent is of just sufficient interest to be mentioned for the sake of completeness.

ALCIDE FROMENT, in British patent No. 12,778, June 4, 1902, described a flotation process that involved the use of oil, and also of a gas. He recognized clearly the important principle, which is emphasized in later developments, that when ore, water, oil, acid, and a gas are mixed and agitated together in the proper proportions, the oil not only has a selective action for the sul-

PATENTS.

phides, but the gas also has a selective action for the oiled particles, and it is not necessary to have a large amount of oil present to float the sulphides by oil-buoyancy. He mixed the ore with three times its weight of water, and added a small quantity of oil. If there was no gas-forming mineral in the ore, a little limestone was added, and then also a small quantity of acid, which generated carbon dioxide in the pulp. He then agitated freely. He says the oiled mineral particles collected in spherules and were carried to the surface by the gas bubbles. Finally, he enunciates this important principle: 'The rapidity of the formation of the spherules and their ascension is in direct ratio to the quantity of gas produced in the pulp in a given time.' This patent was taken out only in Great Britain and Italy.

JOSEPH BARTON SCAMMELL, in British patent No. 15,280, July 9, 1902, described a method of thickening oils by the addition of sulphur chloride in order to increase the buoyancy of the oil and so increase the efficiency of the oil-buoyancy flotation processes. He agitated the ore, water, and sulpho-chlorinated oil in a suitable vessel, transferred the mass to settling-pans, and after a time skimmed the oil with the sulphides.

GUILLAUME DANIEL DELPRAT, in British patent No. 26,279, Nov. 28, 1902, described a process of flotation that consisted in immersing the ore in a hot but not boiling solution (of specific gravity 1.4) of salt-cake, or a solution (of specific gravity 1.4) of sodium sulphate and sulphuric acid. The ratio of sodium sulphate to sulphuric acid was 2.5 : 1. The sulphides in the ore, he says, floated at the surface and were removed by a stream of water or by skimming.

ARTHUR EDWARD CATTERMOLÉ, in British patent No. 26,295, Nov. 28, 1902, described a process of oil-concentration in which he made use of the idea of oil-selection. His method of procedure is not made plain in his patent, but seems to be about as follows: To a freely flowing pulp he added from 4 to 6% of oil, and 2% of soap, the amount depending on the metallic contents of the ore, his object being to produce granules of sulphides of a certain size. For slimy ores he added a portion of coarser sulphide particles to serve as nuclei for the formation of granules, and effected the separation by an upcast current of water, taking the gangue off the top, and the granules at the bottom. For ores containing small amounts of mineral he added a portion of oiled pumice or oiled charcoal to serve as nuclei and removed the granules so made

by flotation. After the concentrate had been secured, the oil was recovered by treating the oiled sulphides with an alkali, thus dissolving the oil and making it available for use again.

ARTHUR EDWARD CATTERMOLÉ, in British patent No. 26,296, Nov. 28, 1902, described a process of classifying mixed sulphides after they had been removed from an ore by his oil-granules concentration process. He accomplished this classification of sulphides by fractionally dissolving the oil of the granules in alkaline emulsifying agents of varying strength and activity. He first added to the oiled concentrate, with agitation, an alkaline solution that had a strength just sufficient to dissolve the oil from the sulphides having the least adhesiveness for the oil. This sulphide of least adhesiveness for oil was freed from the mixed sulphide granules, and was removed by an upcast of water or other suitable device. An alkaline solution of greater strength was then added to the remaining portion, with agitation, and the oil was dissolved from the sulphide having the next second adhesiveness for oil. This second sulphide was released in the same way as the first; and so the process was repeated as often as was necessary.

GUILLAUME DANIEL DELPRAT, in United States patent No. 735,071, Jan. 2, 1903, described a process whereby flotation of sulphides is secured in a nitric acid solution.

GUILLAUME DANIEL DELPRAT, in United States patent No. 768,035, Jan. 2, 1903, duplicated British patent No. 26,279, Nov. 28, 1902.

ALEXANDER STANLEY ELMORE, in British patent No. 184, Jan. 3, 1903, described an improved apparatus for oil-concentration wherein air was excluded from the operation. His method was substantially the same as that described in his previous patent, and that of Francis E. Elmore, except that by sealing all open vessels with a ring or surface of oil, the operation was performed in such a manner as to prevent the introduction of air into the pulp and thus prevent the possibility of oxidation of the minerals. He also describes two methods of removing the concentrate from the oil, one by heat and one by filter-press treatment. He calls attention to the necessity of cooling the oil after heating, presumably for the purpose of maintaining its viscosity and to prevent emulsification.

JOSEPH BARTON SCAMMELL, in United States patent No. 770,659 Jan. 31, 1903, duplicated his British patent No. 15,280, July 9, 1902.

GUILLAUME DANIEL DELPRAT, in United States patent No. 763,662, Mar. 9, 1903, described a new form of apparatus for the application of his processes described in United States patents Nos. 735,071 and 768,035, Jan. 2, 1903.

HENRY A. ALLEN, in United States patent No. 762,870, Mar. 16, 1903, described a complicated apparatus for treating ores with oil and other chemicals under super-atmospheric pressure.

JACOB DAVID WOLF, in United States patent No. 787,814, May 22, 1903, duplicated British patent No. 4,793, May 22, 1903.

JACOB DAVID WOLF, in British patent No. 4,793, May 22, 1903, described a method of applying the principles of oil flotation. He used sulpho-chlorinated oil, with violent agitation in a mixer like Fig. 2, and aimed to secure a high degree of mineral extraction with a low grade of concentrate in the first step, and by washing the concentrate with hot water in a suitable vessel




FIG. 2.—Wolf Apparatus.

to increase the grade of concentrate in the second step; as a third step in his process, air or steam was blown into the refuse, which raised to the surface globules of lost oil, with some sulphides adhering thereto, thus increasing the extraction.

COSMO KENDALL, in United States patent No. 771,075, July 21, 1903, described a process of separating graphite from gangue by means of oil.

GOYDER & LAUGHTON, in British patent No. 16,839, July 31, 1903, described a process of ore concentration that employed the idea of adding the ore to an acid solution. They describe an apparatus for trapping the mineral sulphides as they are brought to the surface. They were the first to disclose the principle governing Potter's and Delprat's acid-flotation processes, namely, that the action of the acid on the ore generated gas-bubbles to which the sulphide particles attached themselves and were floated to the surface. One of the difficulties of the acid-flotation process

was that the bubbles broke on reaching the surface, and the mineral particles sank again, that is, the surface tension was not active enough to hold them up. This invention not only seeks to obviate this bad feature of the acid-flotation process, but in a measure takes advantage of it. This machine has horizontal




FIG. 3.




FIG. 4.—Goyder and Laughton Apparatus.

sections decreasing in area upward.

GOYDER & LAUGHTON, in United States patents No. 763,749 and 784,999, Aug. 5, 1903, described an improved form of apparatus and process for the application of the acid-flotation process of Potter, being a duplicate of British patent No. 16,839, July 31, 1903.

CATTERMOLE, SULMAN & PICARD, in British patent No. 17,109, Aug. 6, 1903, described a process of concentration that consisted (1) in mixing the freely flowing pulp with a soap solution and agitating; (2) adding a small portion of acid to liberate the fatty acid from the soap, whereby the sulphides collected in granules, as disclosed previously by Cattermole, and were removed from the pulp by an upcast current of water; and (3) generating a gas in the pulp to remove the granules by flotation. After the concentrate was removed it was treated with an alkali, which dissolved the oil of the granules, converting it into a soluble soap, which was immediately available for use again.

MORITZ F. R. GLOGNER, in United States patent No. 736,381, Aug. 18, 1903, described a process for the recovery of graphite, by means of an oil and froth process.

JACOB DAVID WOLF, in New South Wales patent No. 13,571, Aug. 19, 1903, duplicated his British patent No. 4,793 of May 22, 1903.

VAN METER & BOSS, in United States patent No. 762,774, Aug. 19, 1903, described an apparatus for the application of the oil-buoyancy process.

ALFRED SCHWARZ, in United States patent No. 766,289, Aug. 19, 1903, described a process for separating sulphides from gangue by the use of oil and saline solutions or other liquids differing in specific gravity. His apparatus is different from any previously described, and he gives a theory for his process which it is difficult to accept.

ARTHUR EDWARD CATTERMOLLE, in British patent No. 18,589, Aug. 28, 1903, secured a revision and amplification of his previous patents, and described the formation of granules. He describes an improved form of apparatus. This process failed of practical application.

HOMER L. ORR, in United States patent No. 758, 464, Sept. 1, 1903, described an apparatus for separating metallic particles in an ore by means of oil and other chemicals.

GUILLAUME DANIEL DELPRAT, in British patent No. 19,783, Sept. 14, 1903, described a flotation process wherein the bisulphate of an alkali metal is used.

SULMAN & PICARD, in British patent No. 20,419, Sept. 22, 1903, described a process of oil-concentration in which they introduced bubbles of air or other gas, and also oil in the form of a spray, into the freely flowing acidulated pulp. This invention follows some of their previous patents in its main lines, but is novel in the methods of introducing the oil and air into the slightly oiled pulp.

SULMAN & PICARD, in New South Wales patent No. 13,632, Sept. 24, 1903, described a process consisting in the recovery of metallic particles in an ore by floating them to the surface with bubbles and films of air after oiling them with a small amount of oil in an acid circuit.

ARTHUR EDWARD CATTERMOLLE, in United States patent No. 763,260, Sept. 28, 1903, duplicated British patent No. 26,295, Nov. 28, 1902.

ARTHUR EDWARD CATTERMOLLE, in United States patent No. 777,273, Sept. 28, 1903, duplicated British patent No. 18,589, Aug. 28, 1903.

ARTHUR EDWARD CATTERMOLÉ, in United States patent No. 763,259, Sept. 29, 1903, duplicated British patent No. 26,296, Nov. 2, 1902.

SULMAN & PICARD, in United States patent No. 793,808, Oct. 5, 1903, duplicated British patent No. 20,419, Sept. 22, 1903.

ALICE H. SCHWARZ, in United States patent No. 771,277, Nov. 6, 1903, described a process of ore concentration in which she made use of an oil or grease that is solid at ordinary temperatures.

ISRAEL F. GOOD, in United States patent No. 745,960, Dec. 1, 1903, described an oil-flotation method of recovering graphite from rock.

GUILLAUME DANIEL DELPRAT, in British patent No. 27,132, Dec. 11, 1903, described the use of a solution of common salt and sulphuric acid to be used in the acid-flotation processes previously disclosed by him.

ALEXANDER STANLEY ELMORE, in United States patent No. 865,334, Dec. 11, 1903, duplicated British patent No. 184, Jan. 3, 1903.

EDMUND B. KIRBY, in United States patent No. 809,959, Dec. 14, 1903, described a process of oil-and-gas flotation, in which air was blown into the previously agitated oiled pulp.

CATTERMOLÉ, SULMAN, & PICARD, in United States patent No. 788,247, Mar. 29, 1904, duplicated British patent No. 17,019, August 6, 1903, in part.

CATTERMOLÉ, SULMAN, & PICARD, in United States patent No. 777,274, Mar. 29, 1904, duplicated in part British patent No. 17,109.

JAMES D. DARLING, in United States patent No. 763,859, April 28, 1904, described a method of separating carbon from impurities by means of oil.

SULMAN & PICARD, in British patent No. 13,481, June 14, 1904, described a method of slime-deposition by means of soap, which produces coagulation. This is of limited interest to this discussion.

FRANCIS EDWARD ELMORE, in British patent No. 13,578, June 15, 1904, described a process of flotation wherein he made use of the electrolysis of water to generate gas in a freely flowing pulp. This patent is chiefly of interest in that it marks the departure of this inventor from his old line of oil-buoyancy flotation, emphasized in his former patents, and he thenceforth turns his attention to gas-and-oil flotation.

JACOB DAVID WOLF, in British patent No. 17,407, Aug. 10,

1904, described an apparatus similar to that of Haultain & Stovel.

FRANCIS EDWARD ELMORE, in British patent No. 17,816, Aug. 16, 1904, described a process to be performed in a vacuum or a partial vacuum. He says he uses a small quantity of oil, and also says that "under a vacuum or partial vacuum, air or gases dissolved in the milling water are liberated. These liberated gases may be augmented by the generation of gases in the pulp, or by introduction from an external source." The apparatus is an admirable invention, and the patent discloses a new principle, namely, the use of the vacuum in connection with the flotation.

AUGUSTE JOSEPH FRANCOIS DE BAVAY, in British patent No. 18,660, Aug. 29, 1904, described a flotation process in which a thin film of freely flowing pulp was brought on to the surface of a vessel of water, where advantage was taken of the surface tension of the liquid, and the sulphide floated. He further points out that if the surface of the sulphide particles is coated with a film of carbonate from weathering, this is detrimental to the process, and should be removed by (1) soaking the ore in a weak solution of carbonate of ammonia, or (2) passing carbonic gas through the pulverised wet ore, or (3) by friction.

JAMES HYNDES GILLIES, in United States patent No. 778,747, Sept. 7, 1904, duplicated British patent No. 20,159, Sept. 19, 1904

JAMES HYNDES GILLIES, in United States patent No. 780,281, Sept. 8, 1904, duplicated British patent No. 20,160, Sept. 19, 1904.

JAMES HYNDES GILLIES, in British patent No. 20,159 and No. 20,160, Sept. 19, 1904, described an apparatus to be used in conducting the Potter and Delprat processes.

SULMAN & PICARD, in Commonwealth patent No. 1,909, Oct. 27, 1904, duplicated their N.S.W. patent, No. 13,632.

ALFRED SCHWARZ, in British patent No. 23,906, Nov. 4, 1904, described a process of concentration wherein he added to a dry or slightly wet pulp a portion of fat, oil, or resinous substance, which was solid at ordinary temperature. After several complicated manipulations, the oil and mineral were separated from the gangue by flotation. This is a duplicate of United States patent No. 771,277, Oct. 7, 1904, by Alice H. Schwarz.

ARTHUR PENRHYN STANLEY MACQUISTEN, in British patents No. 25,204 and No. 25,204 A, Nov. 19, 1904, described a process and apparatus therefor, making use of the surface tension of

liquids for separating minerals, whereby some floated and others sank. His apparatus is new and important, but works on the old and well known principle of surface tension.

AUGUSTE JOSEPH FRANCOIS DE BAVAY, in British patent No. 25,858, Nov. 28, 1904, described an apparatus for mineral separation by the process described in his patent of Aug. 29, 1904, previously mentioned.

AUGUSTE JOSEPH FRANCOIS DE BAVAY, in United States patent No. 864,597, Dec. 19, 1904, duplicated British patent No. 18,660, Aug. 29, 1904.

AUGUSTE JOSEPH FRANCOIS DE BAVAY, in United States patent No. 912,783, Dec. 19, 1904, described an apparatus for performing processes at pressures above normal.

SULMAN, PICARD, & BALLOT, in British patent No. 29,374, Dec. 31, 1904, described a process and apparatus therefor wherein they made use of the idea of oil-and-gas flotation combined with surface tension. A mineral particle coated with a film of oil not only adheres to a small bubble of air or other gas introduced into the pulp and floats with the bubble, but all oiled particles that are exposed to the air above the surface of the pulp take unto themselves films of air of much larger dimensions than if un-oiled, and so float more readily than un-oiled particles.

FRANCIS EDWARD ELMORE, in British patent No. 29,282, Dec. 31, 1904, described an apparatus to perform the operation described in his vacuum-process patent.

SULMAN & PICARD, in British patent No. 1,821, Jan. 30, 1905, described a process that depends on the surface tension of the liquid.

SULMAN, PICARD, & BALLOT, in United States patent No. 879,985, Feb. 2, 1905, duplicated British patent No. 29,374, Dec. 31, 1904.

WALTER MURRAY SANDERS, in United States patent No. 805,382, Feb. 7, 1905, described a method of gas-flotation in which he used alkaline solutions to generate bubbles of hydrogen gas on the minerals.

SULMAN, PICARD, & BALLOT, in British patent No. 5,260, Mar. 13, 1905, described a process of flotation in which they revert to surface tension as applied to dry ores. In the simplest method described by them they sprinkle the dry ore on the surface of the liquid in a spitzkasten. The sulphides being more difficult to wet, or rather, adhering more strongly to their air-films than the gangue, floated, and the gangue sank.

ALEXANDER STANLEY ELMORE, in British patent No. 5,953, Mar. 21, 1905, described a method of using calcium chloride and other chlorides in flotation-concentration.

SULMAN, PICARD, & BALLOT, in British patent No. 7,803, April 12, 1905, described a process of flotation in which they added extremely small amounts of oil, less than 0.1%, to a freely flowing pulp, and gave it violent agitation for from 1 to 10 minutes.

CYRIL DOUGLAS MCCOURT, in British patent No. 10,475, May 18, 1905, described a process for concentrating graphite and other non-metallic substances by means of oil-flotation. No new principle is disclosed herein, but previously patented processes are put to a new use.

SULMAN, PICARD, & BALLOT, in United States patent No. 835,120, May 29, 1905, duplicated British patent No. 7,803, April 12, 1905.

SULMAN, PICARD, & BALLOT, in United States patent No. 835,479, May 29, 1905, duplicated British patent No. 26,712, Dec. 21, 1905.

HENRY LIVINGSTONE SULMAN, in Commonwealth patent No. 4,667, June 6, 1905, duplicated his invention in British patent No. 19,709, Sept. 25, 1905.

ARTHUR PENRHYN STANLEY MACQUISTEN, in United States patent No. 865,194, July 3, 1905, duplicated British patent No. 25,204, Nov. 19, 1904.

FRANCIS EDWARD ELMORE, in United States patent No. 826,411, July 10, 1905, duplicated his process in British patent No. 17,816, Aug. 16, 1904.

ALFRED SCHWARZ, in United States patent No. 825,080, July 12, 1905, described an improved form of apparatus for use in his processes previously described.

ALFRED SCHWARZ, in United States patent No. 842,255, July 19, 1905, duplicated British patent No. 23,906, Nov. 4, 1904.

ARTHUR PENRHYN STANLEY MACQUISTEN, in British patent No. 15,119, July 22, 1905, described an improvement to his surface-tension process, in which he made use of oil and various salts and acids.

HENRY LIVINGSTONE SULMAN, in British patent No. 19,709, Sept. 29, 1905, described an improvement upon the previous oil-and-gas process; this consisted in bringing the contents of the agitating-vessel to a boiling temperature.

JACOB DAVID WOLF, in British patent No. 20,322, Oct. 7, 1905, described an improvement to his greased-belt apparatus.

HENRY LIVINGSTONE SULMAN, in United States patent No. 835,143, Oct. 20, 1905, duplicated British patent No. 19,709, Sept. 29, 1905.

SULMAN, PICARD, & BALLOT, in British patent No. 26,711, Dec. 21, 1905, described a process for separating heavy sulphides from each other. They begin with the known fact that in a pulp containing mixed sulphides in a sunken condition, if the sulphides are raised above the surface and allowed to drain, the sulphides take unto themselves films of air, and upon again seeking to immerse the drained pulp, the sulphides float; and they discovered also that the time required for drainage and taking on of air-films varied in the different sulphides. By taking advantage of these drainage periods of different lengths they could effect a separation of the sulphides from each other. This is a novel conception, but the practical application of it has been a failure.

SULMAN, PICARD, & BALLOT, in British patent No. 26,712, Dec. 21, 1905, described a method of applying oil-and-gas flotation. This consisted in subjecting a freely flowing oiled pulp to pressure for the purpose of dissolving air or other gas therein, and when the pressure on the pulp was removed the air immediately escaped from solution and collected the oiled minerals and floated them; also the introduction of highly aerated water with the pulp for the same purpose. They make use herein of facts well known in physics under the name of Henry and Dalton's law, namely, the quantity of gas dissolved in water is in direct proportion to the pressure.

SULMAN, PICARD, & BALLOT, in Commonwealth patent No. 5,150, Jan. 31, 1906, duplicated British patent No. 26,712, 1905.

SULMAN, PICARD, & BALLOT, in Commonwealth patent No. 5,334, Feb. 26, 1906, duplicated British patent No. 26,711, 1905.

ARTHUR PENRHYN STANLEY MACQUISTEN, in United States patent No. 865,195, Mar. 17, 1906, duplicated British patent No. 25,204A, Nov. 19, 1904.

JAMES FRANCIS LATIMER, in United States patent No. 851,600, Mar. 27, 1906, described flotation processes as applied to graphite concentration.

SULMAN & SULMAN, in British patent No. 9,981, April 28, 1906, described the adaptation of the buddle and rubber strakes to flotation processes, whereby the particles are exposed to the air advantageously.

AUGUSTE JOSEPH FRANCOIS DE BAVAY, in Commonwealth patent No. 6,239, June 21, 1906, described a flotation process where a fluoride or a carbonate is added to the acid pulp.

GEORGE ALBERT CHAPMAN, in British patent No. 17,328, Aug. 1, 1906, described an improvement to Sulman's previous patents. This is a method of limiting the amount of acid used in flotation. While it is advantageous to have some acid in the pulp to increase the selective action of the oil, it is not necessary to maintain the acidity of the whole mass for more than a short time; the operation can be carried on in a neutral circuit if the acid is added before the oil. This is a working detail of considerable importance.

HENRY LIVINGSTONE SULMAN, in British patent No. 19,944, Sept. 7, 1906, described a process in which the separation of minerals was brought about by the repeated exposure of the particles to the air, and by warming the liquid in which the operation was performed.

WALTER MURRAY SANDERS, in United States patent No. 988,737, Oct. 27, 1906, patented a non-acid process of flotation-concentration.

DUDLEY HIRAM NORRIS, in United States patent No. 864,856, Nov. 19, 1906, described a method of effecting a separation of minerals by flotation by adding to a freely flowing pulp a portion of water in which air was dissolved at high pressure. His apparatus is new.

WALTER MURRAY SANDERS, in United States patent No. 911,077, Mar. 27, 1907, described an apparatus for performing flotation processes.

HOOVER & SULMAN, in British patent No. 13,268, June 7, 1907, described an apparatus for performing the high-pressure operation previously described by Sulman, Picard, & Ballot.

DUDLEY HIRAM NORRIS, in amended British patent No. 14,806, June 27, 1907, duplicated his United States patent No. 864,856, 1906, with modifications.

MARCUS RUTHENBURG, in British patent No. 28,191, Dec. 21, 1907, described a method of separating mixed sulphides by using a light oil instead of water, in ordinary table or vanner concentration.

LOCKWOOD & SAMUEL, in British patent No. 12,962, June 17, 1908, patented a process for making sulphide particles more magnetic by utilizing the selective action of oil.

FRANK BURNETT DICK, in British patent No. 16,667, Aug. 7, 1908, described a process for treating copper ores by an oil-and-gas flotation process, where the ore is given a preliminary preparation by a reducing roast.

LOCKWOOD & SAMUEL, in British patent No. 26,264, Dec. 4, 1908, described a method of increasing the selective action of oil by treating it with various salts.

ARTHUR HOWARD HIGGINS, in British patent No. 26,852, Dec. 10, 1908, described a flotation process in which the frothing agents are aromatic hydroxides such as phenol.

SULMAN, PICARD, & BALLOT, in British patent No. 28,173, Dec. 24, 1908, described a method of securing flotation by the use of soluble frothing agents of the alcohol series.

HENRY AZOR WENTWORTH, in United States patent No. 938,732, Jan. 2, 1909, described a process of separating sulphides from each other where the sulphides were submitted to a slight roast for the purpose of rendering one or more of the sulphides non-floatable.

LOCKWOOD & SAMUEL, in British patent No. 16,229, Jan. 7, 1909, described a process wherein magnetic or magnetizable substances are added to an ore-pulp, the whole then treated with an oil to cause the sulphides and the magnetic particles to adhere together, and then removing them from the pulp in a magnetic machine.

LOCKWOOD & SAMUEL, in United States patent No. 933,717, Jan. 11, 1909, duplicate in part British patent No. 12,962, June 17, 1908,

EDWARD JAMES HORWOOD, in Commonwealth patent No. 12,763, Jan. 13, 1909, described a process for separating zinc sulphide from lead sulphide by flotation, after first giving the concentrate a slight roast.

EDWARD JAMES HORWOOD, in amended British patent No. 1,789, Jan. 25, 1909, duplicated his Commonwealth patent No. 12,763, Jan. 13, 1909.

GREENWAY, SULMAN, AND HIGGINS, in amended British patent No. 2,359, Feb. 1, 1909, described a process of flotation-concentration accelerated by the use of soluble frothing agents.

THEODORE JESSE HOOVER, in British patent No. 4,911, Feb. 27, 1909, described an apparatus for applying the frothing process. This is probably the most important mechanical development in the whole series, and together with its later improvements crystallizes the commercial application of the flotation method.

GREENWAY, SULMAN, & HIGGINS, in United States patent No. 962,678, April 30, 1909, duplicated British patent No. 2,359, Feb. 1, 1909.

FRANK WYNNE, in British patent No. 12,266, May 25, 1909, described an oil-belt apparatus.

JACOB DAVID WOLF, in British patent No. 15,469, July 2, 1909, described an improvement to his previous inventions.

SULMAN & PICARD, in British patent No. 26,019, Nov. 10, 1909, described a flotation treatment for oxidized ores.

ALFRED ARTHUR LOCKWOOD, in United States patent, No. 956,773, Nov. 15, 1909, duplicated British patent No. 26,264, Dec. 4, 1908.

SULMAN, HIGGINS, & BALLOT, in British patent No. 28,933, Dec. 10, 1909, described a flotation process where turpentine is the agent.

FRANK BURNETT DICK, in British patent No. 2,500, Feb. 1, 1910, described an improvement to his invention for the treatment of copper ores described in his British patent No. 16,667 of 1908.

HENRY AZOR WENTWORTH, in United States patent No. 980,035, March 11, 1910, described a process of differential separation of mixed sulphides.

THEODORE JESSE HOOVER, in British patent No. 6,896, Mar. 18, 1910, described a form of apparatus for flotation processes, being an improvement on British patent 4,911 of 1909.

SULMAN & PICARD, in British patent No. 8,650, April 9, 1910, described a process of preparing ores for flotation treatment, which consists in submitting them to a reducing roast.

THEODORE JESSE HOOVER, in British patent No. 10,929, May 3, 1910, described a form of apparatus for flotation processes; a further improvement on British patent 4,911 of 1909.

ALFRED ARTHUR LOCKWOOD, in British patent No. 13,009, May 28, 1910, described a new magnetic flotation method.

GREENWAY, SULMAN, & HIGGINS, in United States patent, No. 962,678, June 28, 1910, duplicated British patent No. 2,359, Feb. 1, 1909.

THEODORE JESSE HOOVER, in United States patent No. 979,857, July 14, 1910, duplicated British patent No. 6,896, Mar. 18, 1910.

JAMES M. HYDE, in United States patent No. 1,022,085, April 2, 1912, described an apparatus and flotation process where the acid required is added at some time and distance

prior to the act of flotation; the patent contains the first description of an ingenious method of making high grade concentrates and high recovery simultaneously.

CHAPTER III.

LITIGATION.

In the previous chapter 140 patents were summarized, but out of them it would not be possible to cull 140 new ideas. Besides the dearth of ideas, the question of priority and the fact of diffuse ownership were bound to give rise to a complicated mass of litigation.

The patent law has been one of the greatest accelerating factors in our modern civilization, because it has offered an adequate potential reward to individual effort. When inventions were few and widely differentiated, Governments were able to give adequate protection to the inventive class, there being in the nature of things little interference or clash of interests. However, after a hundred years of highly accelerated development, we have arrived at a point where it is obvious that either the patent idea or its method of operation has completely broken down. The historical situation is changed for another reason, namely, a patentee has to protect himself not only in his own country, but all over the world, and to conduct independent law-suits in each country.

Men nowadays work conscientiously and expend their energy in the development of ideas, only to learn later that these have already been the subject of patents, and that no new patent will be granted. The man who does this can attribute a part of his misfortune to his own fault, for the law presumes he has knowledge of precedent inventions. The individual who has received letters patent on an idea, however, and later finds that this brings him no reward when the matter is adjudicated in the courts, certainly deserves sympathy. He is in an entirely different position from the first man; the Government has passed his invention as patentable, and if later the courts deprive him of the benefits definitely promised, someone has blundered. Every legal case in which the patents of one litigant are declared invalid is an indictment of the most serious nature against the system. Leaving out of account the victims of patent 'pirates'—unfortunately a

large class—there are numerous well-intentioned people who have been deceived as to the value of the contract and covenant issued by the Government purporting to guarantee to them, their heirs and assigns, certain definite benefits and profits. The industrial world is alive to this breakdown, and a discussion of remedies has occupied the attention of serious reformers. The captains of industry have met this *impasse* in a measure by suppressed knowledge and secrecy in the arts. No better exposition of the iniquity of such secrecy can be made than that of James Douglas in the 'Transactions of the American Institute of Mining Engineers,' Vol. xxxix., 1907. This paper is so able, and deals with a subject of such wide economic interest, that it deserves much wider circulation than it has had. The suppression of knowledge and secrecy in the arts is grossly contrary to the public weal, and deteriorating to the individual. It threatens to stifle industrial development, because the incentive of the potential reward, to a large extent, is withdrawn. Sooner or later Governments must undertake to make their guarantees good. They must make the letters patent a contract as inviolable as the simple language on the face of it now would lead a sensible man to believe. The amount of money spent in patent litigation (including the expenses of the courts), and in the patent office of either the United States or Great Britain, is a heavy tax on industry, and it yields no economic result. The men who are most competent to judge in these cases are not called until the matter is before the courts, technical and scientific men of ability and training generally being conspicuous by their absence. The patent commissioner, or chief, is generally a politician, whose chief ambition is to draw his salary with a minimum of effort. Examination by the patent office should be thoroughly scientific. As no expert examiner has perfect knowledge, the specification, as determined by the official examiner, before final sealing should be published in the recognized technical press covering the particular subject of the patent, announcing that unless valid objections are submitted within six months the patent shall hold good from the date of publication, and be a perfect protection against any possibility of the patent ever being the subject of a law-suit. This would fix 'knowledge at the time,' and prevent professional unearthing of old and abandoned ideas.

DECIDED CASES.

All the legal cases that in any way bear on the validity or

ownership of this complex and tangled series of patents are here summarized :

ELMORE v. VAN METER.—The Elmore company, in 1902, opposed the granting of patents to Van Meter in Peru, but, after a hearing, the patents were granted. A compromise was subsequently effected between these two interests, by which the Van Meter patents were absorbed by Elmore.

SULMAN & PICARD v. WOLF.—Decision given in May, 1905. This was an action brought in the Chancery division of the English courts, before Mr. Justice Buckley, by Sulman & Picard, metallurgical chemists, against Wolf, inventor of a flotation process, for fees that Sulman & Picard claimed were due for work done on Wolf's process. Wolf counter-claimed that Sulman & Picard had violated their contract with him in that, being employed by him to investigate his process, they used the information obtained thereby, and took out patents in respect to certain discoveries that they made for him, and which they ought to have handed over to him. The counter-claim stated that this claim was unwarranted for the reason that Sulman & Picard had notified Wolf before he employed them that they were interested professionally and commercially in another similar oil process belonging to Minerals Separation, Ltd. They informed him that, in view of their opinion that this new process would prove superior to Wolf's, they did not feel justified in accepting fees from him, and suggested he retain the services of someone else to conduct his trials. Nevertheless, Wolf entered into an agreement whereby Sulman & Picard were, among other things, to give him the benefit of all discoveries made in the course of their investigation of his process. The learned judge held that they had fulfilled every undertaking of the contract, and in the course of his judgment construed the meaning of various oil patents submitted to him as follows :

The Elmore process was for treating crushed ore by mixing with water and oil, so that the gangue shall become loaded with water and shall sink, and the sulphides shall become engaged by the oil, and shall float as by little rafts of oil. The process in which Wolf was interested was a process of the Elmore type, and was the subject of a patent by Scammell. Scammell's improvement on the Elmore process consisted in increasing the viscosity and cohesion by treating the oil with sulphur chloride. As a result of the investigation of this Elmore-Scammell process by Sulman & Picard, Wolf ultimately took out a patent for a process

that was of the Elmore-Scammell type, with this improvement : that after the oil had rafted off the sulphides, air was blown through the tailing to recover the oil that had been lost in the tailing. The other process that Sulman & Picard were investigating was different altogether. In this process, belonging to the Minerals Separation, Ltd., a very small quantity of oil was used, the original object being not to float the sulphides, but to collect the sulphides together in the form of granules and make them sink, adding just enough oil to act as a cement for the granules. Later this process was improved by the Minerals Separation, Ltd., in such a way that by introducing air into the pulp the granules could be made to float by the attached air-bubbles. This was not flotation by oil, but flotation by air. The only point of resemblance between the Elmore-Scammell-Wolf process and the process of Minerals Separation, Ltd., was that they both used a jet ; but the object of the jet in Wolf's case was to recover lost oil, while in the other case it was used to make the sulphides float, and so recover them. The learned judge, therefore, held that Sulman & Picard had discharged every obligation faithfully, and that Wolf must pay the fees agreed upon.

DE BAVAY *v.* MACQUISTEN. Decision delivered in Jan., 1907. Macquisten applied for a patent in Australia for his process, which involved the use of the surface tension of water applied in a slowly revolving tube. De Bavay opposed the granting of this patent, but, after hearing the evidence of both parties, the Commissioner decided that Macquisten was entitled to his patent.

POTTER *v.* THE BROKEN HILL PROPRIETARY COMPANY. Decision delivered in February, 1907. This was an action brought in Australia by Charles V. Potter, inventor of an acid-flotation process, against the Proprietary company for infringement by the use of the Delprat process. Delprat pleaded that Potter's patent was invalid because :

- (1) It will not do as much as it professes to do with any sulphide ores.
- (2) That with some sulphide ores it will not work at all.
- (3) That with many sulphide ores it will not work with any result that could be useful.
- (4) That it will not work with the class of ore mentioned in the specification.
- (5) That it will not work with slime.
- (6) That although the patentee says that any acid may be

used, some acids will not be operative, and an acid that will be operative on one ore will not be operative on another.

Much detailed evidence was presented to the Court on these points, and Mr Justice à Beckett decided that Potter's patent was invalid for want of utility, for the following reasons :

"(a) That with many ores no such separation can be effected, although partial separation can be effected.

"(b) That in many instances in which high percentages of separation have been obtained in flotation of sulphides a large percentage of gangue has been floated with the sulphides.

"(c) That some ores are not amenable to the process under any condition.

"(d) That in cases in which only part of the sulphides are floated no reason can be assigned for the other part of the sulphides failing to float, and no repetition or variation of the process will make this part float.

"(e) That no assay or examination of a particular ore will enable an operator to discover whether with that ore the process will be successful wholly or partially, or will fail altogether."

On the other hand, the court held that the Delprat process would have been an infringement if Potter's patent had not been invalid by reason of having been badly drawn up. There was no question but that Potter had a novel idea.

This unsatisfactory decision was at once appealed to the High Court of Australia, but before the High Court was called upon to revise the findings of Mr. Justice à Beckett, a compromise was effected as follows :—

(1) Potter granted to the Proprietary company the right to use free his process in Australia.

(2) The Proprietary company assigned to Potter all the Delprat patents in Australia.

(3) The Proprietary company paid Potter £10,000 in cash.

(4) Each party paid its own costs.

In view of the compromise it would seem that the defendants had little confidence in Mr. Justice à Beckett's decision.

ORE CONCENTRATION COMPANY, LTD., *v.* WEBSTER AND OTHERS. Decision rendered in October, 1908. This was a suit brought in the King's Bench division of the English courts before Mr. Justice Darling by the owners of the Elmore process against Webster and others for damages for non-fulfilment of contract. The Elmore company and Webster *et al.* had entered into a

contract some years before, wherein Webster *et al.* were given an option on the rights of the old Elmore process for Australia at a fixed price, and were to be allowed to inspect and investigate the Elmore process previous to exercising the option. Among other clauses in the option was one providing that any patents for improvements in oil-concentration acquired in any way by Webster and associates should become the property of the Elmore company, and be treated for the purpose of the option as if they were the original patents. After investigating the Elmore process for some time, Webster and associates come to the conclusion it was not what they wanted and they allowed their option to expire, and so waived all their rights and lost the payments they had already made. Some time later, A. E. Cattermole brought on the market his oil process, and after offering to sell the patent rights to the Elmore company and others unsuccessfully, he offered them to Webster and associates. After due consideration, Webster and associates formed a syndicate, into which they took a number of other people, and this syndicate purchased the Cattermole, Froment, Sulman & Picard, and other oil-process patents. Webster and Ballot, two of the holders of the old option on the Elmore process for Australia, were directors of the new syndicate, which was called Minerals Separation, Ltd. The Elmore company then brought a suit against Webster, Ballot, and Hay, to enforce the clause in the contract above mentioned.

After hearing evidence on the negotiations leading up to the option, Mr. Justice Darling delivered judgment to the effect that the particular clause had been introduced into the contract without authority after it had been signed, sealed, and delivered by both parties, and that therefore the Elmore company was not entitled to any redress.

The Elmore company appealed from Mr. Justice Darling's decision to the Court of Appeal, which court, after hearing the arguments of counsel, ordered that the judgment of Mr. Justice Darling be set aside and a new trial held.

The new trial was held in the Chancery division of the English courts before Mr. Justice Parker. In this trial the Elmore company introduced evidence to show that the Minerals Separation processes were oil-flotation processes, similar to the Elmore processes, and that they belonged rightfully to the Elmore company under the terms of the clause of the option above-mentioned. Webster and associates introduced evidence to show that they



LITIGATION.

had never owned these patents ; that they were never in their possession but had been bought by a trustee of the syndicate, and had passed directly from the inventors through a trustee to the Minerals Separation Syndicate. When the proceedings reached this stage, the learned counsel for the plaintiffs asked the Court for a moment to confer with the learned counsel for the defendants. Thereupon it was mutually agreed between the plaintiffs, the defendants, and the Court, that the proceedings be stayed on the following terms :

That both parties to the action pay their own cost.

That the option agreement be treated as if the clause referred to were struck out altogether.

The result of this piece of litigation leaves the impression that it was unnecessary and wasteful.

ELMORE *v.* MINERALS SEPARATION, LTD. Decision delivered May, 1909. The Minerals Separation, Ltd., through Sulman, Picard, and Ballot, applied for a patent in Germany. This was opposed by Elmore, but the patent was granted. The Elmore company appealed from the decision of the Patent Office to a higher court, which reversed the decision of the Patent Office.

MINERALS SEPARATION, LTD., *v.* NORRIS. Decision rendered May, 1909. Dudley Norris applied for a patent in England for a method of introducing air into an oiled pulp. This was opposed by the Minerals Separation, Ltd., and after hearing evidence the law officer held that practically all but one of Norris's claims were anticipated by the earlier patents of Hoover & Sulman.

MINERALS SEPARATION, LTD., *v.* POTTER. Decision rendered July, 1909. After the Potter company had compromised with the Delprat interests they applied for amendments in Australia with a view to overcoming the invalidity in their patents as indicated by Mr. Justice à Beckett. These amendments were opposed by the Minerals Separation, Ltd. The case was heard before the Commissioner of Patents, and some of the amendments were granted and others rejected. The Minerals Separation, Ltd., appealed from the decision of the Commissioner to the High Court of Australia, and this court decided in favour of Potter, and the amendment was granted. In December, 1909, Minerals Separation, Ltd., applied to the Privy Council in London for permission to appeal from the High Court of Australia, but the application was denied on the grounds that the case could only come before them on a question of infringement.

BRITISH ORE CONCENTRATION SYNDICATE, LTD., AND ALEXANDER STANLEY ELMORE, *v.* THE MINERALS SEPARATION, LTD. Decision rendered in November, 1909. This was a suit brought by the Elmore interests, owners of an oil-concentration process, asking for "an injunction restraining the defendants from using "ores or mineral substances treated by any one of the processes "described and claimed respectively in the specifications of "letters patent No. 21,948 of 1898, and 6,519 of 1901, of which "the plaintiffs are the registered legal owners." The trial case was heard in July, 1908, by Mr. Justice Neville, of the High Court of Chancery, who, after an inquiry lasting seven days, pronounced judgment to the effect that the Minerals Separation, Ltd., owners of the Minerals Separation process, were not infringing. In his judgment Mr. Justice Neville made the following points :

(1) The selective action of oil for sulphides was known before Elmore obtained his patents, and was disclosed in prior expired patents.

(2) Elmore's patent was for a process wherein a large quantity of oil was used, sufficient to carry all the sulphides to the surface by the buoyancy of the oil.

(3) The Minerals Separation process used only an infinitesimal amount of oil for the purpose of attaching air-bubbles to the sulphides, and so causing them to float by the buoyancy of the air-bubbles.

(4) The use of acid in oil processes was known before Elmore obtained his patents and was disclosed in prior expired patents.

Mr. Justice Neville then summed up in these words :

"I think, therefore, in that case, whether you take it that "the patent is confined to the 1898 patent, or whether you take "it generally, the defendants have not infringed, or they have "infringed a patent which has no validity, and consequently no "relief can be granted against them."

The plaintiffs (the Elmore company) appealed from this decision and the appeal was heard in the Court of Appeal before the Master of the Rolls, Lord Justice Fletcher Moulton, and Lord Justice Farwell, in November, 1908. Judgment was rendered on December 2, reversing the decision of the lower court and finding that Minerals Separation, Ltd., were not infringing the 1898 patent, but were infringing the 1901 patent. An injunction was granted as applied for. Lord Justice Fletcher Moulton's idea of the patents in question was as follows :—

(1) That the first Elmore patent was not anticipated by previous expired patents.

(2) That if Minerals Separation used a thin oil they would not infringe Elmore.

(3) That the second Elmore patent was not anticipated by previous expired patents.

(4) That the Minerals Separation infringed the second patent by using acid.

The Court of Appeal thereupon reversed Mr. Justice Neville's decision and granted the injunction against Minerals Separation, Ltd.

The Minerals Separation, Ltd., appealed from this decision to the House of Lords—the court of last resort—and on November 16, 1909, the Lord Chancellor and Lords Halsbury, Ashbourne, Atkinson, and Shaw, reversed the judgment of the Court of Appeal and upheld the judgment of the trial court as follows :

The Lord Chancellor held that the Elmore patents were drawn up with great subtlety in order that the claims might be expanded or contracted as occasion might require in the interests of the patentee ; that the only definite claim in the patent was for acidulation, and that this was anticipated in the expired Everson patent ; therefore the Elmore patents could not be sustained.

Lord Halsbury held that the Elmore and the Minerals Separation processes were essentially different, in that the one was based on the selective action of oil, and the other on surface tension ; that Elmore had no valid claim to acidulation, because it was known and had been previously described ; that the Elmore patent should not be upheld, if for no other reason than because of its ambiguity.

Lord Atkinson held that the Elmore process was the addition of a small quantity of acid and a relatively large quantity of oil to a mixture of ore and water, where the oil, in accordance with some obscure law of affinity, seized upon the minute particles of ore in preference to the earthy particles, and, by the buoyancy of oil, floated them to the surface ; that the Minerals Separation did not infringe this process because their process was one where they made use of the known selective action of oil, yet the oil was used in relatively small quantities, and the metallic particles were only coated with a thin film of it, and the lifting force was found, not in the buoyancy of the oil, but in the natural buoyancy of the air-bubbles, which, introduced into the mass by violent agitation,

envelop or become attached to the oiled mineral particles and raise them to the surface.

Lord Shaw held that the two processes were essentially different, so much so, that apart from the question of the prior state of knowledge of the art, there was no infringement.

Lord Ashbourne concurred with the decision of their lordships, thus making the judgment of the Court unanimous.

UNDECIDED CASES.

ELMORE v. THE SULPHIDE CORPORATION, LTD. The Elmore company filed a writ in Australia alleging that the Sulphide Corporation is infringing the Elmore patents by the use of the Minerals Separation process. The case came to trial in New South Wales, and was decided in favour of the Sulphide Corporation, but an appeal to the Privy Council is now pending.

POTTER v. THE SULPHIDE CORPORATION, LTD. The Potter Sulphide Process Co. filed a writ in Australia alleging that the Sulphide Corporation is infringing the Potter patents by the use of the Minerals Separation process. This suit has now been withdrawn as a result of the amalgamation of the interests involved.

MINERALS SEPARATION, LTD., v. DE BAVAY. The Minerals Separation, Ltd., filed a writ in Australia alleging that the Amalgamated Zinc, Ltd., is infringing the Minerals Separation patents by the use of the De Bavay process. This suit also has been withdrawn as a result of the amalgamation of the interests involved.

MINERALS SEPARATION, LTD., v. HYDE. The Minerals Separation has brought a suit against James M. Hyde alleging infringement on the Butte and Superior mine, in Montana, U.S.A.

All this mass of litigation is inconclusive. No one of these suits would involve a decision on all the patents. In fact, if all the law-suits already started were brought to a final decision it is doubtful whether the public would know whether they could use the processes of the successful litigants without fear of further litigation. If the whole situation could be placed before a competent court to decide on merit it would be far preferable to the engineer, but it might be less acceptable to the legal profession, for obvious reasons.

CHAPTER IV.

THEORIES.

An entirely unnecessary veil of mystery has been suffered to obscure the theoretical side of flotation processes. The forces involved, it is true, are not of such common cognizance as are those in the older methods of gravity concentration, but they are no more wonderful or mysterious in the one case than in the other. The forces utilized are finite in the range of their manifestations, but we have to appeal to molecular considerations for a complete exposition. The imagination of professional engineers is so well trained in these days that they should have no difficulty in grasping the significance of most of the observed facts, and there is, therefore, no reason why anybody engaged in metallurgical pursuits should not become as familiar with these methods of ore treatment as with any other.

A few analogies may be instanced in order to inspire confidence and allay the well established fear of the mysterious. For example, the amalgamation treatment of gold ores, wherein crushed ore, water, and quicksilver are mixed in proper proportions and in suitable devices, is so well known, and metallurgists have become so familiar with it, that the wonderful and obscure molecular reactions between the gold and the quicksilver are never given any thought. Again, the chemical reactions characterizing the cyanide treatment of gold ores, though we are in a measure able to quantify them by a familiar symbolism, require an undoubted exercise of the imagination by means of a written or mental picture of $\text{KCy} + \text{Au} = \text{KAuCy}$. So in the case of flotation-concentration processes the physical laws are for the most part plain; and where obscure, the obscurity is not a matter that need obstruct practical application. It is not my purpose to enter into a mathematical or physical discussion of the laws regulating these forces. James Clerk Maxwell, in his classical article on 'Capillary Action,' in the ninth edition of the *Encyclopædia Britannica*, has laid the foundation for a mathematic demonstration of all the phenomena involved; moreover

H. Livingstone Sulman and Hugh F. K. Picard have in preparation a full dissertation on the observed facts of surface tension and oleaginous and gas-film adhesion, with special reference to their bearing upon concentration by flotation. Sulman & Picard's essay is a document of the highest scientific quality, and we have had a pleasant foretaste of its merit in Sulman's recent announcement of the hysteresis range of the contact angle.

My purpose is to give a description in plain and simple language of what takes place when a particle of mineral floats at the surface of a liquid, leaving the mathematical and molecular aspects of the subject to be discussed at some future time.

Unfortunately, the nomenclature hitherto adopted in discussing the laws and principles governing flotation processes has not been such that it carried any explanation with it, but it is the better part of wisdom not to attempt to introduce new terms. I must confess to an inexplicable dislike of the term, 'surface tension,' a dislike that dates from my undergraduate days in the physical laboratory.

SURFACE-TENSION.

All masses of substances, whether solid, liquid, and probably gaseous also, have, acting at their surfaces, a force parallel to the surface that is the resultant of molecular activity within the body of the substance, and that tends to resist rupture of the surface. This force, in the case of a liquid, is known as 'surface tension.' It is difficult to measure it, but it has been measured for many liquid substances. For the surface of plain water in contact with air, the magnitude of this force has been determined to be 81 dynes per square centimetre.* In all likelihood the figures will be modified by further experimentation, but for any purpose of the engineer this figure is quite accurate enough.

When a slightly oiled needle floats upon the surface of water, the force that causes it to float is 'surface tension.' This force is strong enough to prevent the needle from rupturing the surface; hence, if the needle cannot rupture the surface, it lies apparently on top of the water, or 'floats.'

As to the nature of the manifestation of energy or force, which we call 'surface tension,' the textbooks will give enough to clarify and even confuse, but some attempt must be made here

**Encyclopedia Britannica*, 11th edition, p. 275.

to render clear what the nature of this force may be. W. R. Ingalls says :* "A body of water, or of any liquid, has greater cohesion in its free surface, *i.e.*, the surface exposed to the air, than elsewhere in its interior, because, whereas the particles in the interior are mutually attracted by adjacent particles in all direc-




FIG. 5.—Beaker of Liquid.

tions, those which are at the surface have no attractions from the outside—from above, let us say—to counteract the pull from those in the interior." The state of affairs he describes can be illustrated diagrammatically by imagining the molecules of the liquid to be of sufficient size to be represented on paper. In Fig. 5

**Eng. & Min. Jour.*, Oct. 26, 1907, p. 765.

each circle will represent a molecule. The molecular attraction of each molecule can be resolved into resultants for purposes of illustration, the resultants being placed as shown by arrows in the figure.* Now the molecule at A, for instance, attracts and is attracted by adjoining molecules by resultant forces that are equal, and the molecule is free to move in all directions. The molecule at B, however, having no molecule above it to attract and be attracted is in a somewhat different state from the molecule at A. The molecule at B has its upper one of the six resultant forces uncompensated by a molecule lying above it, so we can assume that this upper resultant is compensated between the molecules on any side of B. This gives the topmost row of molecules a stronger attraction for each other than the molecules adjacent to A have for one another. The attraction of the molecules within the liquid, as, for instance, those at and adjacent to A, is known as the force of cohesion. If this force of cohesion is resolved into the six resultants as above described, and its magnitude is called 6 units, then the magnitude of the molecular attraction acting on a molecule in the top layer, as at B, will be 6 units just the same, but the molecule will not be as free to move in every direction as is the molecule at A. If the stress between any two molecules in the horizontal row containing A is 2, then the stress between any two molecules in the horizontal row containing B will be $2\frac{1}{2}$. Ingalls goes on to say in explanation of this: "The effect of this is to reduce the mobility of the particles on the surface. The surface, as it were, is stretched by [like] an elastic skin, the effect being the same as if the surface layer exerted a pressure on the interior. The production of this 'surface tension' represents energy, *i.e.*, molecular energy which may be measured." As we have quoted above, from the *Encyclopedia Britannica*, this surface tension has been determined for water to be 81 dynes per square centimetre, a force that resists penetration from within or without the liquid.

ADHESION.

We must go further afield in the study of molecular forces before we can understand clearly the act of the flotation of particles heavier than water, and consider the molecular phenomenon known

*To make the assumption complete we must imagine two resultants acting at the centre of each circle, at right angles to the plane of the drawing.

as 'adhesion.' Referring again to Fig. 5, at C there are molecules that have uncompensated attractions unless we assume these are compensated by attraction between the liquid and the solid walls of the vessel. But the force of adhesion is also made up in part of the molecular activities of the solid surface molecules, which, we believe, lie much closer together than those of a liquid. The surface activity of a solid would be difficult to measure; but by analogy we are justified in assuming it is in general greater than the surface activity of a liquid. So that a liquid and a solid in contact should have an attraction for each other in general stronger than the surface tension of the liquid. This state of unbalanced liquid stresses at the bounding surfaces of a liquid also gives rise to a further noticeable condition, as at D, where the corner molecule has not only its upward component, but also one of its lateral components near E abnormally compensated. This will give an illustration of what produces the meniscus, where a liquid, a solid, and a gas come into contact. Adhesion is not, however, limited to solids on liquids, but acts in solid-gas, and probably gas-liquid couples. The mathematics of these forces and the theoretical discussion could be pursued considerably further, but enough has been given to illustrate the terms employed.

The films of gases that are attracted to the surfaces of solid particles adhere strongly in some instances, and are displaced therefrom by a liquid with considerable difficulty. This quality of adhesion varies remarkably with different substances.

With some substances the gas adhesion is strong and the liquid adhesion is weak; in other words, they are wetted with difficulty. In this class are the metallic sulphides, which, although they have a natural tendency not to adhere strongly to water, do fortunately have a strong natural tendency to adhere to oil. And further, oil has an even stronger tendency to adhere to its gas film, so that a sulphide particle covered with an oil film has an already strong tendency not to adhere to water considerably increased. Quartz and gangue minerals generally, on the other hand, have preference in directly the opposite direction. They have a comparatively feeble adhesiveness to gas films and oil, and a strong adhesiveness to water, and this already strong adhesiveness for water is greatly increased by a slight acidulation of the water. There has been no satisfactory theory yet propounded as to why acid does promote the preferential adhesion of water to gangue particles, and probably

also at the same time the preferential adhesion of oil to sulphides, and for the present commercial purpose it does not seem necessary to do more than record this important fact. Bertram Blount, in speaking of sulphide particles, has expressed the idea of selection or preferential oiling as follows: "Before they were oiled at all their surfaces had certain qualities, one of which is a tendency not easily to be touched by and wetted with water. On the other hand, correlated with that property is the power of being easily touched by and wetted by oil. When they were put through this process they exercised both properties, and acquired or annexed a minute quantity of oil, which was presented indifferently to them and to the gangue, only they obtained it and the gangue did not. They came out of the process with that inherent quality enhanced by a minute film of oil, and then they were even less ready to be wetted by water and to sink through it than they were before, but it was only an exaggeration of what was a native quality."* Kenneth A. Mickle, in an excellent paper,† giving the results of experimental work on gas-bubble and oil attachment, points out that gas-bubble adhesion does not take place if the amount of oil is too large—that is, if the sulphide particles are too much wetted by oil. His paper is the most valuable contribution that has yet appeared on these subjects; but, unfortunately, he has used both the words 'cohesion' and 'adsorption' where he should have used 'adhesion.'

Thus it has been established that there are:

- (1.) Forces acting at the surface of a liquid, the resultant of which tends to prevent rupture of the surface.
- (2.) Forces acting at the surfaces of all substances, and especially at the surfaces of sulphide particles, that cause films of gases resisting displacement to adhere to their surfaces.
- (3.) Forces acting at the surfaces of sulphides that cause these surfaces to show a preferential adhesion to oil.
- (4.) Forces acting at the surfaces of gangue minerals that cause these surfaces to show a preferential adhesion to water, and especially acidified water.

We now have the main principles by which to account for the 'floating' of particles heavier than water, and we shall not worry as to what more these forces are, nor discuss the mathe-

*Evidence at trial of B.O.C.S., Ltd., v. M.S., Ltd., 1908.

†*Australian Mining Standard*, Vol. XLVII., 1912, pp. 333, 357, 381 & 403.

metrical formulas by which they can be resolved into their component parts.

In the simplest case we have a small particle of zinc sulphide, which has been exposed to the air, and upon the surface of which there is adhering a film of air. This particle of blende P, Fig. 6, is then brought into contact with water. The force of adhesion between the particle and the film of air prevents the water from displacing the film of air, and the force of surface tension prevents the particle of blende from penetrating the water surface; therefore the particle is suspended at the surface thus:



FIG. 6.—Floating Piece of Mineral.

If this particle of blende, P, before being brought into contact with the water, had been coated with a thin film of oil, and if the water had been slightly acidified, then both the adhesiveness of the particle for the gas film and the resistance of the liquid surface to rupture would have been increased, and the act of 'floating' would have been made triply sure by the natural tendency of the blende and the enhancing action of the oil and acid. If at the same time a particle of quartz gangue had been brought into contact with the acidified water surface, it would have behaved in an entirely different manner. The particle of quartz, having a much feebleness for its air film, and having a strong natural tendency to adhere to water, and also having this tendency to adhere to water and become wetted with water increased manifold by the acidulation of the water, it would have quickly penetrated the liquid surface and sunk to the bottom, for the act of wetting implies at the outset penetration of the surface.

BUBBLES.

In Fig. 6 it should be pointed out that the surface A B may be either the horizontal surface of a liquid at rest (and considered the limiting surface of a bubble of infinite radius), or, equally important, the surface A B may be considered the surface of a bubble of small diameter within the body of a liquid. This bubble may have a radius of one foot or one inch or one thousandth of an inch, and the action of the sulphide particles with reference to the bubble will be just the same as it is with reference to the

free surface of a liquid. If the bubble has a radius of, say, one-tenth of an inch, and the blende particle a mean diameter considerably less, the bubble will rise by its buoyancy to the surface of the liquid, and carry up with it the blende particle adhering to the surface A B of the bubble. If then, instead of only one blende particle, we mix slightly acidified water with crushed ore and a little oil, and release in the whole body of the pulp a large number of minute gas bubbles, we will have the above described sequence of events taking place in innumerable instances, and these innumerable bubbles will rise to the surface of the liquid and rest there in the form of a froth, carrying with them the sulphide particles, while the gangue in the meantime has exercised its preferential adhesion for the water and become wetted, and remains within the body of the liquid and sinks to the bottom of the vessel. The bubbles may be bubbles of air introduced by violent agitation of the pulp, or air bubbles released from solution in the liquid by subjecting the liquid to a vacuum, or air bubbles dissolved in the liquid at super-atmospheric pressure, followed by a release of pressure, or they may be carbonic-acid gas bubbles released by the chemical reaction of sulphuric acid on carbonates, or in several other ways.




FIG. 7.—The Contact Angle.

In Fig. 7 it will be seen that near C there is a point where the air, the liquid, and the solid all meet in a common point, this point being the trace of a line perpendicular to the plane of the drawing. The angle E C D is made up on one side with the solid and the other side with a tangent drawn somewhere on the curve C F. It is certain that a study of the curve C F, by means of a microscope and screen, would be a profitable line of experimental work. Maxwell says: "The constancy of the angle of contact between the surface of a fluid and a solid was first pointed out by Dr. Young." It is difficult to say where this tangent should be drawn. From a consideration of the forces acting near the region of mutual contact between a solid, a liquid, and a gas, it seems most reasonable to assume that there is no definite point where

one could draw a tangent, but that the curve C F is a continuous curve, the functions of which are : (1) The force of surface tension of the liquid ; (2) the force of surface activity or adhesiveness between the solid and the liquid ; (3) the force of adhesiveness between the solid and the gas ; (4) the force of adhesiveness between the gas and the liquid ; (5) the force of gravity ; (6) temperature ; (7) pressure ; (8) shape of the solid surface ; (9) composition of the solid ; (10) composition of the liquid ; (11) composition of the gas ; and others.

The methods of measuring what are termed contact angles are shown in Fig. 8, a piece of mineral having one plane surface, generally a cleavage plane, being immersed in a liquid surface as at A, and then turned through an angle, α , to a position like B. As the piece of mineral turns, the curved surface of the liquid in the neighbourhood of the line of mutual solid-liquid-gas contact flattens until it is horizontal, and the angle $180^\circ - \alpha$ is said to be the angle of the contact. This angle is a definite angle under fixed conditions.



FIG. 8.—Measuring Contact Angle.

H. Livingstone Sulman, in Bulletin No. 79, Trans. I.M. & M., speaking of the angle $180^\circ - \alpha$, announced that "a study of a series of observations on various substances showed a series of curiously discrepant readings, which on further research proved to be due to the existence of a variable range of the contact angle between liquids and solids, though of constant magnitude of variation for each substance. This hysteresis appears to be intimately connected with the ability of a given solid to condense upon itself gas films, and when submerged in a liquid to determine the attachment of a gas when generated. It follows that this angular hysteresis reaches its highest value for minerals that are the most susceptible of flotation. Besides roughly quantifying the gas-condensing power due to the surface energy of solids, it brings us somewhat closer to an explanation of the efficiency of acidification. Whereas the angular hysteresis of silica in plain water may exceed 30° , thus indicating that substance to have a definite power to occlude gas and float, it drops to from 4° to 0° in water acidulated with

sulphuric acid." Sulman has here announced a discovery of the first magnitude, and places in the hands of the physicist a clue to many puzzling questions.

COMMERCIAL EFFECTIVENESS.

The forces with which we are dealing are feeble in magnitude when compared with, say, the force of gravitation. It should be emphasized, however, that although these forces acting at the surface of substances are to our conception feeble, they act continuously at all surfaces; and although we cannot increase the unit force, we do have it in our power to increase enormously the units of surface, and thereby we can bring the nett resultant work of these forces up to an effective sum.

There are two ways in which the surfaces involved can be increased. A cube of ore 2.1544 feet on each edge contains 10 cubic feet. If this ore is a definite mixture of quartz, blende, galena, etc., it will weigh just a ton. The cube will have a total surface area of about 28 square feet, or roughly 4,000 square inches. If this cube of ore is crushed to 40-mesh it is certain, on reasonable assumptions, that the superficial area of the ton of ore is increased to more than 30,000,000 square inches, an increase in area of several thousand times the original.

The De Bavay process uses the surface film of the liquid at rest as the transporting agent, and therefore does not get the advantage of the second method of increasing the surface factor, which is advantageously made use of by Elmore, Minerals Separation, and Potter-Delprat. This second method of increasing the effective surface is by creating a froth of bubbles, each bubble of which acts as previously described. It is no unusual sight to see on the flotation boxes of the Potter-Delprat and Minerals Separation processes two inches of froth composed of a compact arrangement of bubbles and sulphides. By determining, roughly, the size of the bubbles and the distance apart, it is safe to say that the available liquid surface is increased from 20 square feet on the free surface of the liquid in a box to 2,000 square feet when the surface of all the bubbles is counted. In both the case of the mineral and the liquid it is obvious that only a small portion of the surface is used for the work of flotation.

As before stated, the surface tension of water has been determined to be a force of 81 dynes per square centimetre, acting at the surface, to resist penetration of the surface. If we assume

that the force tending to make finely divided sulphides penetrate the surface is the force of gravity, then each gramme of sulphides is impelled to penetrate the surface by a force of 981 dynes, and therefore one square centimetre of the surface will hold up $81 \div 981 = 82.6$ milligrammes of ore.

Leaving out of account the enhancement of this force of surface tension by the admixture of oil and acid and other means, the following table will show that this force is adequate for the work required of it. The efficiency of the utilisation of the force is in all four cases very low :—

	No. of Machines.	Feet of overflow lip.	Sq. feet of Surface.	Times per min.	Capacity at (81 dynes per sq. cm. = 82.6 mg. per cm.) lb. per hr.	Actual lb. pro- duced per hour.	Actual lb. per hour per ft. of lip.	Actual lb. per hr. per sq. ft. of surface.	Theoretical Capacity lb. per sq. ft. per hour.
De Bavay	88	2765	1620	20	328,800	44,800	16	28	202
Elmore	10	45	6.5	60	3,960	8,064	179	1,240	609
Minerals Separation	6	24	120	3	3,650	31,360	1,300	260	30
Potter- Delprat	3	14	68	3	2,065	26,880	5,376	395	30

Referring to the last two columns, in the case of Minerals Separation, Elmore, and Potter-Delprat, it will be seen that they have increased their theoretical capacity per hour, based on the surface area of the boxes, to several times more actual working capacity by means of making a froth. The variables in the problem are so many that it is not safe to attempt more than to roughly quantify the force available, but it is certain that the force available is many times as large as is necessary for the work to be done. This phase of the subject is an interesting one for research and speculation, and will, no doubt, receive critical study.

SOLUBLE FROTHING AGENTS.

In what has been said before in regard to the production of a mineral froth, I have had in mind the use of some insoluble substance like oil to promote the flotation and froth production. In the Potter-Delprat process a froth is presumably produced without any oil, but in that case carbonic acid gas is the gas used. It is a significant fact that no method has yet been found of producing a mineral froth by air bubbles without the addition of oil or some other substance. Among other substances that will assist in producing a commercially effective mineral froth are a number of soluble substances, as amyl alcohol, camphor, most of the essential oils, the phenols, and a number of gas-tar derivatives.

The phenomena to be observed in connection with the use of these soluble substances as mineral frothing agents are confusing. What has been said about the oil adhering to the sulphides in the first part of this chapter does not apply in the case of these substances, because they are completely soluble in the proportions used; being completely soluble in the proportions used, the small amount employed in treating the ore (1 lb. per ton of ore) cannot be thought to adhere preferentially to the sulphides. On the other hand, although these substances are soluble, the solution cannot be used over and over again beyond narrow limits, but the frothing agent must be added continuously. It is also inconceivable that there is any chemical reaction between, say, the soluble essential oil of *eucalyptus amygdalena* and any of the ingredients of the ore. The froth produced in this case has identically the same appearance as where air, oil, and acid, or acid and carbon dioxide, are the froth constituents, and we are justified in assuming that in the main there is no difference in the forces acting. A complete answer as to just 'What is a froth?' would probably clear away all the uncertainty as to just 'What is a flotation process?'

COAGULATION.

One of the most significant facts to be observed in these processes is the coagulation effect of the operation. As an illustration, when a little salt or acid of almost any kind is added to soapy water, the soap collects in flocculent masses; we say the soap has coagulated. So in this ore-treatment operation it will be observed that the sulphides are coagulated in masses, some of which are of appreciable size even when they have not gathered sufficient air bubbles to float them. The gangue, on the other hand, has not coagulated; but, due to the fact that the sulphides have coagulated, the gangue assumes an appreciably different and generally lighter colour than was the original ore. If the sulphides have not been floated as a froth (due to insufficient gasification), it will be observed that the ore as it settles has a streaky or mottled appearance, due to the fact that the darker sulphides have coalesced in considerable masses. It is not to be inferred that coagulation is a condition necessarily precedent to successful flotation, for it is not; but in tests, and in the operation of a working plant, coagulation is a 'sign of good work.'

R. Storm says¹: "Fine slime cannot be treated by these processes because, as the volume and area of the particles ap-

proach zero, they will have no adhesion effect." This is just where coagulation becomes a factor in rescuing the slime, and, contrary to his opinion, establishes the fact that adhesion does act, and that coagulation is simply one of the manifestations of adhesion. By a process that gives violent agitation with aeration and warming, the slimed sulphides coalesce together in the form of coagules, and then become, if they were not before, amenable to the forces of gas-adhesion and surface tension.

This coagulation of the sulphides is similar to that in the case of butter, when, after a period of agitation of the cream, the butter-fat particles in the cream begin to adhere together, and finally grow into balls of butter of appreciable size, and the dairy-man says: "The butter has come." So in the case of an ore-pulp with a small portion of oil added, with or without acid, if it is stirred for a suitable length of time with a rolling motion, the sulphide particles begin to adhere together, and if the rolling motion is sufficiently prolonged, the sulphides can be made to gather together into balls an inch in diameter free from any gangue particles. If this coagulation effect is stopped in its incipient stages, and if a multitude of infinitesimally small gas-bubbles are released in the pulp, each bubble lays hold of a 'coagule' of sulphides and buoys it to the surface where the mixed bubbles and sulphides rest in the form of what we call 'froth.'

CHAPTER V.

TESTS.

From what will be said later in regard to the limited applicability of these methods, it will be evident that anyone undertaking the study for the first time of either the application of the processes to a particular ore, or a study of the theory of the processes themselves, should begin with an ore that is easily treated by flotation. What is needed is an ore that presents the fewest special problems. An ideal mixture for the experimental work of a beginner would be one composed of 60% quartz and 40% brown blende, or say, 70% quartz and 30% of pyrite or chalcopyrite. These mixtures are not common in nature, but approximations thereto occur frequently. With the above proportions in mind as ideal ores for the beginner, it is well to ascertain that the ore chosen does not contain more than 2.5% of calcium carbonate or other carbonates. A series of experiments for the beginner who has had no previous knowledge of the processes can easily be made without special apparatus, and such experiments will serve to illustrate some of the phenomena of concentration by floating part of an ore at the surface of a liquid. At the very outset a standard test should be selected for trying each new ore studied or each new oil investigated. The behaviour of the new material under these standard conditions can then be compared with previous results, thus giving the investigator a point of departure in his explorations. A good standard experiment is 1,000 parts of ore crushed to 60-mesh, 3,000 parts of water, 10 parts of sulphuric acid, and 1 part of oil, all by weight and at a temperature of 70° C. Variations can then be made from these proportions in conformity with the special characteristics of each ore under examination, or the special nature of the oil used, or of any other variable that may be under examination. In beginning the investigation of any ore, the above is a good combination with which to start the first experiment, and then the proportions may be varied by gradual steps until the combination giving the maximum result is reached.

In the following experiments the ore can be weighed in an ordi-

TESTS.

nary balance ; the water can be measured in cubic centimetres, calling 1 cc. a gramme ; the acid can be measured from a burette, but the oil should be measured by counting drops from a glass tube drawn to a medium fine point, previously having determined by trial how many drops of a given oil go to make up one-tenth and one-hundredth of a gramme, because the preliminary experiments will be with small amounts of materials.

EXPERIMENT I.

Take	10	grammes	of	ore.
	30		„	water.
	0.1		„	acid.
	0.01		„	oleic acid.

Temperature 75° C.

Place these in a test-tube of 75 to 100 cc. capacity ; warm contents to about 75° C ; close the tube with the thumb, and shake energetically for about a quarter of a minute. The only measure that can be cited for the amount of shaking necessary is to shake the tube until the arm aches. Upon allowing the tube to stand a few seconds there should be decided indications of a separation into layers. At the bottom should be a layer of quartz or gangue much lighter in colour than the original ore ; then a layer of gradually settling gangue-slime ; then a small layer, gradually increasing, of sulphides dropping through the liquid ; then a considerable layer of dirty water ; and finally, on top of all, a layer of froth composed of bubbles of air and sulphide particles. By varying the amounts of oil or other ingredient of the mixture a series can be secured for comparative inspection. Some of the froths made with certain oils are of wonderful persistence, and if undisturbed will stand without alteration for months.

The next step is to take a larger vessel, say, a wide-mouthed bottle holding 200 cc., one that can be grasped comfortably by both hands and held in front of the operator with the thumbs over the cork. The shaking must also proceed to the aching point by the energetic use of the arms and shoulders. The charge in a series of tests of this kind will be :

Ore (60-mesh)	30	grammes.
Water	90	„
Acid	0.3	„
Oil	0.03	„
Temperature	75°	C.

Shake and allow to settle. By carefully preparing a set of bottles for comparison, or by familiarity with a long range of similar tests, the operator can make a rough estimate as to the result. In both the case of the test-tube and the bottle it is difficult, if not impossible, to get quantitative results.

The question of securing, on a small scale, quantitative results that would bear some known relation to actual milling operations, and at the same time be under ready control as to the various factors, has occupied considerable attention. Small machines built exactly like large machines do not always duplicate the





FIG. 9.—Slide Test Machine.

large-scale operations. Perhaps the best all-round apparatus for a study of ores and the influence of oils, acids, temperatures, etc., on surface-tension results is a small machine,* suggested originally by the author to H. L. Sulman and John Ballot, first made by H. F. K. Picard, and improved to its present form by James M. Hyde and others of the Minerals Separation, Ltd., Staff, as illustrated in the accompanying photograph. The driving mechanism to the left of the picture does not require any description, and can with advantage be discarded in favour of a small motor. The motor also

*This machine is not patented.

has the advantage that exact speeds can be duplicated, as well as exact lengths of time of agitation. The portion of the apparatus on the right can be better described by reference to Fig. 10, which is a section drawn through the apparatus parallel to the plane of the photograph. Fig. 11 is a transverse section, and Fig. 12 a plan of the machine.


This machine is made in two parts, an upper one A, and a lower one C, both sliding easily on a rubber cushion B between the two parts, or, better still, having the bearing surfaces highly polished. The rectangular section of the interior is $4\frac{1}{2}$ inches. The upper part



LONGITUDINAL SECTION.

FIG. 10.—Machine for Tests.

A has a tail D, the purpose of this being to prevent leakage of the froth when the upper part is slid to the right for the purpose of removing the froth. Windows of glass in each of the two parts enable the operator to watch the progress of the test. At E there is a simple agitator with four arms at right angles. The shaft driving this agitator goes through the bottom G of the lower part C,



TRANSVERSE SECTION





FIG. 11.—Machine for Tests.



PLAN

FIG. 12.—Machine for Tests.

and is packed with a small stuffing-gland to prevent leakage. At F is a hole communicating with the interior at the bottom, closed with a valve. This hole is for the withdrawal of tailing. The agitator-arms are 2 inches long from the centre of the shaft, thus describing a circle of 4 ins. when revolving, and so leaving a clear space of $\frac{1}{4}$ in. wide between the ends of the arms and the sides of the interior. The normal speed of this agitator is about 1,500 r.p.m. The machine should be made of some metal that gives a clear casting. The lower surface of A, which rests on the rubber cushion B, and the upper surface of C, upon which the rubber cushion rests, should be planed and polished smooth. The cushion is a piece of rubber insertion about one-sixteenth of an inch thick, and just wide enough to fill the space between the edges H and J of the tray-like top of C. The cushion can be discarded if the surfaces are accurately planed and polished.

The equipment necessary for the tests will also include a tin boiler, with the proper connections to make steam at a low pressure, the steam being introduced by a tube hanging from the top of the machine almost to the agitator inside. An assortment of agate-ware dishes, burettes, pipettes, etc., is an obvious necessity. Having arranged everything in order, the method of making a test is as follows: Measure 1,500 cc. water and place in the machine. This will fill it to about $\frac{1}{2}$ inch above the bottom of the upper window. There will be no leak at the plane of junction between the upper part A and the lower part C, because the planed surfaces adhere to the rubber sufficiently to prevent leakage under the slight head. Start the agitator at half-speed, and then admit the steam. While the agitator is running, steam in large volume can be admitted without any 'bumping.'* Weigh 500 grammes of properly crushed ore, and put it into the agitating water; test the temperature, and when it is at 75° C add the oil and acid in such quantity as the test requires. Turn on the motor to full speed, and let it run, say, five minutes. Stop the motor and agitator, and let the whole experiment set for one half-minute to allow time for the froth to collect on the surface of the water and for the gangue to settle. If the experiment is a success, the gangue will be much lighter in colour than was the original ore, and will mostly settle to the bottom of the machine, where it can be seen through

*This machine can be cast with a heating-chamber around the lower section, thus enabling heat to be applied by a gas-burner and obviating the necessity for steam.

the lower window. Immediately above the heaviest sandy gangue will be seen the finer gangue and slime rapidly settling. At the bottom of the upper window will be a gradually increasing layer of nearly clean water, and on the surface of the water will be from $\frac{1}{2}$ to $1\frac{3}{4}$ inches of a dense sulphide froth, the amount of froth depending on the proportion of sulphides in the ore and the success with which the experiment is conducted.

The purpose of the peculiar construction of the apparatus will then be apparent, for the upper part A can be slid along the cushion B, carrying with it the froth and that portion of the clean water above the plane of junction of the two parts. When the upper part has been slid to a position where the screws in the right-hand side of the upper window are directly over the lip K, the froth and clear water will run out into a dish placed under K. The tailing, slime, and remaining water can be given a further agitation, but enough water should be added to bring the water up to a line above the bottom of the upper window. After the second period of agitation, a further amount of froth will be formed; this can be removed in a similar manner, and a third and fourth also, if desired. After all the froth has been secured, the tailing, slime, and remaining water can be removed at F, and the two products, concentrate and residue, examined for weight,




FIG. 13.—Quantity of Oil.

size, or composition. In this machine an average of 20 tests per day

can be made, and the following series is suggested as instructive :

Take 100 lb. of ore crushed to 60-mesh, such as described above as being suitable ; mix thoroughly and put in a dry place for use in the whole series of experiments.

SERIES A

No. 1.—Ore	500 gm.
Water	1,500 "
Acid	5 "
*Oil (oleic acid)	0.1 "

Temperature 80° F.

Agitate at 1800 r.p.m. for five minutes.

Let settle five minutes.

Remove froth, filter dry, and weigh and assay if desired.

2.	Same as No. 1 except 0.2 gm. oleic acid.
3.	" " 0.3 " "
4.	" " 0.4 " "
5.	" " 0.5 " "
6.	" " 0.6 " "
7.	" " 0.7 " "
8.	" " 0.8 " "
9.	" " 0.9 " "
10.	" " 1.0 " "

A useful series of observations can be secured by simply observing the weights of concentrate produced. More interesting data, however, can be obtained by sizing both the tailing and the concentrate on a standard series of screens and then assaying the sizes. When the results are plotted from the weights of the various concentrates secured in this series, the curve will be of the nature of Fig. 13. This curve shows that for this ore under these conditions the maximum effect is secured with 0.8 gramme of oil. More than that amount is detrimental, which fact would be proved by still further increasing the amount.

*Oleic acid is an oil by-product from tallow candle manufacture, which can be secured almost anywhere.

SERIES B.

- No. 1. Same as Series A, except oleic acid 0.5 gm. and sulphuric acid 0 gm.
 2. Same as No. 1, except sulphuric acid 0.5 gm.
 3. " " " " 1.0 "
 4. " " " " 1.5 "
 5. " " " " 2.0 "
 6. " " " " 2.5 "
 7. " " " " 3.0 "
 8. " " " " 3.5 "
 9. " " " " 4.0 "
 10. " " " " 4.5 "




FIG. 14.—Quantity of Acid.

According to the amount of carbonate in the ore, the curve of the plotted results will be something like Fig. 14. This ore needs but little acid, the maximum result being secured with 3 grammes. It will probably be ascertained that if the acid is increased sufficiently the recovery is less, because a point is reached where H_2S gas begins to be evolved, and this gas is generally fatal to flotation.

Other series can be built upon the two illustrations already given by varying at regular intervals the temperature, the proportions of ore and water, the nature of the oil, the length of time of agitation, and the speed of agitation. Then having exhausted the




FIG. 15.—Time of Agitation.

possibilities of variation using oleic acid, start a series with a different oil, say, the soluble essential oil of *eucalyptus amygdalena*.

Fig. 15 shows the effect of variations in time of agitation.

Fig. 16 " " " speed " "

Fig. 17 " " " temperature.

Fig. 18 shows the effect of variations in time of agitation with various oils, and also recoveries with various oils.




FIG. 16.—Speed of Agitation.




FIG. 17.—Temperature.

The above series of tests, it will be observed, is by means of a process that includes the use of oil and acid and the addition of air by violent agitation. The general principles are the same as in any other combination, and as they are easily applied and approach working conditions, and the results are comparable with those secured in large plants, they are of considerable value. Over a period of four years, when thousands of small tests were made on





FIG. 18.—Various Oils.

an ore that was being treated in two plants of 1,000 tons per day, the results from the small tests averaged 5% less recovery and 3% lower-grade zinc in the various concentrates than were secured in the large plant.


This machine is a useful addition to the ore-testing laboratory, whether flotation processes are in view or not, because, by the use of it and the expenditure of sufficient acid and agitation, the sulphide contents of almost any ore can be determined accurately.

Another machine of simpler design and cheaper construction is shown in section in Fig. 19, and in plan in Fig. 20. It is made of easily procurable materials, and can be constructed in the laboratory. It has the disadvantage, however, that it requires some skill in removing froth after the agitation. The froth can be removed by careful skimming with a spoon. Some froth will unavoidably be sunk during the skimming operation, but the agitator can be started again, followed by a second skimming. If there appears to be still further chance of a useful result, a third and fourth period of agitation and skimming can be tried. If this machine is made $4\frac{1}{2}$ inches square, inside measurement, and 10 inches deep, it will be the right size for tests on 500 grammes of ore. The equipment necessary for making tests will also include a tin boiler, with the necessary connections for introducing steam into the apparatus. The agitator should be so belted to the motor that it will run about 1,500 r.p.m. The agitator should be about 4 inches in diameter, thus leaving $\frac{1}{4}$ inch clear all round its path of rotation. The method of conducting a test will be just the same with this machine as with the other, except in the matter of removing the froth, and in this instance it will have to be removed by an ingenious hand. Carefully dip as much as possible of this froth off the surface of the water with a large spoon. The design and material of this spoon can be left to the ingenuity of the experimenter, as each man will fancy one of his own invention. Some froth, as said before, will be sunk during the skimming operation, but the agitator can be started and run for one minute previous to another skimming. A third and a fourth, if necessary, will give a fair recovery, provided good mineral-frothing conditions have been established. This machine will yield much instruction, but is not as direct in its results as the one in Fig. 6.


An interesting series of experiments can also be conducted in an ordinary soda-water syphon. The cap of the bottle should be altered so that the pressure can be raised in the bottle with a bicycle



SECTION



PLAN

SCALE OF  INCHES

FIGS. 19 AND 20.—Apparatus for Tests.

pump. The necessary alterations are quite easily done, and can be effected in the laboratory. The charge will be 100 grammes of ore, 300 gm. water, with acid and oil to suit. The air-pump should be one with a pressure-gauge attached, so that pressures can be noted. After pumping to 30 lb. pressure, the bottle with the charge should be shaken a few times, so that the air will dissolve. Then the lever being depressed, most of the charge can be drawn into a beaker, and the froth and tailing examined at will. It is worth noting in this connection that excellent mineral froths can be made at normal atmospheric temperature.

FURTHER TESTS ON OTHER PROCESSES.

The processes are so intimately related that it is difficult to give tests serving clearly to differentiate them. Laboratory tests to determine whether any result will be produced can be easily tried without any special apparatus.

TEST FOR POTTER PROCESS.

Take a 200 c.c. beaker and place therein 100 cc. of 3% H_2SO_4 solution. Place this in a water-bath, and raise the temperature to as near boiling point as possible. Stir into the solution gently 30 grammes of ore crushed to 50-mesh. The froth composed of sulphides and CO_2 gas should form at once on the surface of the liquid if the ore is adapted to the process. If the ore contains no calcite or other carbonates, there will probably be no result. In the latter case, of course, a result can be secured by adding to the ore 3% of ground calcite before stirring it into the solution. The concentrate can be removed with a spoon.

The test-tube experiments that formed the basis of the Goyder & Laughton invention are interesting and instructive. Goyder observed that "when heating some Broken Hill sulphides* in a test-tube filled with dilute sulphuric acid, the bubbles, with their sulphide load, travelled to the surface, broke, and then fell back again. By inclining the tube as in 2, Fig. 21, the sulphides rose and travelled up the smooth side of the tube until they met the surface, when, as before, the granule of sulphide fell off, but this time it fell vertically until it met the side of the tube, down which it glided. The inference was that if there was a pocket in the under-side of the sloping test-tube the sulphides should gather

*'Australian Mining and Metallurgy,' Donald Clark, p. 397.

in the pocket." A special test-tube like 3, Fig. 21, is easily made, and a number of interesting experiments can be conducted by trials of different ores at varying temperatures and varying strengths of acid.

TEST FOR DELPRAT PROCESS.

The procedure in this case is identical with that above outlined for the Potter process, except that the solution is made from acid salt-cake. This obviously is only different from the preceding test in that, besides sulphuric acid, there is present in solution a portion of sodium sulphate. Most of the acid sodium sulphate on the market is made by mixing strong sulphuric acid and sodium




FIG. 21.—Tube for Potter-Delprat Tests.

sulphate in the proportion of about 7 of acid to 3 of sulphate. If there is no carbonate present in the ore, the same result will be secured and the same remedy found efficacious, as with the Potter process.

TEST FOR DE BAVAY PROCESS.

This process depends on a film of sulphides formed on the surface of water to effect a separation. Take 100 cc. of water, containing about 0.1% H_2SO_4 ; add to this 30 gm. sulphide ore crushed to 50-mesh; add a few drops of petrol, and stir with glass rod for half-minute. Empty pulp on a vaning plaque, and gently

rock the plaque so that the liquid alternately covers and uncovers the ore. As these little waves cover and uncover the ore the sulphides are picked up, and float upon the surface. With patience a clean tailing can be produced.

TEST FOR MACQUISTEN PROCESS.

Take 30 grammes of sulphide ore on a vanning plaque. Add 100 cc. water and a few drops of sulphuric acid. Subject the ore to the same manipulation as in the case of the De Bavay and a similar result will be produced, but much less float material will be secured. No amount of patience will serve, however, to produce a clean tailing. This test serves merely to show the principle on which this particular process works.

TEST FOR ELMORE PROCESS.

What is known as the old Elmore process may be tried in a glass jar of about 1,000 cc. capacity. What is known as a Mason fruit-jar with a screw-top is the best apparatus for this trial. Place in the jar 300 cc. water, 100 gm. sulphide ore, and stir slightly to make a uniform pulp; add half cc. strong sulphuric acid and 200 cc. thick oil, such as the thick tarry residue of petroleum or a cylinder-oil. Screw on the top of the jar and turn it end-for-end about 20 times, and set aside to settle for a few minutes. The contents of the jar will settle into layers; at the bottom a layer of sand mixed with some sulphides; next above will be a layer of muddy water, and above that again will be a layer of oil containing most of the sulphides (the amount depending on the success of the manœuvre) and some gangue. The oil layer may be removed by adding more water carefully beneath the oil through a tube, and after the oil and sulphides have been removed the sulphides can be separated from the oil by heat and gentle stirring, when the sulphides will settle to the bottom.

The new vacuum process is more difficult to test in a small way so as to produce a satisfactory result. Probably the best method is as follows: Take a large-mouthed 300 cc. bottle, and fit a stopper with a tube to be attached to a laboratory suction-pump. Put into the bottle 30 gm. sulphide ore, 100 gm. water, one-fifth cc. Texas or California fuel-oil, and one-fifth cc. H_2SO_4 . Stir with a glass rod until a uniform pulp is produced, but do not beat any air into the pulp. Place the stopper in the bottle and attach to the suction-pump. Start the pump, and gently shake the bottle to

keep the ore stirred a little. As the vacuum is produced the sulphides should begin to rise to the surface and form a layer of froth.

MECHANICAL AGITATION.

A simple laboratory experiment will give a clear idea of the efficiency of this method of providing gas bubbles for the purpose of flotation. Take in one hand a test-tube half full of distilled or ordinary water. In the other hand take a test-tube of distilled or ordinary water, to which has been added the smallest possible drop of any one of the following substances: Oleic acid, kerosene, amyl alcohol, any of the essential oils, camphor, or alcohol. Taking one of the above test-tubes in each hand, shake them violently at the same time and to the same extent. The water in the test-tube that had the drop of foreign substance added to it will, upon ceasing the agitation, be white with occluded air-bubbles of small size, and, depending on the substance used, these bubbles and the milky appearance will last for some time. The water in the other test-tube will, however, show no such appearance; the water is as clear and unclouded in appearance as before shaking. An interesting series of tests can be made in this way, in which the time factor for complete clearing away of the milkiness can be observed. This series of tests will show that those substances which produce the best and the most persistent milkiness are in many instances the best materials to use in flotation processes. There are some remarkable exceptions to this rule, however, and some of the worst substances that can adventitiously be introduced into flotation-concentration work, as it is understood at present, are excellent producers of air-occlusion.

DELETERIOUS SUBSTANCES.

A beneficial study can be made of substances deleterious to mineral-froth formation. Having performed an experiment as above described to the point of having secured a froth of, say, one inch depth, one cubic centimetre of a solution of saponin, of a strength of one of saponin to one million of water is added, and then the agitation is started. It will be observed that the froth will have completely disappeared, and cannot again be reproduced. Probably one pound of saponin introduced into the operations of the largest oil-and-gas flotation plant in the world would completely suspend all useful results for a week unless all traces of the saponin were completely removed by complete rejection of all the water

and ore that had become contaminated with saponin, and the plant would probably require a thorough scrubbing with clean water besides. Many other substances have the same effect (though not so pronounced for the small amounts used); among them are glue, starch, flour, tannin, and ox-gall. On one occasion R. Gilman Brown, consulting engineer to a mining company using the Elmore process, described a peculiar aberration of the process. On a certain day the process discontinued working for no apparent reason, and it seemed impossible to ascertain the trouble. No concentrate was produced for several shifts. He investigated to determine whether the water could contain anything deleterious, and noted that these erratic results had begun after they had changed from the ordinary brook water, which had become exhausted in the dry season, to water that had been stored in a series of small lakes and ponds in a peaty marsh. He found that there was probably enough tannin or analogous compound in the marsh water to destroy flotation, especially if the water was brown. The water was at once changed, and no further trouble ensued.

PROBLEMS SUGGESTED FOR RESEARCH.

There are a number of problems, some already mentioned, that will repay scientific investigation. A few are here mentioned:

What is the significance of the hysteresis range in the contact angle between the rising and falling meniscus?

What is the real function of acid in flotation processes?

Can a feasible scheme of flotation treatment be devised for carbonate ores?

Can a non-acid flotation treatment be devised?

What is the significance of the fact that a too strong acid medium in oil-and-gas flotation methods is fatal to good work?

Why are some of the substances that produce good air-occlusion bad flotation-concentration reagents?

Why will air not replace carbonic acid gas in the Potter process, all other conditions being equal?

What is a froth?

Would some method of producing coagulation without the aid of acid and oil enable one to introduce directly the gas-film adhesion-factor, and so secure flotation without oil or acid?

CHAPTER VI.

THE POTTER-DELPAT PROCESS.

The inventions which form the basis of this method were the work principally of two men working entirely independently—Charles V. Potter and Guillaume D. Delprat. It is another in a long line of instances where two minds arrived at practically the same scientific point simultaneously. The ideas are so similar that litigation soon developed; but, unlike many engaged in the development and application of metallurgical patents, these people soon wisely compromised. Potter had priority of patent date, and the slight differences between their processes, it must be admitted, would put a judge in a quandary. The basis of compromise was that Delprat was free to use the process in Australia, while the Potter Sulphide Company acquired all the patents and the right to license the use of the process. The amount asked for royalty in the past was 2s. 6d. per ton of concentrate, which amounts to about one shilling per ton of ore of the Broken Hill type.

After what has been said of the general theory of flotation processes, it is not necessary to give *in extenso* the whole of the principles set forth in Chapter IV. The Potter-Delprat is one of the processes making use of surface-tension phenomena. The act of flotation is accomplished by virtue of the natural adhesion of carbon-dioxide gas bubbles to particles of sulphide, and the result of the manipulation to which the material is subjected is the formation of a dense froth of bubbles and mineral, which floats at the surface of the apparatus. No substance other than acid is used in the process, as in most of the other processes for the purpose of enhancing the adhesion of gas films, but there may be organic substances in the ore which, upon the addition of acid, yield gummy organic compounds that selectively adhere to the ore. It is difficult to understand the working of this process without some such theory to account for the gummosity of the concentrate. It is worth noting that this process is the only one that secures flotation by the buoyancy of carbon dioxide gas, all the others claiming to use it alone as the active flotation gas. To differen-

tiate from the other flotation processes this one may be called an 'acid-flotation process,' or more correctly a 'carbon-dioxide gas-flotation process.' The gas is generated in the pulp by the action of hot dilute sulphuric acid, or acid salt-cake, on the carbonates which occur naturally in the gangue.

This process, as in use at the Broken Hill Proprietary mine, treats the tailing from the lead-concentrating mills. The tailing assays roughly 20% zinc, 6% lead, and 6 oz. silver. The gangue is a mixture of quartz, rhodonite, and garnet, with about 3% of calcium and iron carbonates. The last-named are of prime importance in the process. The material to be treated is taken from the




FIG. 22.—Section of Potter-Delprat Plant.

dumps and re-crushed to about 40-mesh in grinding-pans. After removal of the water used in crushing, the material is hauled to the treatment plant, where it is delivered into bins (see Fig. 22)*.

From these bins it is fed automatically into flotation vats, where the separation takes place. These vats are inverted wooden pyramids (see Fig. 23), lined with sheet lead. It will be noticed that these vats have two pockets at the bottom—one with and one without an outlet. Iron pipes introduce the solution into the vat close to the bottom, and so aid in stirring the material. One of these pipes discharges into the blind pocket A, and the

*A paper, read as a presidential address, by G. D. Delprat, before the Australian Institute of Mining Engineers, and published in its 'Proceedings' for Sept., 1906.

other into the pocket with an outlet. The blind pocket collects all heavy stones, bolts, nails, etc., which otherwise would obstruct the outlet. A 2 to 3% solution of sulphuric acid is introduced into the vat at a temperature of $82^{\circ}\text{C}.$, but as the quantity introduced is more than can run through the bottom outlet, a large




FIG. 23.—Potter-Delprat Frothing Box.

quantity passes over the top by an overflow specially arranged for this purpose. The tailing is then fed mechanically from the bin into the vat, above the blind pocket. As the material falls into the pocket it is washed over the partition B, which separates the two pockets, and the gangue passes away through the outlet. On its way down the vat, however, the acid acts on the carbonates contained in the ore, and produces bubbles of carbon dioxide gas. This gas shows a selective action, and adheres to the particles of

blende and galena, but not to the particles of gangue. The adhering bubbles cause the particles of blende and galena to float ;




FIG. 24.—Flow-Sheet Potter-Delprat Plant.

they come to the surface in the form of a dense froth, and are washed away by the current over the lip C.

The overflows of all the vats pass to one launder, which discharges into a set of wooden tanks, where on cooling the particles of blende and galena lose their bubbles of gas, and fall to the bottom.




FIG. 25.—Potter-Delprat Frothing Box.

When the tank is full, another tank is filled while the contents of the first is being drained, washed with clean water, drained again, and finally loaded into railway trucks. A flow-sheet for the process

THE POTTER-DELPAT PROCESS.



with the re-treatment of the concentrate is shown in Fig. 24.

It is found that each flotation vat can treat from 10 to 12 tons of material per hour, but three vats are generally used for this amount. The speed depends greatly on the fineness of the material. About 200 tons of concentrate is the daily product of three units, but as much as 300 tons per 24 hours has been produced by each flotation vat. Another form of vat for the same process is shown in Fig. 25.

The bottom outflow from the vats carries all the gangue with it. The solution and gangue together fall on a 3-ft. india-rubber travelling belt, with side rollers to make it into a trough. The belt runs uphill, by which means the solution is separated from the tailing and run into a sump, while the solids settle on the belt. On the arrival of the tailing at the end pulley of the belt it is sufficiently dry to be used as filling for the underground workings of the mine.

The temperature most suitable is 80°C . ; in order for each this, superheated steam at 260°C . is introduced into the solution vats, which stand on a high enough level to command the whole plant. Air-lifts are used to return the spent solution from the drained tailing and concentrate to the solution vat. One treatment only is given the material in this process, and in this regard the process has an advantage over several of the others which require repeated treatments to secure commercial recoveries.

As there are no moving parts in the plant, except the mechanical feeders and travelling belt, the cost of repairs is small. Two engines of 10 h.p. each supply all the power required, except that required for the air jets.

It was found in the experiments conducted by the Zinc Corporation that the addition of some substance that would produce a coagulated appearance to the pulp was of material benefit. Among other substances tried was resin, but the best substances for the purpose of producing this effect would be oils. This brings us back to the question of the enhancement of the inherent quality of the sulphide particles to adhere to gas films by coating the sulphide particles with films of oil, and shows the near relationship of all the flotation processes. Recent Potter patents have sought to cover this idea. It has been said that the present users of this process do not use any oil in their operations, and when I visited the plant on the Proprietary mine none was being used. At first glance it would appear that the concentrate from this process

would be readily amenable to re-treatment by concentrating tables; but the Zinc Corporation found that the concentrate had a 'gummy' or 'sticky' quality, which rendered such an operation extremely difficult. This is surprising, as the sulphuric acid or any of the salts derived from its use are apparently sufficiently soluble in the table water to render the sulphides loose and sandy. The explanation may be that the hot sulphuric acid forms with the organic matter, which is always present in tailing heaps, insoluble 'gummy' or 'sticky' compounds which exercise a preferential adhesion to the sulphides.

The apparatus and equipment of this method has arrived at a state of finality that some of the others have not reached, the reason being the great simplicity of the idea involved. The cost of the plant is obviously low. The equipment is such that it can be built on the spot from easily procured materials. Ordinary timber, with sheet lead for a lining of the flotation-boxes, is all that is needed. The cost per unit should not exceed £200, including installation.

In the early development of the process, difficulty was encountered in finding a machine or flotation-box that would save the concentrate, the trouble being that the bubbles would break and drop their load. This was overcome by Goyder & Laughton in a machine having a series of traps. Later, when it was discovered that a froth prevented the bubbles breaking, it was an easy step to see that if the flotation-boxes were crowded to a high capacity the froth itself, if produced in sufficient quantity, would act as a blanket, and so prevent the troublesome breaking of the bubbles.

APPLICATION.

BLOCK 14.—The first plant was erected at Broken Hill, on the Broken Hill Proprietary Block 14 company's mine, in 1903, to treat middling from the lead-concentrator. Aside from the small amount of zinc concentrate produced by the Sulphide Corporation by magnetic concentration, this marks the beginning of the Broken Hill zinc industry. The first machines installed were of the Goyder & Laughton type, which were of complicated design and low capacity. In 1904 the Delprat pan (Figs. 23 and 25) was introduced instead. After 1905 this plant was shut down owing to lack of material for treatment. Fig. 25A is a flow-sheet of this plant.

PROPRIETARY.—Concurrently with the above plant, in 1903, the Broken Hill Proprietary installed the Delprat process, the inventor—G. D. Delprat—being the general manager of the mine. This plant in 1904 was treating 3,500 tons per week, which was




FIG. 25A.—Flow-Sheets, Block 14, Potter Plant.

increased to 5,500 tons in 1905. During 1906 the plant treated 235,000 tons, and a system was installed whereby the material from the dumps was first sent to tables to recover some lead, delimed to provide material for sintering, and then re-ground for

the flotation process. Litigation had begun between Potter and Delprat, but was settled in 1907. By the end of 1907 this plant had produced 180,000 tons of zinc concentrate. The plant worked steadily during 1908, and produced 65,000 tons of concentrate. For five months of 1909 it was idle because of the strike, but in the remaining time produced 52,000 tons of concentrate. In 1910 the production was 70,000 tons, and in 1911 92,000 tons. The total production has been 459,000 tons of concentrate from over 2,000,000 tons of tailing treated.




FIG. 26.—Proprietary Flotation Plant.

Figs. 26 and 27 are photographs which give some idea of the magnitude of the operations. The concentrate assayed nearly 46% zinc, 8% lead, and 130z. silver per long ton. During the first half of 1910 the plant was re-modelled at a cost of £8,000 by the introduction of cast-iron flotation-boxes, presumably of the same design and principle as those shown in Figs. 23 and 25, and by the introduction of conveyors from the heaps and steam-shovel excavators.

For several years it was not possible to treat slime by this method, but an ingenious idea of E. J. Horwood has solved the

difficulty. He found that as the slime contained a large amount of finely ground calcite, the carbon dioxide gas was generated too rapidly, and the bubbles grew too fast to effectively attach themselves to the sulphides. He therefore introduced a centrifugal pump between each two of a series of separating boxes for the purpose of mechanically breaking the bubbles to small size. This violent agitation also, no doubt, assisted in coagulating the slimed sulphides; this, together with the breaking up of the bubbles, enabled the frothing to proceed on this material as easily and perfectly




FIG. 27.—Zinc-Tailing Heaps.

as upon any other class. A plant is now in operation which produces about 1,000 tons per month of concentrate from material 90% of which will pass a 200-mesh screen.

ZINC CORPORATION.—In 1905 this company began its operations by an installation of the Potter process on the British mine, where they had purchased a large dump of tailing and middling. This plant was intended to treat 2,000 tons per week. The plant ran intermittently through 1906, with many alterations, and finally the process was abandoned.

GILLIES.—The Gillies company purchased a large dump on the Block 10 mine, and erected a plant in 1906 with an estimated capacity of 2,000 tons per week. In 1907 this plant produced 7,700 tons of concentrate during the periods when it was being altered, but finally the Potter process was abandoned, and after a short trial of the Minerals Separation process the plant was dismantled and the tailing sold.

WORKING COST.

The working cost is difficult to calculate. In the Broken Hill Proprietary Co.'s half-yearly report for the period ended December 31, 1910, the tonnage is given as 179,713, and in the working account £45,213 18s. 1d., or 5s. 0 $\frac{3}{4}$ d. per ton, is charged to the zinc plant for 'wages, salaries, and expenses.' There are, however, items of electric light, machine shop, assaying, electric power, experimental account, fire account, fuel and fluxes, water, locomotive traction, and horses and drays, a portion of which should be charged to the zinc treatment. The previous half-yearly report gave 103,792 tons treated at a cost for 'wages, salaries, and expenses' of £44,999 19s. 4d., or 8s. 11d. per ton treated. The same list of other items was also given. It is a hopeless task to obtain the actual working cost of the process from these reports. We can, however, arrive at one useful deduction, namely, that 30lb. of acid was used per ton treated. The average market price of acid in Broken Hill is about one halfpenny per pound, so that the cost of acid was 1s. 3d. per ton of material treated. The sum of £4,846 was spent for water during this period. As water costs 5s. per 1,000 gallons at Broken Hill, this means 19,384,000 gallons of water was used in the operations. About 100 gallons of water per ton is the loss at Broken Hill, and these figures fit sufficiently well to justify the inclusion of 6d. for water. The heating of the pulp to 82° C. is also a charge which can be accurately deduced from a knowledge of local conditions, and amounts to nearly 6d. per ton. The power charge is practically confined to the items of pumping solutions and elevation of pulp. This charge cannot be ascertained from the published reports; an estimate would be 3d. per ton. Tabulating these and other items, the following table gives the items which concern the actual process itself, excluding all the expense of tramming, de-sliming, and grinding:

						s. d.
Power	3
Acid	1 3
Supplies	2
Labour	4
Fuel	6
Assays	1
Water	6
Superintendence	1
General	3
						<hr/>
						3 5

The acid would actually cost the company less, but is charged at $\frac{1}{2}$ d. per lb. for the purpose of comparison.

RECOVERY.

In the report for the last half of 1910 figures are given from which a fair idea of the recovery can be obtained. To do this it will be necessary to assume the metal content of the material treated. There are no authoritative figures relating to this, except in the Annual Report of the Department of Mines of New South Wales for 1904, where the Proprietary company is said to have 2,500,000 tons of tailing assaying 17% zinc, 4% lead, and 6oz. silver per long ton. This, it is believed, is too low. Using these figures, the recovery and products are as follow :

	Tons	ASSAY			CONTENT		
		Zinc	Lead	Silver	Zinc Tons	Lead Tons	Silver Oz
Feed.....	179,713	17.00	4.0	6.00	30,551	7,189	1,078,278
Concentrate	43,907	46.06	6.3	12.49	20,224	2,766	548,398
Tailing ...	135,806	7.70	3.3	3.90	10,327	4,423	529,880
Recovery %	...	66.2	38.5	50.9			
Ratio of concentration 4.1 to 1							

For the six months ended November 29th, 1911, 137,249 tons was treated, yielding 3,136 tons of lead concentrate assaying 54% lead and 28 oz. silver, and 48,192 tons of zinc concentrate assaying 45% zinc, 7% lead and 13 oz. silver. The concentrate being produced now assays 47% zinc.

CHAPTER VII.

THE DE BAVAY PROCESS.

This process is the result of the researches of A. J. De Bavay. The patents are owned by the De Bavay Sulphide Process Company, which lets the use of the process on a royalty. By a recent combination with the Minerals Separation, Ltd., these patents have been merged with those of the latter company.

De Bavay, as reflected in his early patents, was developing a process in which the surface tension of the liquid, without the extraneous aids of oil and acid, was the idea involved. The process works on the principle of the 'greased needle,' and there is none of the frothing which characterizes the Potter-Delprat, Minerals Separation, and Elmore processes. During the operation of the process there is simply a film of sulphides floating just as indicated in Fig. 10, Chapter IV. De Bavay, in the course of the development of his process, recognized the value of oil and acid as accelerating factors in surface-tension processes, and now uses oil for the same purpose as the others. The similarity in many ways of the early De Bavay patents to that of Bradford is apparent.


The first plant was erected on the mine of the North Broken Hill Mining company. This plant was altered and re-modelled many times while the process was being developed, and no complete story of these will probably ever be written, nor is it necessary. The plant did much good work all through the period of development from 1905 to 1908, when a measure of finality was reached in the methods. The process, as worked here in the later stages, is as follows: The tailing from the lead mill is first de-slimes, leaving practically a clean sandy product. The slime is discarded. The clean sand, crushed to about 40-mesh, is then fed into a mixing device, known locally as the A.Z. agitator, and mixed with cold acid solution of 0.19 strength. A photograph of the machine is shown in Fig. 28. This agitator is provided with a central tube worked with a rack and pinion for raising and lowering the upper end of the tube. The proportion of acid solution added is four or five

of solution to one of material. Thorough agitation is imparted to the mixture for a considerable time. The agitator is run at high speed for the purpose, as explained by the millman, of cleaning the surfaces of the mineral particles. This operation being completed, the speed of the agitator is reduced and the centre tube lowered so as to draw off the bulk of the solution, upon which is floating some metallic scum. When the excess of the solution has been removed, the centre tube is raised, clean wash-water added, and agitation renewed at high speed. After thorough washing, the speed of the agitator is again reduced, the excess of liquor removed



FIG. 28.—A.Z. Agitator.

as before, and a second washing effected to free the tailing of any acidity remaining. The scum of metallic particles drawn off is treated on vanners for the recovery of lead concentrate. The cleaned tailing is next conveyed to the 'oiling' vat. In this vat, which is provided with an agitator, the material is mixed with water, to which a definite proportion of oil has been added, and the whole mass thoroughly agitated to bring the metallic particles into contact with the oil. The oil is composed of one part of castor oil and four parts of low-grade kerosene; two to three pounds of oil to one ton of ore is used, and also some chlorine gas. From this oil-mixer the oiled pulp is elevated by means of a montejus and compressed air to the first tier of eighty-eight flotation cones, one of which is shown in section in Fig. 29, and in plan in Fig. 30. The material is fed to the cone at the top, and runs down over a series



SCALE OF 0 1 2 3 4 5 FEET

FIGS. 29 & 30.—De Bavay Flotation Cone.

of corrugations to the water level A, where the sulphides float at the surface of the water (Fig. 30), and pass over the lip B into the launder C. The tailing, on the other hand, sinks through the surface of the water at B, and passes down the box and out at D. It is then fed to another similar cone and box with some further recovery of sulphides, and so on to a third and fourth cone and box. Throughout this manipulation, including the acid washing, the oiling, the raising with compressed air, and the flowing over the corrugated cone, the sulphide particles are repeatedly aerated, and as a result, especially after the oiling, take up their adhesive air films and float at B in exactly the manner shown in Fig. 2, Chapter IV. The function of the chlorine may be that of gasification of the sulphide particles, or, through the formation of hydrochloric acid, it might indirectly assist by acidulating the solution; or it may have some other obscure and secondary uses. The subjecting of the oiled pulp to compressed air may be an essential part of the operation. If so, the analogy to other oil-and-gas processes is close.

NORTH MINE PLANT.—The De Bavay plant on this mine was erected in 1905, and began operation in 1906. The first unit was estimated to treat 10 tons per day, and this was increased during the latter year until the plant was treating 300 tons per week. During 1907 more or less experimental work was done, and by the close of the year £65,000 had been expended on the plant. It was then considered capable of treating 1,700 tons per week, and during the year 17,000 tons of tailing was treated. In 1908 the capacity of the plant was further augmented, and a total of 74,200 tons was treated during the year. The 22,590 tons of concentrate produced this year averaged 47.5% zinc, 7% lead, and 6oz. silver per ton. This was the best concentrate produced by any flotation process at Broken Hill, and in this regard the De Bavay process continues to hold the lead. This factor is due to the careful de-sliming of the material before treatment. In 1909, 30,000 tons of concentrate was produced, assaying 48.5% zinc, 6.4% lead, and 5.9oz. silver. This high-grade concentrate was a noteworthy product. During the first half of 1910 the plant continued operations, but in August of that year it was closed because of the new phase of operations under the ownership of the Amalgamated Zinc, Ltd.

AMALGAMATED ZINC. — This company took over the Australian rights to the De Bavay process, the mill on the North

mine, and all the tailing contracts of the De Bavay Treatment Company. It purchased further dumps, and in 1909 began the construction of a large new mill at the extreme north end of the Broken Hill district. The first section of the new mill was started in March, 1910; the second section in August, and the third in October. The capacity of the whole plant is 1,800 tons per day. A re-treatment plant, consisting of tables, was installed, and the whole or a part of the flotation concentrate is treated thereby for the recovery of lead concentrate.

The tailings which are available for treatment by this plant are as follows: From the South mine 150,000 tons from the dump, and the current production of the lead-concentrating mill for ten years, a total of 1,750,000 tons, assaying 19% zinc, 3.5% lead, and 3.5oz. silver. This material contains 5 to 6% of carbonates, and gave the other processes which tried to treat it no end of trouble. From the North mine 100,000 tons of dump tailing, and the current production for ten years, a total of 1,700,000 tons, assaying 18.5% zinc, 4% lead, and 5oz. silver. From the Block 10 mine 370,000 tons of dump tailing, assaying 18.7% zinc, 4.8% lead, and 8.7oz. silver. In comparing this plant and process with others it should be kept in mind that this material is the cream of the district. It is of high grade, and free from slime, and for this reason is the most easily treated of any zinkiferous material now being treated.

Owing to the small capacity of each of the cone units, this plant covers a large area. The cost of the plant exceeds, per unit of tonnage, that of any of the other flotation plants, being £200,000, or £111 per ton daily capacity. Some auxiliary works were included in these figures, such as sulphuric acid plant, but it is certain that the De Bavay plant proper cost in excess of £100 per ton daily capacity for a plant of 1,800 tons per day.

RECOVERY.

If one of the best month's operations is taken and the content of the material treated is calculated from the figures given in the prospectuses and Government reports and from what is known otherwise of the district, the recovery in the De Bavay process works out as given in the following tables. We are, however, in the dark as to how much material was discarded as slime, which generally is considerably richer than the original material:

	Tons	ASSAY			CONTENT		
		Zn %	Pb %	Ag Oz	Zn Tons	Pb Tons	Ag Oz
Feed	41,430	18.8	4.0	5.0	7,789	1,657	207,150
Zinc concentrate	12,108	48.6	7.2	10.3	5,885	872	124,712
Lead concentrate	216	15.3	54.0	33.6	33	117	7,258
Total concentrate	12,324				5,918	989	131,970
Tailing	29,106	6.4	2.3	2.6	1,871	668	75,180

	Zn. %	Pb. %	Ag. %
Recovery in zinc concentrate ..	75.6	52.6	60.2
„ „ lead „	0.42	7.1	3.5
Total recovery	76.02	59.7	63.7
Ratio of feed to zinc concentrate	3.4 to 1		
„ „ lead concentrate	191.8 to 1		
„ „ total concentrate	3.36 to 1		

The following table gives the tonnage treated in this plant to 1912, with the products :

YEAR	FEED Tons	ZINC CONCENTRATE				LEAD CONCENTRATE			
		Tons	Zn %	Pb %	Ag Oz	Tons	Zn %	Pb %	Ag Oz
1910	252,725	74,925	48.1	6.9	7.9	1,243	11.7	57.5	24.7
1911	483,942	141,983	48.4	6.7	9.4	2,389	14.2	54.4	32.2
1912 6 mos.	259,452	70,496	49.2	6.3	9.3	984	16.6	53.8	35.7

CHAPTER VIII.

THE ELMORE VACUUM FLOTATION PROCESS.

If water taken from an open vessel where it has been exposed to the air at ordinary temperature and pressure be confined in a glass vessel and subjected to a nearly complete vacuum, it will at once be evident that the water contained a gas in solution, because, as the vacuum increases, the gas—which in this case is air—will be seen forming in minute bubbles on the walls of the vessel, or at any other available points. At sea level and at ordinary temperature the quantity of air which open water holds in solution amounts to about 2.2% of its volume. This solution of air is explained by the law of Henry and Dalton. The amount of a gas which will go into solution in a liquid varies in general directly as the pressure and inversely as the temperature.

If we subject a pulp of acidified water and crushed ore to an operation whereby a small amount of oil has been applied to the sulphide particles in a suitable mixing vessel, and then subject this oiled, acidified pulp to a vacuum, the air in solution in the water is at once released, and attaches itself to the convenient points and angles of the oiled sulphide particles in the form of small bubbles, which gradually increase in size until they are sufficiently large to overcome by their buoyancy the force of gravity acting on the sulphide particles. When of sufficient size for this purpose the bubbles rise to the surface of the pulp, carrying along with them the sulphide particles; at the surface a froth, composed of air bubbles and mineral, forms, and is removed over a lip.

Francis E. Elmore invented an apparatus in which this operation is performed. This apparatus is unique in its features, and it is allowable to marvel at the ingenuity displayed in its invention.

The apparatus is shown in the accompanying sketch, Fig. 31. The pulp from the crushing mill flows continuously into the mixer A, into which also is introduced small quantities of oil, and, if required, of acid also, at the point B. The agitation is done by the rotation of the beaters C. The agitated pulp flows con-

tinuously from the mixer into the funnel D. The concentrate discharge-pipe E and the tailing discharge-pipe F are both sealed with water in the tanks G and H respectively. The upper end of the feed-pipe D enters the centre of the conical separating vessel I. Upon the application of a vacuum through pipe J, the pulp from the mixer is caused to ascend the feed-pipe and fill the conical chamber I. The rate of flow of the pulp down the pipe F being slightly less than that up the feed-pipe D, a small amount of the liquid overflows the lip of the annular space K, this quantity of




FIG. 31.—Diagram of Elmore Vacuum Machine.

liquid being sufficient to carry floating sulphides down the pipe E into the tank G. The rakes L are caused to rotate slowly by means of the worm and wheel M, the angle of the rake-blades being such as to cause the water-wetted gangue in the pulp to travel from the centre to the periphery of the conical chamber, whence the gangue continuously discharges down the pipe F. The feed-pipe D is usually about 25 to 30 ft. long, the tailing and the concentrate pipes E and F being a few feet longer, so that in effect the feed-pipe and tailing-pipe form the long and the short leg of a syphon; thus the power is supplied by the falling column of pulp in the tailing-pipe. So long as a continuous

flow of pulp is supplied to the mixer, a continuous and entirely automatic discharge of tailing and concentrate is secured. The annular space K is surrounded by a thick glass cylinder, or by a metal cylinder with one or more thick glass windows, through which the discharge of the sulphides over the lip of the annular ring may be observed.

Fig. 32 is a photograph of the separating vessel I. The capacity





FIG. 32.—Elmore Vacuum Machine.

of each unit is from 30 to 50 tons per day, depending on the nature of the ore. The apparatus is constructed of metal, with the exception of the glass windows, and the mixer is a simple wooden trough with wooden beaters. The power required for a 5-ft. unit is said to be 2 to $2\frac{1}{2}$ h.p., including that required for driving the vacuum pump, mixer, and separator. The apparatus is usually constructed in standard units, the conical separating chamber of which is 5 ft. diameter. Including the mixer, conical separating chamber,

THE ELMORE VACUUM FLOTATION PROCESS.



vacuum pump, all piping, etc., complete, the unit costs, f.o.b. London, approximately £350. The capacity of the apparatus naturally varies with the kind of ore to be treated, the fineness to which the ore has to be ground, and other conditions; but a 5-ft. machine will ordinarily treat from 25 to 45 tons of crude ore per 24 hours.

The cost of the plant is low for so large a capacity. No expensive foundations are required, because the beaters in the mixing cylinder only make 30 to 40 r.p.m., and the rakes in the conical separating chamber only one to two revolutions per minute. Vibration is, therefore, entirely absent. No sizing of the pulp is required, and the operation of the plant is entirely automatic.

The quantity of oil and acid required is not the same for all ores, but usually amounts to not more than a few pounds, say from 3 to 10 lb. per ton of ore treated. A large variety of oils and similar substances have been tried and found suitable: Californian crude oil, Texas crude oil, Texas residuum, fuel oil, Russian crude, Borneo, Sumatra and similar cheap oils, tars, blast-furnace oils, olive-oil residues, oleic acid, kerosene, a variety of light oils, and fish oils.

WORKING COST.

The working cost must vary with the locality and the cost of supplies and labour. For the flotation-concentration, at Broken Hill, exclusive of crushing, sizing, and any after-treatment of the concentrate, the working cost has been given as, roughly, 3s. per ton. As these figures were derived from a plant where sulphuric acid was comparatively cheap, it would be safe to take a round figure of four shillings per ton. In detail the figures referred to are as follow:

MEN EMPLOYED FOR SIXTEEN MACHINES.

Vacuum floor	I
Mixer floor	I
Discharging floor	I

Three shifts per 24 hours.

			s.	d.
Cost in grinding section	I	3.96
„ flotation section	2	4.16
„ drying section	I	3.64
„ re-treatment section		7.48
Royalty	I	0

6 7.06

THE AMOUNT OF AIR.

If the pulp was made up in the ratio of 4 tons of water to 1 ton of ore, and if the ore was of the Broken Hill type, this would be 4 tons of water to about half a ton of sulphides. The water contains 2.2% by volume of air in solution, and it may be assumed that the vacuum releases 2% by volume. Four tons of water is 142 cubic feet; 2% of this is 3 cubic feet of air released for the purpose of floating half a ton of sulphides. Three cubic feet of air loaded with sulphides to an extent just sufficient to remain in suspension would require 3 by 63 lb. of sulphides = 189 lb. of sulphides, or considerably less than half a ton. There is enough air in a pulp of 1 ton of water to 1 ton of ore to lift 60 lb. of concentrate. The following table gives the amounts of air for pulps of different proportions :

Proportion water to ore.	Cubic feet of air available in this water.	Lb. of sul- phide this will float.	Percentage of mineral in ore.
1 to 1 ..	.75 ..	60 ..	2.7
2 „ 1 ..	1.50 ..	120 ..	5.4
3 „ 1 ..	2.25 ..	180 ..	8.1
4 „ 1 ..	3.00 ..	240 ..	10.8
5 „ 1 ..	3.75 ..	300 ..	13.5
6 „ 1 ..	4.50 ..	360 ..	16.2
7 „ 1 ..	5.25 ..	420 ..	18.9
8 „ 1 ..	6.00 ..	480 ..	21.6
9 „ 1 ..	6.75 ..	540 ..	24.3
10 „ 1 ..	7.50 ..	600 ..	27.0

As the proportion of water to ore rarely exceeds 6 to 1, and as the ores treated generally yield more than 16% of concentrate, it will be seen that some gas other than that naturally dissolved in the water must be found to effect flotation. This is generally secured by adding limestone to the ore, and then acid at the point where the pulp enters the vacuum chamber. It would be interesting to investigate whether, by limiting the quantity of gas available for froth production, it would be possible to secure differential flotation between lead and zinc sulphides. This machine seems especially adapted to the development of this idea.

APPLICATION OF THE PROCESS.

A large number of trials, both on a small scale and with a full-sized apparatus, have been conducted on a great variety of

ores, but it is not claimed that the process and plant are applicable to all ores, although its scope of application is wide.

The process has been applied with success to the concentration of ores which, because of their peculiar characteristics, are quite impossible of concentration by usual methods. For instance, chalcopyrite is readily separated from magnetite and spathic iron gangue; galena and zinc blende from a gangue of barite; and copper sulphides from oxide of tin, leaving the tin in the tailing to be subsequently separated by the usual methods. Zinc, copper, and lead minerals may be separated from garnet and similar heavy gangue; and such minerals as antimony or molybdenum sulphides which, because of their friable nature, suffer prohibitive losses in water concentration, are found amenable to treatment by the Elmore process. Cinnabar and iron pyrite carrying gold are readily concentrated, yielding high-grade products with practically clean tailing. The native metals, gold, silver, and copper, when in a fine state of division, are said to concentrate readily and with very small loss.

Continuous working has shown that the plant is eminently practical; no delicate adjustments are required, wear and tear is to all intents a negligible quantity, and the excellent mechanical design and substantial construction of the apparatus have made breakages almost unknown.

DOLCOATH, CORNWALL.*—In certain parts of this mine the ordinary tin ore of Cornwall is found impregnated with varying proportions of sulphides, principally of copper. This ore is crushed in an Edgar Allen ball-mill, and passed direct to one Elmore vacuum unit. By this operation almost the whole of the sulphides are recovered as a high-grade copper concentrate, which is saleable as such. This concentrate contains a remarkably small proportion of tin, on the average probably not exceeding 2 to 3 lb. of tin per ton of concentrate. Substantially, the whole of the tin oxide is left in the tailing from the vacuum unit. The tailing is subsequently treated by Frue vanners, etc., in the ordinary way for the recovery of the tin oxide. The oil and acid used in no way injuriously affect the subsequent recovery of the tin. This plant was supplied to the Dolcoath company in March, 1907, and yielded highly satisfactory results for some time, giving an

**Engineering & Mining Journal*, December 14, 1907, by Edward Walker.

extraction of over 90% of the copper contents, but the plant is not now in use.

RAMSLEY MINE, DEVONSHIRE.—Here the ore consists of a mixture of chalcopyrite and bornite with some chalcocite in a slaty micaceous gangue. The average grade of the crude ore is about $2\frac{1}{2}\%$ copper. It is crushed in stone-breakers, high-speed rolls, and a Huntington mill in the usual way, the pulp being sent direct to one unit of Elmore plant. On the average the concentrate produced assays about 12% copper.

DOLGELLY MINE, NORTH WALES.—The ore consists of chalcopyrite with varying proportions of iron pyrite in a schistose gangue. The grade of the ore is usually about 1.2% copper, 0.08oz. gold, and 0.8oz. silver per ton. The ore is crushed by a reciprocating stone-breaker, followed by a 20-head Californian stamp-battery (1,050lb.), through 6-mesh screens. The pulp from the battery is sized on a 16-mesh screen, and the oversize re-crushed in a grinding pan. The pulp is then sent direct to 3 Elmore units, and yields a concentrate of about 12% copper, 0.7oz. gold, and 7oz. silver per ton, the tailing assaying about 0.25% copper, with very small amounts of gold and silver. Prior to the installation of the vacuum plant, much money had been spent at this mine on various forms of water-concentration machines; but, owing to the extreme softness of the copper mineral and the unusually tough character of the rock, the loss of fine material was always prohibitive.

ZINC CORPORATION.*—The material treated here was a zinc tailing from the lead-concentration plants. The gangue consists largely of quartz, garnet, and rhodonite, being of practically the same specific gravity as the blende with which it is associated; hence no separation by ordinary water-concentration was possible. Much of the tailing on the dump was already fine enough for direct treatment in the Elmore plant; that portion that was too coarse was crushed in 12 grinding pans, sized on improved revolving screens, the oversize being re-crushed in six additional grinding pans. The average assay of the material treated in this plant was about 19% zinc, 5% lead, and 8oz. silver per ton. This yielded a concentrate assaying on the average about 43% zinc, 11% lead, and 17oz. silver per ton. It was found that, if this concentrate was dried and subjected to a sufficiently high tempera-

**The Mining Journal*, February 20, 1909, by A. Stanley Elmore.

ture to expel the small quantity of oil which it contained, the de-oiled concentrate could then be mixed with water and passed over Wilfley tables, yielding a zinc product assaying 46% zinc, 6.1% lead, and 13oz. silver per ton, and a lead concentrate assaying about 57% lead, 16% zinc, and 37oz. silver per ton. The assay of the final residue depended, to a great extent, upon the more or less oxidized condition of the mineral, much of the material on these dumps having been exposed to atmospheric oxidation for many years; but the following may be taken as fairly representative: Zinc, 5.90%; lead, 2.5%; and silver, 4oz. per ton.

Fig. 33 gives a condensed flow-sheet of the arrangement of this mill, including crushing, sizing, flotation, and re-treatment on Wilfley tables. The plant contained 16 units, and was installed only after exhaustive trials had been conducted with one unit. The mill was in continuous operation for two years, and gave a higher capacity, better grade of concentrate, and greater percentage of extraction than was indicated by the trials with the one-unit plant.

The following table gives the total tonnage treated from the beginning of February, 1908, to the end of July, 1911, inclusive, with the results:

FEED		Tons	714,399
	Assay {	Per cent. Zn	19.1
		oz. Ag	7.9
		Per cent. Pb	5.5
FINAL ZINC CONCENTRATE		Tons	241,710
	Assay {	Per cent. Zn	46.0
		oz. Ag	13.34
		Per cent. Pb	6.63
FINAL LEAD CONCENTRATE		Tons	20,639
	Assay {	Per cent. Zn	15.84
		oz. Ag	36.76
		Per cent. Pb	56.57
ZINC SLIME		Tons	7,977
	Assay {	Per cent. Zn	38.85
		oz. Ag	21.11
		Per cent. Pb	13.55
RESIDUE		Tons	452,050
	Assay {	Per cent. Zn	4.88
		oz. Ag	3.67
		Per cent. Pb	2.59

PERCENTAGE DISTRIBUTION.

FEED	Per cent. ..	100
FINAL ZINC CONCENTRATE ..	Per cent. Weight ..	33.8
	Zn	81.4
	Ag	57.1
	Pb	40.6
FINAL LEAD CONCENTRATE ..	Per cent. Weight ..	2.9
	Zn	2.4
	Ag	13.4
	Pb	29.6
TOTAL CONCENTRATE ..	Per cent. Weight ..	36.7
	Zn	83.8
	Ag	70.5
	Pb	70.2
RESIDUE	Per cent. Weight ..	63.3
	Zn	16.2
	Ag	29.5
	Pb	29.8




FIG. 33.—Flow-Sheet of Elmore Plant.

The Elmore process has now been discarded for reasons before given, and the Minerals Separation process installed in its place.

EDMUNDIAN COPPER MINE.—The ore at this mine in South Africa consists of chalcopyrite finely disseminated through a felspathic gangue. It is crushed by stone-breakers and Holman pneumatic stamps, and passes direct to a two-unit Elmore plant. The ore assays on the average about 2.5%, and yields a concentrate assaying about 22.5%, with a recovery of 85%.

GARPENBERG MINE, SWEDEN.—The ore consists of a quartzitic gangue with some magnetite carrying chalcopyrite and iron pyrite. The ore, although fairly heavily mineralized with iron pyrite, is of low grade, assaying on the average about 1% copper. The crushing plant consists of a stone-breaker, followed by rolls, the product going to jigs and tables in the ordinary way. The fine tailing, together with the jig tailing after re-crushing in wet ball-mills, is treated in the vacuum machines. One unit of plant was tried first ; later two more were installed, but the plant is now closed.

TRAAG MINE, NORWAY.—The ore carries both zinc and lead associated with a heavy gangue. After crushing in stone-breakers and in an Allis-Chalmers Anaconda-type Huntington mill, the pulp is treated on Wilfley tables for the production of a lead concentrate. The tailing from the Wilfley table is passed to a one-unit Elmore plant, which yields a concentrate assaying on the average 58% zinc. The zinc sulphide in the ore is present in the form of a very friable resin blende, and, in consequence of excessive sliming, coupled with heavy gangue, could not be collected by any ordinary water concentration appliances. This plant has now ceased working.

HADELAND MINE, NORWAY.—The ore consists of blende associated with a large proportion of magnetite and some spathic iron. Trials with various water-concentration appliances had all proved unsatisfactory. The ore is crushed in Krupp ball-mills, and sent direct to the Elmore plant. It yields a high-grade concentrate with a satisfactory extraction. The company, after having operated the one-unit plant for about six months, has ordered additional units.

TELEMARKEN MINE, NORWAY.—The ore consists of chalcopyrite and bornite in a gangue composed of hornblende, micaceous schist, and hard quartz. The crude ore from the mine is hand-sorted with a view to rejecting some of the waste. The ore thus enriched assays on the average about 4.5% copper. It is crushed in a No. 5 Gates crusher, followed by Ferraris wet ball-mills. The pulp is sent direct to a three-unit Elmore plant, from which a concentrate assaying about 26% copper is obtained, the final tailing containing only 0.20%, thus giving a recovery of about 95% of the total content. Fig. 34 shows a section of the vacuum plant, and Fig. 35 a flow-sheet of the plant at this mine.

SULITELMA MINE, NORWAY.—The ore carries copper in the

form of chalcopyrite associated with a large proportion of iron pyrite, the gangue being micaceous schist. As the ore comes from the mine it is crushed in large stone-breakers, and carefully hand-sorted with a view to selecting clean lump pyrite, which is sold to sulphuric acid works for its sulphur content, the burnt ore





FIG. 34.—Section of Elmore Plant.

being subsequently treated for its copper content. The low-grade ore left after hand-sorting is crushed in rolls and passed to jigs, tables, and vanners. This water-concentration plant is of first-class design, operated with good labour and under excellent technical supervision and control. Nevertheless, the loss of copper in the tailing is heavy owing to the friable nature of the copper pyrite. The residue from this water-concentration plant



FLOW SHEET
TELEMARKEN MINE, NORWAY.

FIG. 35.

varies in grade from 1 to $1\frac{1}{4}\%$ copper, with a quite considerable proportion of iron pyrite and some magnetite. The concentration mill handles about 800 to 900 tons a day, and produces about 500 to 600 tons a day of tailing. This tailing is in the form of an unusually dilute pulp, the proportion of water to solid being probably 100 to 1. At the present time about 400 tons of solid per day with the above proportion of water is sent to the 12-unit Elmore plant for the recovery of the copper mineral. Arrangements are being made which will enable the whole of the 500 to 600 tons of tailing from the water-concentration plant to be sent to the Elmore plant. The small part of the tailing, which is too coarse for treatment direct in the Elmore process, is re-crushed by Heberle ball-mills. The pulp, which, as before stated, is associated with an immense amount of water, is run into large settling-tanks with a view to getting rid of the excess of water before treatment in the Elmore plant. Concentrate varying from 6% up to 11% of copper (the grade depending upon the proportion of iron pyrite) is produced. The final tailing assays on the average 0.2% copper. The great bulk of the material handled by the vacuum machines consists of absolute slime. An average of about 250 tons of concentrate per week is produced from waste material which had previously been discharged direct to the tailing dump. Six additional machines have been delivered to this firm, and will shortly be erected at one of their other mines.

SAXBERGET MINE, SWEDEN.—The ore here is a mixed zinc-lead-silver material, which, after crushing in stone-breakers and wet Grondal ball-mills, is treated on tables for the recovery of the lead. The lead recovery, however, is not good, and consequently the tailing from the tables contain notable proportions of lead and silver in addition to the zinc. Various attempts had been made previously to treat the tailing without success. The Elmore plant produced a mixed lead-zinc-silver concentrate, which was subsequently smelted in an electrical furnace. Its use has been discontinued and a Minerals Separation plant of 125 tons per day capacity is at present in operation.

Other Elmore plants have been installed in several places, but data as to results are not available.

CHAPTER IX.

THE MINERALS SEPARATION PROCESS.

This process represents the joint efforts of Sulman, Picard, and Ballot, and various improvements in processes and apparatus have been added at different times by Froment, Cattermole, Sulman, Picard, Ballot, Higgins, Chapman, Lavers, Greenway, Nutter, Hoover, and others of a large staff. The owner of all these patents is the Minerals Separation, Ltd., a company, the special province of which was intended to be the development of flotation processes. The company licenses the use of the process.

The application of this process to a typical Broken Hill zinkiferous material will be described. This material is the tailing from the lead-concentrating mills after the major part of the lead has been removed by gravity-concentration. Mineralogically, the material has approximately the following composition :

					Per cent.
ZnS	27.1
ZnSO ₄	2.4
PbS	6.4
PbSO ₄	1.3
FeS ₂	2.5
MnCO ₃	4.6
CaCO ₃	3.2
SiO ₂	42.4
Total					89.9

The balance of the 100% is made up mostly of garnet and rhodonite and a complex carbonate containing iron, calcium, zinc, and magnesium. The blende is 'black jack' of about the following composition :

					Per cent.
ZnS	81
FeS ₂	14
MnS	3

The average assay of the material to be treated by flotation is :

Zinc	14 to 20%
Lead	6%
Silver	7.5 oz. per long ton.

It is necessary to crush this material to about 40-mesh for three reasons : (1) Larger particles float with reluctance ; (2) the sulphides must be freed from the gangue ; (3) crushing has a brightening effect on the sulphide particles.




FIG. 36.—Hoover Frothing Machine.

In this process wide limits as to the amount of slime produced in crushing are permissible. A certain amount of slimed sulphides is absolutely essential to the best frothing result ; but there seems no upper limit beyond which fine crushing is deleterious. One plant worked successfully on material 95% of which would pass a 100-mesh screen. After the ore is crushed to the requisite fineness it is de-watered to a pulp as near as may be three of water to one of ore, this proportion having been determined by a series of trials extending over several years to be the most likely to produce good results under the other conditions imposed.

After de-watering, the pulp is run into an apparatus designed by the author, and patented for Minerals Separation, Ltd., owners of this process, in British Patent 4911 of 1909. The original form of the apparatus was as in Fig. 36, but several improvements were made later. In order to understand the later form it will be easiest to begin with a description of the original apparatus. This consisted essentially of three mixing and agitating compartments joined to a modified spitzkasten. The three mixing compartments were connected together by apertures A_2 at the bottom of the partitions A_1 . These apertures can be of almost any shape as long as the area of the aperture is within certain wide limits. The right-hand mixing compartment is connected with the spitzkasten by the aperture A_3 similar in all respects to the aperture A_2 . At J is a horizontal lip, which maintains a water-level, and at H is an outlet which is of such a size that there will always be an overflow over J. The agitators B are driven by belts or gears and should travel with a peripheral speed of about 1,200 or 1,300 feet per minute. This will cause the liquid pulp in the compartments to line the sides of the compartment about half-way to the top, and at the centre of the compartment the water-level will be considerably lower than it is in the spitzkasten. Fig. 37 is a longitudinal section of the three mixers and spitzkasten, and shows the position assumed by the water during operation. At K is a baffle over which the pulp must flow, the edge of K being a few inches below the water-level J, this distance depending on the size of the plant and other factors, the outside limits being 2 and 8 inches. At D is an apparatus for feeding acid, and at E is an apparatus for feeding oil.

The 3 to 1 pulp is fed into the compartment to the left of Fig. 36 at C, and along with it are fed in also, say, 2lb. of oil and 10lb. of sulphuric acid to the ton of ore. Live steam is also introduced into this compartment through a pipe (not shown) in sufficient quantity to raise the temperature of the pulp to 70° C. Owing to the speed of the agitator these ingredients are thoroughly mixed; in fact, they are churned violently. Large quantities of air are beaten into the pulp. By running the machine for a few minutes on water alone it will be observed that the quantity of air so beaten into the pulp is enormous, for the clean water will be milk-white. As the inflow of pulp is continuous, the outflow from the left-hand compartment into the middle compartment is also continuous and of equal volume. In the middle compartment

the pulp receives a further violent agitation, and then passes continuously into the right-hand compartment to be agitated once more. From the right-hand compartment the froth emerges through A_3 into the spitzkasten over the baffle K . The rate at which the pulp passes over the baffle K is exactly the same as that at which it is fed at C . As the pulp emerges from A_3 a dense froth, composed of sulphides and bubbles of gas, immediately rises to the surface, where it floats along to J , and passes over into the launder G , and so to the bins. The gangue, on the other hand,




FIG. 37.—Diagram of Water Levels.

does not float, but just manages to get over the baffle K , and then drops to the tip of the spitzkasten, and is removed at H .

A single box of the above description will not give a perfect extraction, and it is necessary to give the pulp a second and third treatment in a similar box with less agitation. This can be done by simply building three sets like that shown in Fig. 36, and placing them one under the other as in Fig. 38. A set of boxes of this design, with mixing compartments 3 by 3 feet and a spitzkasten 4 by 5 ft., will treat 400 tons of this material per day, and will make something over 150 lb. of clean zinc concentrate per minute.

Instead of placing three sets of this kind one above the other, a much simpler mechanical arrangement can be made which saves





FIG. 38.—Arrangement for Re-treatment.

head-room, floor-space, and labour in operation ; and as this is the form of apparatus most recently installed by the Zinc Cor-

poration, and represents the latest development in the process, it will be described at the risk of some repetition. These ideas were also patented for the Minerals Separation, Ltd.

This arrangement of plant makes use of the centrifugal effect of the agitators, and uses them partly as pumps. Referring to Figs. 39, 40, and 41, which are elevation, plan, and section of the




FRONT ELEVATION.

FIG. 39.—Hoover Single-Level Apparatus.

latest arrangement, A, B, C, D, E, and F are mixing compartments, each containing an agitator running at high speed; X, Y, and Z are spitzkastens. The ore, water, oil, acid, and steam are fed into the compartment A in proper proportions, where the pulp is thoroughly mixed and violently agitated; A has a hole at the bottom, which allows the pulp to pass into B, where there is more violent agitation; B has a hole in the bottom, which allows the

pulp to pass into C and from C goes over a baffle into the spitzkasten X, where a heavy, dense mineral froth is floated over the lip of X; the gangue, along with some of the sulphides, passes to the tip of the spitzkasten X, the tip being connected by a pipe M with the bottom of D. The agitator in compartment D acts as a centrifugal pump, and draws the material from the tip of X up into compartment D, where the pulp receives further agitation and aeration. The lift required of this pump is very




PLAN

FIG. 40.—Hoover Single-Level Apparatus.

slight, for it will be observed that there is one liquid level throughout the whole of this combined arrangement; the agitator pump in D has to pump against a head which is practically only the friction head of the system. From D the pulp passes to E, where further aeration by agitation is given; from E the pulp passes over a baffle into the spitzkasten Y, the froth flowing over the lip of Y and the gangue with a little remaining sulphide dropping down to the tip of Y; the tip of Y is connected by a pipe N with the bottom of the mixing compartment F, and the agitator in F acts

as a pump to draw the pulp up into F. Here the head on the pump is only the friction head, and as in the case of M, N is also the suction side of the centrifugal pump. The pulp gets further agitation in the mixing compartment F, and finally emerges over a baffle into the spitzkasten Z, where the last available



— **SIDE ELEVATION.** —

FIG. 41.—Hoover Single-Level Apparatus.

mineral froth passes over the lip, and the gangue drops down to the tip, from whence it is drawn through a regulated opening and passes to the tailing flume. A perspective drawing of this plant is also shown in Fig. 42, which may help to understand the scheme.

This plant has the merit of extreme compactness. One unit of 400 tons per day capacity would occupy a floor space of less

than 30 by 10ft., and less than 12ft. of vertical height. The whole operation is in front of one man, and the labour required is so reduced to a minimum. By placing two units front to front, one operator should watch the treatment of 1,000 tons per day. These agitators take 5 h.p. each for a plant of 400 tons per day capacity, and on most ores six agitators would be ample. Some ore would probably require that the agitators be arranged first a set of three followed by a spitzkasten; then a set of two followed by a spitzkasten; and lastly, one agitator followed by a spitzkasten. Other forms consist of one agitator for each of eight spitzkastens, and variations of connections in each case depending on the nature of the ore.




FIG. 42.—Hoover Single-Level Apparatus.

In most flotation plants, whether using this process or the others previously described, it will be found of decided advantage to use the water over and over again, as there is some latent acidity always in solution after the flotation is complete, and besides, the salts in solution have a beneficial coagulating effect. If the salts in solution increase to beyond 4,000 grains per gallon, the millmen have acquired the idea that it has a detrimental effect on the flotation, but this does not seem to be based entirely on sound reasoning; the detrimental effect is probably an indirect result of salts in solution, and could be obviated by proper manipulation.

One of the recent improvements in this process is by way of

using as a froth-producing agent a soluble substance to replace the insoluble oil formerly used. The soluble substances which are available for this purpose are: Alcohols, especially amyl alcohol and some of its soluble salts, such as amyl acetate; all the phenols and their near derivatives; the turpentine and many of the products from the destructive distillation of wood; most of the essential oils, and especially the oil from *eucalyptus amygdalena*, one of the most common eucalyptus in Australia. This last is probably the best of all, and as the quantity used is less than a pound per ton of ore, the high price of the oil does not hinder its use. One decided advantage of using these soluble frothing agents is that where a subsequent treatment of the concentrate is desired for the separation of lead and zinc sulphides, it can be treated directly on tables. Where an insoluble oil was formerly used it was necessary to burn this insoluble oil, as it made the sulphides gummy, and they could scarcely be separated by gravity.

The following figures give the dimensions of units of various sizes. Part of this information has been derived from actual observation, and part is deduced from the known behaviour of the process under given conditions. No doubt further work with the process will modify the ideas as to size, even if the form is maintained as at present.:

Estimated daily capacity.		Tons. 50-60	Tons. 100	Tons. 200	Tons. 300	Tons. 500
Agitators	Number ...	6	6	6	6	6
	Diameter, inches ...	12	14	16	18	24
	Height of web, inches ...	2	2	2½	2½	4
Agitator	Number ...	6	6	6	6	6
	Diameter, inches ...	1¼	1½	1¾	2	2½
	r.p.m. ...	440	380	335	300	225
Mixing boxes	Number ...	6	6	6	6	6
	Width, inches ...	16	18	22	25	36
	Depth, inches ...	36	40	37	43½	54
Spitzkastens	Number ...	3	3	3	3	3
	Width, inches ...	16	18	22	25	36
	Depth, inches ...	51	58	62	62½	78
	Length, inches ...	39	42	45	48	54
Openings from	Number ...	3	3	3	3	3
Mixers to Spitz-	One into each spitzkasten.					
kastens	Dimensions, sq. in. ...	18	25	32	36	48
	Height above floor of mixer, inches ...	2	2	2	2	2
Main driving-shaft	Number ...	1	1	1	1	1
	Diameter, inches ...	1½	2	2½	2½	2¾
	Speed ...	288	250	220	96	363
Driving-shaft pulleys	Number ...	6	6	6	6	6
	Diameter, inches ...	12	16	20	24	32
	Width, inches ...	4½	6	6½	9	11
Return pipes from Spitz to next mixer	Number ...	4	4	4	4	4
	Diameter, inches ...	2	2½	3	3½	4

A further improvement to this apparatus, that eliminates all pipes, pumps, and valves, and makes the process practically independent of the operator, is illustrated below. The apparatus and its application to flotation processes will be sufficiently clear from the following descriptions, and Figs. 43, 44, and 45, which are elevation, plan, and section of the new machine :




FIG. 43.—Elevation Hoover Valveless Apparatus.




FIG. 44.—Plan Hoover Valveless Apparatus.

The ore is fed in at A (Figs. 44 and 45), along with water, oil, and acid, and after a period of agitation and mixing, emerges at the opening B into the flotation-box C. A portion of the sulphides floats and is removed at the lip D. The remainder of the sulphide with the gangue, etc., is drawn through the hole E

into the mixing-compartment F, whence, after further agitation, it is discharged from the hole G into the flotation-box H, where more floating sulphides are removed at the lip I, and so on through the whole series, alternately agitating and taking off a froth, until the last frothing-box J, where the gangue-sand fully depleted of sulphides is withdrawn at the valve K. The agitators in the mixing-compartments should run at a peripheral speed of about 1,500 linear feet per minute.




FIG. 45.—Section Hoover Valveless Apparatus.

Another form of apparatus which has many advantages of simplicity is shown in Figs. 46, 47, and 48. In this case the pulp moves in a straight line through the whole series, receiving successive agitations at A, A, A, and yielding froths at B, B, B, which froths are drawn off at the lips D, D, D. At C is a valve and pipe which regulate the outflow of the tailing and the height of water in the whole series. The agitators in the mixing-

compartments A, A, A should run at a peripheral speed of about 1,500 linear feet per minute. In B, B, B there are slow-moving agitators to keep the sand slowly in motion; these should run at 10 to 20 r.p.m., but not fast enough to break the surface of the water. On some ores the agitators may not be needed in B, B, B, etc.




FIG. 46.—Elevation Hoover Valveless Apparatus.




FIG. 47.—Plan Hoover Valveless Apparatus.




FIG. 48.—Section Hoover Valveless Apparatus.

OLD GRANULATION PLANT.

The first mention of the Minerals Separation process is in the Annual Report for the Department of Mines of New South Wales for 1904, where it is recorded that the Sulphide Corporation had

been experimenting with an oleaginous process, and that a plant would be erected in the following year. In 1905 the process was described as being either one where the mineral was coagulated and sunk, or where a small amount of oil was used to make the mineral float. At this plant the patents of the company had their first practical application. During 1905 the Cattermole idea was abandoned, and the plant was altered to a flotation-process plant, and operated as successfully as could be expected in a plant which had undergone so many vicissitudes. The work here in 1907 served as a model for the Zinc Corporation in their first trial of the Minerals Separation process, but they were not able to duplicate the results, and as a result abandoned the Minerals Separation, and installed the Elmore process. The plant continued operations during 1907, but was finally closed in 1908. The material treated was typical Broken Hill dump-tailing from the lead-concentrating mills, and the three years' operations are here shown.

YEAR	Tons	FEED ASSAY			Tons	CONCENTRATE ASSAY			RECOVERY		
		Zn	Pb	Ag		Zn	Pb	Ag	Zn	Pb	Ag
		%	%	Oz		%	%	Oz	%	%	%
1906	23,709	20.4	6.4	7.4	8,013	44.0	11.8	14.8	72.8	62.1	67.3
1907	65,705	21.0	5.6	7.0	20,621	45.2	9.7	13.4	67.7	54.2	60.7
1908	46,394	20.4	5.6	7.0	16,513	45.1	9.5	13.8	78.7	60.0	69.6

This plant at periods gave much better results than the average, and subsequent work elsewhere with the process justified the confidence of the engineers in its merit.

SLIME PLANT.

In 1906 the Minerals Separation, Ltd., purchased from the Block 10 company 60,000 tons of high-grade slime, and began the erection of a plant to treat this sort of material on a joint arrangement with the Sulphide Corporation, which company had large dumps of the same sort. This venture was one of the most interesting in the history of the application of flotation processes. The material treated is practically all finer than 100-mesh, and 82% was finer than 200-mesh. The plant was built in 1907, and it was originally intended to re-treat the flotation-concentrate on tables, and separate the lead sulphide from the zinc sulphide. This re-treatment scheme failed, however, and there being at that time no market for the mixed concentrate, the

THE MINERALS SEPARATION PROCESS. 125

plant was shut down. During 1909 there was some demand for the mixed product on the part of zinc buyers and for experimental smelting* work on mixed sulphides, and the plant was run for a time. In 1910 a market was opened in Norway for mixed lead-zinc concentrate, and the plant was operated long enough to fill a contract. The three years' operations are shown in the following table :

YEAR	Tons	FEED ASSAY			Tons	CONCENTRATE ASSAY			RECOVERIES		
		Zn	Pb	Ag		Zn	Pb	Ag	Zn	Pb	Ag
		%	%	Oz		%	%	Oz	%	%	%
1908	4,382	20.9	17.9	17.2	1,912	25.0	26.0	33.1	69.1	62.9	63.6
1909	2,179	19.7	16.8	19.3	1,109	32.5	21.4	28.2	84.0	64.7	74.6
1910	18,395	20.7	17.6	20.8	10,164	32.2	22.4	29.6	85.8	70.5	78.6

It is safe to say that such excellent recoveries on such a slimy material in a concentrate practically pure sulphide were never before secured by any form of mechanical concentration.

NEW CENTRAL MILL.

During 1906 there was under construction a new concentrating mill on the Central mine at Broken Hill, which was so designed that it should receive the ore by bucket-tramway from the mine, and turn out finished lead concentrate from the lead section ; and then, taking the tailing from the lead section, treat it by the Minerals Separation process, and produce finished zinc concentrate, all in one continuous operation.† Two units of the Minerals Separation process of the old type were installed in the zinc section, and the plant started in 1907. Fig. 49 is a flow-sheet of this plant. In 1908 the plant operated continuously with good results, although the concentrate produced from this plant was not of so high a tenor in zinc as the other plants, because of the high iron sulphide content of the ore, and also, perhaps, because some of the gangue minerals have a greater tendency to float when freshly crushed than after they have lain in the dumps for some time. In 1910 alterations in the type of machine were made, and mixing and frothing boxes of the type described in the beginning of this chapter were installed. The capacity of the plant was thereby increased. The tailing is taken from the lead section with all the mill water, and is first drained on a belt, and then the slime goes

**Engineering & Mining Journal*, Vol. xc., 1910, August 13, p. 323-324.

† 'Annual Report for the Department of Mines of New South Wales for 1906,' p. 89.




FIG. 49.—Flow-Sheet Central Mine Plant.

to tanks to settle. From the tanks and the draining-belt the material is fed by belt-conveyors to the flotation section, where the treatment is as previously described. No crushing is required, as the material is sufficiently fine from the lead operations.

Fig. 50 is a photograph of the dump. The results of the four years' work are given in the following table. The columns showing the zinc content of the concentrate and the recovery columns are a fine study in persistence. It was difficult to account for the grade of concentrate being low in this plant for the first two years. The table shows the improvement.




FIG. 50.—Tailing Heap of Central Mine.

YEAR	Tons	FEED ASSAY			Tons	CONCENTRATE ASSAY			RECOVERY		
		Zn	Pb	Ag		Zn	Pb	Ag	Zn	Pb	Ag
		%	%	Oz		%	%	Oz	%	%	%
1906-7	28,275	19.3	6.3	8.6	6,894	36.9	12.6	15.1	46.5	49.3	42.5
1907-8	157,142	20.5	6.1	9.1	54,842	40.4	13.1	17.7	68.9	75.7	67.6
1908-9	157,907	21.4	6.0	8.6	67,981	42.5	11.4	16.6	85.5	82.5	83.8
1909-10	227,126	20.7	6.1	6.8	88,767	43.5	11.2	14.0	82.2	72.0	80.5
1910-11	186,070	19.3	5.6	7.1	71,667	42.7	10.9	14.7	85.4	74.8	80.1
1911-12					69,326	46.3	8.7	16.0			

Several thousand tons of slime from the dumps has been treated in this plant, in addition to the slime in the material coming from the lead mill. In July, 1911, a re-treatment section was started; and, in addition to the zinc concentrate produced in the last year, there was recovered from the lead-mill tailing 2,941 tons of lead concentrate assaying 48.10z. silver and 61.4% lead.

MINERALS SEPARATION, LTD.

In 1906 this company bought a large dump of lead-mill tailing from the Sulphide Corporation, and during 1907 a plant was constructed.* Profiting by lessons learned from earlier experiences, this mill did good work from the start, and has treated nearly 560,000 tons of dump material assaying 20% zinc, 6.2% lead, and 5.9oz. silver, and produced 218,000 tons of concentrate assaying 47.3% zinc, 9.8% lead, and 110z. silver. No re-treatment of the concentrate is given in this plant. The cost in this plant over a typical period was as follows :

					s.	d.
Tramming		6.48
Crushing	1	8.45
Flotation	4	5.84
Disposal of concentrate				6.62
„ tailing				4.46
Total	7		7.85

Of these items the one for 'flotation' is of chief interest, and is made up as follows :

					s.	d.
Power		5.47
Acid	1	0.13
Oil		6.48
Supplies		5.18
Labour and salaries				3.06
Fuel for heating			5.16
Assays		1.22
Water		3.20
Repairs (labour and supplies)		..				6.31
General expense			5.63
Total	4		5.84

ZINC CORPORATION, LTD.

This company tried the Minerals Separation process in 1907, after abandoning the Potter process. The Minerals Separation process was rejected in turn, and the Elmore process installed, which latter process was used successfully for two years, when the

**Engineering & Mining Journal*, April 30, 1910, p. 913, 'Oil Process at Broken Hill.'

Minerals Separation process was again adopted at the beginning of 1911. The Minerals Separation process had shortly before this time been considerably improved as regards its mechanical operation, and had demonstrated its adaptability to the slimiest material.

The cost for a typical period is as follows :

					s.	d.
Tramming	1	4.78
Grinding	1	3.41
Flotation	4	3.79
Re-concentration			8.97
Handling concentrate				4.94
Handling tailing			4.13
General expenses			8.72
						<hr/>
Total	9	2.74	

Of these figures the one for 'flotation' is of chief interest, and is made up as follows :

					s.	d.
Power		1.74
Acid		9.10
Oil		6.00
Supplies		3.50
Labour and salaries				2.22
Fuel for heating			5.42
Assays		0.30
Water		1.50
Repairs		8.90
Royalty	1	1.11
General expense (half)				4.36
						<hr/>
Total	4	8.15	

In all the company owns 27 dumps, most of which are either of a refractory nature, or are slime dumps ; and, seeing that all have to be removed by a given time, it is necessary to take a certain amount from each.

The cheapest and easiest way of removing these dumps is an important problem. At first sight a mechanical means of handling the tailing suggests itself, but as only a small portion of the daily tonnage treated is taken from each dump, it would never pay to

incur a heavy capital expenditure on a mechanism which would be worked considerably under its capacity. As these dumps are scattered over a large area, extending from the north to the south end of the Broken Hill district, the material is hauled (with the exception of the South mine tailing-dumps, which have been equipped with an aerial tram) by the Silverton Tramway Company in its railway trucks. A tram-track is laid into each of the dumps, and at a height a little above the top of the truck a loading gantry or staging is erected; this staging is hinged on the dump side of the track, and can be lifted by means of a small block and tackle to allow the locomotive to pass. The trucks supplied by the Silverton Tramway Company are strong iron cars of the box type, 15-ton capacity, 15ft. by 7ft. 6in., with doors at each side opening in the centre about half the length of the side, leaving a quarter standing vertical at each end. These trucks are certainly not the most suitable type, and entail much labour to empty, all of which has to be done by shovelling. A gang of men (the transport gang) are kept constantly employed at this class of work; and, in addition, they unload all coal, mine stores, etc. As the dumps are so scattered, the company is compelled to lay quite a quantity of tracks both to the dumps and at the works, which at the present time amounts to 22,000ft. The tramway company has set (subject to approval) a time-table each week, stating the number of trucks required from each dump, and the time suitable to both parties, namely, the contractor loading and the tramway company sending the empty trucks to each dump to be filled. The trucks, on arrival at the works, pass over a Pooley weighbridge, capable of weighing 40 tons, and after being weighed and then sampled for assay and moisture, the tailing is emptied into two storage-bins, having a total storage capacity of 1,888 tons (No. 1, 666 tons; No. 2, 1,222 tons). These bins are excavated out of the ground and made of concrete. At the bottom of the bins are openings, which deliver to 16 Challenge feeders (size of table, 2ft. 6in. diam., 15 r.p.m.). No. 1 bin has 10 feeders; No. 2, 6 feeders. By means of the Challenge feeders the millman is able, to some extent, to mix the material from the various dumps. The Challenge feeders deliver to a conveyor-belt, one to each bin parallel to it, and these again deliver to another conveyor-belt at right angles to the bin conveyors, which conveys the tailing up the hill, first to a rubbish trommel (8ft. 6in. by 4ft. by 2ft. 6in., 21 r.p.m.) clothed with a punched plate,

having 2in. holes ; this trommel is for the purpose of removing any stones, large chips, and lumps of slime or any large size material that would interfere with the feeding arrangements from the mill bins, or which would be too coarse to enter the tube-mill feed-pipes, and so cause serious chokage. The product through the trommel passes to another conveyor, No. 4, 24in. wide, troughed 6in., running 363ft. per minute, and then to another conveyor running at right angles to these over the top of the bins. This belt is fitted with an automatic Robins distributor or take-off, which distributes the material evenly over the bins, and is of great assistance in mixing the material.

The following is a statement giving classification tests, assays, and metal content of the feed to the crushing section for the three months ended December 31, 1911 :

		Percentage Weight.	ASSAYS.				Percent. metal distribution.		
			Zn. %	Ag. oz.	Pb %	Zn	Ag	Pb	
Original		100	16.4	7.7	7.0	100	100	100	
<hr/>									
Mesh. Aperture.									
On 40	On 0.5	37.7	14.1	7.4	7.9	32.4	36.2	42.5	
„ 100	„ 0.16	35.4	16.7	5.7	5.3	36.0	26.2	26.8	
„ 150	„ 0.09	8.9	17.8	6.8	5.6	9.6	7.9	7.1	
„ 200	„ 0.06	2.8	19.9	8.0	5.0	3.4	2.9	2.0	
Thro' 200	0.06 to 0	15.2	19.9	13.2	10.7	18.4	26.0	23.2	

All assay figures are in terms of total metals ; dry screening done on Hoover laboratory sizer.

From the mill bins, which have a total capacity of 874 tons, the material is automatically fed by means of four Challenge feeders (2ft. 6in.), running at 6.25 r.p.m. to chutes leading to three elevators 16in. by 8-ply Balata belting, travelling 380ft. per minute. These elevators deliver to six revolving screens clothed with brass woven wire, 12 by 12 mesh and 21 gauge ; the over-size goes to the tube-mills, and the through product, which needs further grinding, to eight grinding pans, which are fitted with Freeman classifier pipes.

The discharge from the tube-mills (size of mill approximately 10 by 5ft., lined with ribbed liners, running at 24 r.p.m.), together with the material from the pans, runs to a Callow settler 8ft. diam. by 9ft. deep, fitted with annular overflow, for thickening ; the overflow from this settler runs to four more 8ft. Callow settlers for de-watering, the clear water returning into circuit, while the

thickened slimy product runs through a small spigot, and unites with the thickened pulp coming from the single settler first mentioned; then to an elevator (size 16in., 8-ply, 300ft. per min.), which delivers to the mixer-box for flotation.

The following table gives the details of the material after crushing, showing classification tests, assays, and percentage metal distribution of the feed to the flotation plant for the three months ended December 31, 1911:

Original	Percentage Weight.		ASSAYS.			Percent. metal distribution		
			Zn. %	Ag. oz.	Pb %	Zn	Ag	Pb
	100		16.4	7.7	7.0	100	100	100
<hr/>								
Mesh. Aperture.								
On 40	On 0.5	2.2	10.3	4.6	3.0	1.4	1.3	0.9
„ 100	„ 0.16	38.6	15.3	4.8	3.9	36.0	24.1	21.5
„ 150	„ 0.09	16.6	17.2	6.7	5.9	17.4	14.4	14.0
„ 200	„ 0.06	6.0	18.6	7.6	5.8	7.8	6.6	5.7
Thro' 200	0.06 to 0	35.7	17.7	11.6	11.6	38.5	53.8	59.1

All assay figures are in terms of total metals; dry screening on a Hoover laboratory sizer.

The mixer-box is divided into 16 compartments, eight of which are for mixing and eight for flotation; the mixing is done in each of the compartments (3ft. square) by means of an impeller or paddle, 2ft. diam., working horizontally on a vertical shaft, having a speed of 306 r.p.m. From the mixer-box to the flotation-box there is an opening, 14 by 4in. and 12½in. from the bottom of the box, as an outlet from the mixer-box to the flotation compartment.

At No. 1 mixer-box the acid solution, the eucalyptus oil, and the steam for heating are added. The feed running into No. 1 mixer-box receives a certain amount of agitation by means of the horizontal impeller before it passes into No. 1 flotation compartment. The feed, being mixed with the acid and oil, becomes emulsified, and causes immediate flotation of a fair proportion of the sulphide particles, which flow over the lip of the flotation compartment into a launder. The rest of the material which has not been lifted falls to the bottom of the flotation compartment, and from there it is drawn by means of No. 2 impeller into No. 2 mixer-box through a 5in. pipe, and after receiving a certain amount of agitation and aeration it is forced into No. 2 flotation compartment, and a further amount of sulphides is floated off into

the launder. This zig-zag track is continued through the length of the mixer-box until it reaches the last flotation compartment, and by that time all the free sulphides should be removed; there only remains the residue, which is removed by opening a valve at the bottom of the last flotation compartment. This valve regulates the whole of the flow through the boxes, and has to be adjusted according to the proportion of water to feed, which is 3.5 of water to 1 of tailing by weight.

The following is a statement showing classification tests, assays, and percentage metal distribution of the flotation concentrate for three months ended December 31, 1911:—

Original	Percentage Weight.	ASSAYS.			Percent. Zn	metal extraction	
		Zn. %	Ag. oz.	Pb %		Ag	Pb
	100	41.8	15.3	12.1	100	100	100

Mesh.	Aperture.								
On 40	On 0.5	1.7	47.1	11.4	6.0	1.9	1.3	0.8	
„ 100	„ 0.16	46.9	43.8	11.3	9.0	49.1	34.6	34.9	
„ 150	„ 0.09	13.9	41.7	13.5	11.3	13.9	12.3	13.0	
„ 200	„ 0.06	4.2	43.3	15.3	11.1	4.4	4.2	3.9	
Thro' 200	0.06 to 0	33.3	38.8	21.9	17.1	30.9	47.7	47.1	

All assay figures are in terms of total metals; dry screening on a Hoover laboratory sizer.

Sectional samples taken from each of the flotation compartments when overflowing at the lips are very interesting, as will be seen by referring to the following table:

SECTIONAL SAMPLING OF M.S. FLOTATION-BOXES FOR PERIOD
JANUARY 30 TO FEBRUARY 13, 1912.

No. 1 Box	..	ASSAYS.	Total Metals.		Oxidized Metals.		Insoluble. %
		Zn. %	Ag. %	Pb %	Zn. %	Pb. %	
„ 2 „	..	38.6	31.9	17.3	0.4	2.8	6.3
„ 3 „	..	43.7	21.1	13.7	0.4	2.4	2.7
„ 4 „	..	46.1	17.1	11.2	0.3	2.1	2.2
„ 5 „	..	46.1	15.7	10.6	0.3	2.3	2.5
„ 6 „	..	44.8	15.1	10.6	0.4	2.8	4.1
„ 7 „	..	41.4	15.8	11.6	0.4	3.7	7.0
„ 8 „	..	39.3	15.7	12.4	0.4	4.0	9.0
„ 8 „	..	32.4	15.0	13.8	0.6	5.1	17.3

No. 1 compartment contained a high percentage of lead, and also of insoluble matter, and it was found that 7 and 8 also contained such a high percentage of insoluble matter that it was necessary to return these to No. 1 mixer-box again for re-flotation, with beneficial results. It was found, however, that, in spite of all the precautions, a high percentage of insoluble matter came over with the float, with certain ores, particularly those containing granular garnet. It is difficult to obtain a high-grade final zinc concentrate from these ores, although they are easily floated, requiring very little acid and oil. With the object of further raising the grade, it was decided to re-float the whole of the concentrate obtained from the first two units of the plant by passing it into a third flotation unit. The results obtained by re-floating the whole of the flotation concentrate from the two units have been very satisfactory, and can easily account for about a 2% rise in the zinc content of the ultimate flotation concentrate. At the time of writing the results obtained from a 14.8% zinc feed are approximately 42% zinc flotation, 44% re-flotation, and 46.5% finished zinc from the de-leading plant.

The following statement shows classification tests, assays, and percentage metal distribution of the re-flotation concentrate for two months ended December 31, 1911 :

		Percentage Weight.	ASSAYS.			Percent. metal distribution		
			Zn. %	Ag. oz.	Pb %	Zn	Ag	Pb
Original		100	43.2	15.7	12.2	100	100	100
<hr/>								
Mesh.	Aperture.							
On 40	On 0.5	1.3	45.1	12.0	6.7	1.4	1.0	0.7
„ 100	„ 0.16	42.1	46.5	10.7	8.5	45.3	28.7	29.3
„ 150	„ 0.09	11.7	43.4	13.0	11.0	11.7	9.7	10.5
„ 200	„ 0.06	4.6	44.2	15.1	10.3	4.7	4.4	3.9
Thro' 200	0.06 to 0	40.3	39.8	22.1	17.0	37.1	56.7	56.2

All assays are in terms of total metals : dry screening on a Hoover laboratory sizer.

The following statement shows classification tests, assays, and percentage metal distribution of sand-residue for three months ended December 31, 1911 :

Original			ASSAYS.			Percent. metal distribution		
	Percentage Weight.		Zn. %	Ag. %	Pb %	Zn	Ag	Pb
	100		2.4	2.7	4.3	100	100	100
Mesh.	Aperture.							
On 40	On 0.5	9.5	4.9	3.3	3.4	19.4	11.6	7.5
„ 100	„ 0.16	51.1	2.2	2.2	3.1	46.8	41.6	36.8
„ 150	„ 0.09	12.1	1.7	2.2	3.7	8.6	9.9	10.4
„ 200	„ 0.06	4.0	1.6	2.9	3.9	2.7	4.3	3.6
Thro' 200	0.06 to 0	23.3	2.4	3.9	7.5	23.3	33.7	41.0

All assay figures are in terms of total metals ; dry screening on a Hoover laboratory sizer.

The following statement shows classification tests, assays, and percentage metal distribution of re-flotation residue for three months ended December 31, 1911 :—

Original			ASSAYS.			Percent. metal distribution		
	Percentage Weight.		Zn. %	Ag. oz.	Pb. %	Zn	Ag	Pb
	100		33.6	13.6	13.4	100	100	100
Mesh.	Aperture.							
On 40	On 0.5	2.9	45.8	7.3	5.4	4.0	1.6	1.2
„ 100	„ 0.16	52.2	36.8	10.0	10.8	57.2	38.4	42.1
„ 150	„ 0.09	13.1	29.6	14.1	14.6	11.5	13.6	14.3
„ 200	„ 0.06	5.2	32.7	15.5	14.0	5.1	5.9	5.4
Thro' 200	0.06 to 0	26.6	27.6	20.9	18.7	21.9	40.9	37.1

All assay figures are in terms of total metals ; dry screening on a Hoover laboratory sizer.

As so much depends on the careful running of the flotation plant, special men are picked for this particular work, so as to get the best efficiency and to avoid waste of acid and oil. The workman has to watch carefully the amount of acid used, and he can do this by keeping the solution in Nos. 7 and 8 flotation compartments slightly acid, or almost neutral. He tests this periodically with methyl orange, and can easily detect any change in the quantity of acid required. With regard to the eucalyptus oil, he is guided entirely by the way the float is coming off ; the temperature he keeps to 118° F., which is easily regulated, having the steam direct on to the No. 1 mixer-box. Probably the most important point of all is the necessity for having a solution not too dense ; if the

density of the solution exceeds 3,000 grains per gal., the flotation invariably goes off. To avoid this the workman periodically takes samples of his solution and tests it by hydrometer, and by reference to the following table he can quickly determine the density :

TABLE FOR ESTIMATING SOLUBLE SALTS.

Density at 60° F.	Salts in Grains per Gal.		
1026	2000
1028	2200
1030	2350
1032	2530
1034	2700
1036	2900
1038	3050
1040	3230
1042	3400
1044	3600

The solution in circulation should not contain more than 3,000 grains per gallon.

CORRECTION FOR TEMPERATURE IN GRAINS PER GALLON.

Temp. Fahr.	Add. Grains.	Temp. Fahr.	Add. Grains.	Temp. Fahr.	Add. Grains.	Temp. Fahr.	Add. Grains.
61	3	71	83	81	200	91	323
62	6	72	94	82	212	92	336
63	12	73	105	83	225	93	350
64	18	74	117	84	236	94	364
65	25	75	128	85	248	95	378
66	33	76	140	86	260	96	393
67	42	77	152	87	273	97	408
68	50	78	165	88	285	98	424
69	60	79	177	89	298	99	442
70	70	80	190	90	310	100	460

To keep the density of the solution within the limit a clear-water pipe is attached to each mixer, and is used not only for this purpose, but also for make-up water. The usual custom is, as soon as the solution becomes too dense, to run off one or more of the slime-residue settling-tanks, and make up the balance with clean water again. This serves the purpose of getting rid of the slime-residue, as well as of improving the solution.

The re-flotation concentrate from the third unit is run direct to a conveyor or draining belt, 36in. wide, working in an iron trough 38in. wide and 15in. deep, for the purpose of draining. The overflow from the trough, which is always very fine and slimy and has a tendency to float, is run to an elevator 12in. by 8-ply, running 300ft. per min., and returned to a settler 8ft. diam. and 9ft. deep for thickening. A spray of clean water plays on the float material in the settler to break it down; the thickened product from the spigot at the bottom is delivered to the same conveyor near the delivery end, and the overflow from the settler is run back into circuit.

The re-flotation concentrate coming off the conveyor-belt drops into a launder; some water from the de-leading section is added to wash it down to an elevator 18in. by 8-ply, running 320ft. per min. It is thus elevated to pass over five revolving screens (clothed with 60 by 61-mesh and 36-gauge, running at 11 r.p.m.), and forms the feed to the de-leading section. The re-flotation concentrate, while being washed down this launder, is calibrated by turning the whole of the flow for a timed period into a large box, where it can settle, and the water can be decanted. This calibrating is done at regular intervals, and forms an *estimated* tonnage prior to de-leading.

The over-size from the revolving screens runs to a revolving distributor, then to 7 of the first row of Wilfleys (running at 310 r.p.m.) for treatment. The under-size runs to a distributor, then to 12 of the second and third rows of Wilfleys (running at 310 r.p.m.), six in each row. These tables make a lead and a zinc concentrate, a middling, and slime. The zinc and the lead concentrates each run to their respective elevators, and are delivered into separate tanks for settling and draining. The middling from the first row of Wilfleys is returned by means of an elevator (16in. by 8-ply, 280ft. per min.) to three Wilfleys on the same row, and re-treated, making a zinc and a lead concentrate and a small portion of middling, which is returned. From the second and third row of Wilfley tables come a zinc and a lead concentrate, also a middling and slime.

The middling from the second and third rows of Wilfleys is returned by two elevators (16in. by 8-ply, 280ft. per min.) to eight of the tables in the second and third row, four in each row, and re-treated for a zinc and a lead concentrate, a small portion of middling being made, which is returned.

The slime from the three rows of Wilfleys is run to two 9 by 18in. 3-throw plunger-pumps, running at 32 r.p.m., and pumped to six Callow settlers; the thickened product is run to 12 Weir-Meredith vanners, which make a lead and a zinc concentrate, a middling, and slime. The middling is returned to two Callow settlers, then to five vanners again, and the slime made on all the vanners is pumped to the dam on the flat for future sale or treatment. This slime, although high enough in zinc to go with the zinc concentrate, is so difficult to drain that it was found advisable to store it rather than include it with the coarser concentrate. If it was included with the zinc concentrate, the moisture in the shipping concentrate would be excessive, involving a penalty on all excess moisture over 6%. This zinc slime, which is high in silver and lead (see analysis of zinc slime), is a saleable product by itself, and some has already been sold.

The following table gives an analysis of fine zinc concentrate for three months ended December 31, 1911:

				%
Zinc	35.3
Lead	12.3
Iron	6.8
Manganese	1.5
Sulphur	23.9
Insoluble	13.1
Lime	1.5
Carbon dioxide	2.3
Silver	21.5 oz.	per ton

CLASSIFICATION TEST.

Mesh.		Aperture.		Percentage Weight.
On 40	..	On 0.5	..	—
„ 100	..	„ 0.16	..	4
„ 150	..	„ 0.09	..	1
„ 200	..	„ 0.06	..	2
Thro' 200	..	0.06 to 0	..	93

The overflow water from both the zinc and lead concentrate settling-tanks runs to five Callow settlers; the thickened product

from these runs to the slime-pumps, and is re-treated on the vanners. The overflow runs to two large settling-tanks, 60ft. in diam. and 4ft. deep, having an annular overflow. These tanks are built of concrete, and have sufficient area to thoroughly clarify the slime-water. The clarified overflow water runs to two 3-throw 9 by 18in. plunger-pumps, and is pumped to the de-leading section supply-tanks, of which there are two, having a capacity of 10,000 gal. each; it is from these tanks that the wash-water for the screens, Wilfley tables, and vanners is supplied. The residue-sand coming from the No. 8 compartment of the flotation section runs direct to two Callow settlers, 8 by 9ft., having an annular overflow, the material passing over going to the elevator carrying the feed to the mixer, while the thickened product is drawn from the bottom, and runs to a 36in. conveyor draining-belt working in an iron trough; the overflow from the iron trough is pumped by means of a 4in. Robinson centrifugal pump to four round tanks, and the residue-slime allowed to settle. These residue-slime tanks (18ft. diam. and 4ft. 6in. deep) are fitted with annular launders, the overflow going to two 9 by 18in. three-throw plunger pumps, which pump the water into the three supply-tanks (16 by 8ft., 10,000 gal.), each elevated sufficiently high to supply the whole plant by gravitation. The residue-slime from these tanks is pumped out by means of a 6 by 12in. three-throw plunger-pump on to the flat, and forms a dam and bank around the main residue-dump.

The sand-residue is conveyed by two 36in. conveyors running slowly, 18ft. per min., to allow sufficient draining, and is dropped upon an 18in. by 5-ply conveyor-belt (rubber), travelling 210ft. per min., and conveyed for a considerable distance to a boom-stacker, which is building the sand dump to a great height.

Owing to the sloppy nature of the residue and the difficulty experienced in conveying it, also to the essential oil being a solvent of rubber, which quickly causes the belts to deteriorate, it has been decided to install a combination sluicing and conveying plant. By this scheme the residue will run direct to large draining-tanks, as far as the natural fall of the ground will allow, and then the residue, which will by this time have its moisture reduced to about 8%, will be conveyed the rest of the distance. By this scheme the conveying will be reduced by more than half and there should be less loss by evaporation, thereby effecting a saving in both belting and water.

The following is an analysis of lead concentrate for three months ended December 31, 1911 :

				%
Zinc	15.7
Lead	55.2
Iron	3.4
Manganese	0.6
Sulphur	19.0
Insoluble	2.8
Silver	35.7 oz.	per ton

CLASSIFICATION TEST.

Mesh.		Aperture.		Percentage Weight.
On 40	..	On 0.5 -
„ 100	..	„ 0.16 22
„ 150	..	„ 0.09 11
„ 200	..	„ 0.06 8
Thro' 200	..	0.06 to 0 59

The following table gives an analysis of zinc concentrate for three months ended December 31, 1911 :

				%
Zinc	45.3
Lead	8.1
Iron	8.3
Manganese	1.6
Sulphur	29.5
Insoluble	4.3
Silver	14.8 oz.	per ton

CLASSIFICATION TEST.

Mesh.		Aperture.		Percentage Weight.
On 40	..	On 0.5 1
„ 100	..	„ 0.16 32
„ 150	..	„ 0.09 11
„ 200	..	„ 0.06 8
Thro' 200	..	0.06 to 0 48

The finished lead and zinc concentrates (see analysis) from the de-leading section, after leaving the Wilfleys, are elevated into

draining-tanks (18 for the zinc concentrate and three for the lead concentrate). These tanks, which are fitted with filter bottoms by means of battens, cocoanut matting, and hessian, are emptied through a circular discharge at the bottom on to a conveyor (one conveyor to each three vats), which conveys the concentrate to another conveyor running at right angles to it, and is discharged into the shipping bins.

The capacity of each zinc-tank is 85 tons, of each lead-tank 125 tons, and the total capacity of the zinc and shipping bins 3,200 tons, making a total holding capacity of finished zinc concentrate 4,730 tons and of lead concentrate 575 tons. The shipping bins are built of stone, fitted with doors and chutes on both sides of the line for filling the shipping trucks; the extreme south end of the bin is partitioned off for the lead concentrate, and the same conveyor is used for conveying the zinc and lead concentrates alternately. After being filled into the Silverton Tramway trucks and sampled, the Zinc Corporation operations are finished.

The results of the operation of the Minerals Separation process in this plant is as follows :

	TONS TREATED				ZINC CONCENTRATE				LEAD CONCENTRATE			
		Zn %	Pb %	Ag Oz	TONS	Zn %	Pb %	Ag Oz	TONS	Zn %	Pb %	Ag Oz
1911	211,675	18.56	5.38	8.51	68,152	46.28	7.0	14.3	6,197	16.91	57.2	39.25
6 mos.	171,005	14.9	5.8	7.3	44,229	46.9	7.6	13.1	5,254	13.9	59.4	33.7
1912												

Recovery—Zn 86% Pb 62.7% Ag 61.3%.

The Minerals Separation plants and their capacity now in use are as follows:—Sulphide Corporation, 700 tons; Zinc Corporation, 1,000; Kyloe Copper Mines, 60; Junction North, 600; Silver Peak, 80; Wallaroo and Moonta, 400; Etheridge, 80; Great Fitzroy, 250; Pinnacles, 160; Great Cobar, 400; Chillagoe, 200; Bradin, 1200; Cuba Copper Co., 150; Saxbergets, 150.

CHAPTER X.

OTHER FLOTATION PROCESSES.

MACQUISTEN PROCESS.

One of the most important of the flotation processes is that invented by A. P. S. Macquisten. The apparatus is a tube so designed as to bring the sulphide particles in the ore on to the surface of the water in the most advantageous manner to insure that the force of surface tension and the inherent quality of the sulphides to resist wetting would insure their flotation.




FIG. 51.—Macquisten Tube.

The tube, Fig. 51, is made of cast iron, 6ft. long and 1ft. in internal diameter.* Two tyres, cast with the outside, run upon rollers, upon which the tube rests. The discharge end of the tube is open, while the feed end is closed, except for a hole in the centre to admit the feed-pipe. On the interior of the tube is cast a helical groove of $1\frac{1}{2}$ in. pitch. The discharge end of the tube, at the right of Fig. 51, connects with a vessel called the 'separating box,' the joint between the box and the tube being watertight, although the tube is free to revolve. The box has an opening for

**Engineering & Mining Journal*, October 26, 1907, 'Concentration Upside Down,' by W. R. Ingalls.

the overflow of water, the lip of this opening being of such a height that about 3 in. of water stands in the tube. The feed of pulp to the tube and the discharge of tailing at the bottom of the box are so regulated that the water passing over the lip of the box is about 1-32 in. deep. The floating concentrate passes over this lip into a launder, and the tailing passes out at the hole at the bottom of the box, going to a second tube for further treatment, if necessary, or to the tailing-flume. In operation the tube is rotated 30 r.p.m. in the direction of the helix. The pulp is thus screwed through the tube, and in its advance at every revolution the sulphides are given an opportunity to slide upon the surface of the water and float. As the tube revolves the pulp is carried up to the surface, and gently rolls over. The angle of emergence is such that some particles of sulphide are at once drained of the adhering water, take on air-films, and float. The gangue simply slides back into the water. This action is taking place at every corrugation, whereby the sulphide particles, which are capable of being held up by the force of surface tension, are given many chances to slide out upon the surface of the water at just the angle at which there is the least likelihood of penetrating the surface.

In any given tube revolving clock-wise (looking toward the feed end) the flotation takes place chiefly at the left-hand side, where the pulp emerges from the water. The bulk of the pulp in any corrugation either slides back into the water, or floats off; however, a certain amount always adheres to the tube, and is carried over to the water on the right-hand side, where upon meeting the water a further flotation takes place, but naturally this is less than on the left-hand side. Consequently, from the time the pulp enters the first tube there are floating sulphides streaming off from the sides of the tube, which by the time the discharge end is reached form a glistening film, covering the entire surface of the water both in the tube and in the separating-box. This is quite different in appearance from the black frothy scum which rises to the surface in the acid-flotation processes. In separating the chalcopyrite and pyrite at Golconda, the surface of the water is covered with the sparkling bronze mineral, the water looking as if it had been sprinkled with the bronze powder that is employed for decorative purposes. In treating a lead ore, there comes off a film of steel-grey galena; in treating a zinc ore from Joplin, Mo., there was a film of mustard-yellow blende. The flotation is persistent. Once it has been effected, the mineral

remains on the water until the latter has overflowed into the launder, which delivers it into the collecting-tank, and even in the latter more or less mineral can be observed floating on the surface. One treatment is not generally sufficient, and the gangue-tailing, with the remaining sulphide, is passed through a second, third, and fourth tube. By far the largest amount of concentrate is secured from the first tube.

The capacity of a single tube is 5 tons of ore per day, but as the material must be put through several tubes, the actual capacity of a set would be, say, 5 tons. The ore at the Adelaide mine assays from 2.7 to 3.2% copper, and the percentage of sulphides is low. It is important to note that on a heavy sulphide ore like that at Broken Hill it would probably be necessary to treat the material through a great many tubes, or else cut the capacity down to a very low point. These tubes have an effective flotation surface




FIG. 52.—Murex Apparatus.

of 6 sq. ft. per tube ; and, therefore, must be limited in capacity as compared with those processes which increase the available surface by froth production.

The accounts of this process so far published seem to indicate a lack of facility in the treatment of slime.

MUREX PROCESS.

This process is not strictly of the same class as the others ; but as it makes use of the principle of the selective oiling of sulphide particles, and has other similarities to flotation processes, it should be described. In this process the crushed ore is fed to an agitator, Fig. 52. A 'magnetic paint' is fed with the ore in quantity ranging from 40 to 60lb. per ton (4 or 5%) of ore. This magnetic paint is made by mixing one part of oil or thin tar of almost any kind with three or four parts of magnetic oxide of iron, natural or

artificial. The oxide must be ground to an impalpable powder. In the mixer A the ore, with the paint and enough water to make a thick pulp, is agitated from five to twenty minutes to thoroughly mix the substances. The paint preferentially adheres to the sulphides because of its oily constituent. When this is accomplished the pulp is fed with some additional water to the upper end of the shaking conveyor B, along which it travels to the magnet C. Around the magnet C is an endless belt D, this belt being between the magnet and the conveyor. As the pulp passes along the conveyor it comes within the magnetic field, and the sulphide particles, partly due to their inherent magnetic permeability and partly to the magnetic permeability of the adhering magnetic paint, are drawn up against the endless belt D and carried outside the magnetic field, where they are washed into the launder E by a stream of water. It is claimed for this process that a great variety of products can be made by varying the material used for mixing with the magnetic oxide. We are already aware that the seriation of minerals, which exercise a preferential oiling, is of much wider range than the seriation of those which will preferentially float, and it is easily believed that among the thousands of oils and coal and wood tar derivatives there may be one which would preferentially adhere to almost any mineral chosen.

This process is a new departure, and well worth research and development. At first glance the successful treatment of oxidized ores, not now treatable by any other process, would seem to lie in this direction. Whether the process could compete with gravity or flotation-concentration for sulphides at present lacks extended demonstration.

SANDERS PROCESS.

This process, tried at Marion, Ky., is somewhat different from the other flotation processes, inasmuch as no acid is used in the bath, the latter being, on the contrary, basic, being in fact a very dilute solution of aluminium sulphate. Moreover, instead of being performed in deep vats, as in the case of the acid-flotation process (wherein the depth of the vat has been found to be a rather important consideration), the basic flotation process is performed in shallow pans, in which mechanical stirrers are operated. Besides the trials at Marion, some experiments with the Sanders process have been made by the Tennessee Zinc Company at Straight Creek, Tenn. The Kelly mine, near Magdalena, N.M., was equipped with a 100-ton plant.

The apparatus (Fig. 53) consists of a vat, preferably round, with a feed-hopper leading below the normal liquid surface. A solution-inlet pipe is placed either in the vat or in the hopper, depending on the ore to be treated. A vertical shaft in the centre of the vat rotates an agitator, the blades of which are arranged to impart a whirling motion to the solution. This whirling motion




FIG. 53.—Sanders Apparatus.

is designed to assist in raising the valuable mineral particles to the centre of the vat, and to cause a slight cavitation at the centre of the surface, which causes the particles which have been elevated to pass at once to the overflow pipe. The tailing is discharged through a pipe in the centre of the bottom of the vat. A steam-pipe is used on the bottom of the vat to keep the solution at an even temperature.

HORWOOD PROCESS.

The principle of this process is that when a mixture of iron, copper, lead, and zinc sulphides is roasted, the surfaces of the




FIG. 54.—Horwood Experimental Plant.

particles of the three former sulphides are changed to oxide and sulphate at a comparatively low temperature, whereas the zinc

sulphide is practically unaltered. The partly roasted material is then subjected to a heated-acid oil-flotation process, such as the Minerals Separation process, when the zinc sulphides will float away, and the deadened or sulphated compounds of iron and lead will sink with the gangue.*

Preliminary tests must be made on ores which are to be treated by this process in order to ascertain in just what combination the metals really exist. While the ores at Broken Hill are somewhat granular, the grains of galena and blende being, to a great extent, separable by comparatively coarse crushing, there are many steely-grained admixtures of blende, galena, and pyrite which have to be reduced to a slime before the individual grains are separated.

A photograph of the small Minerals Separation process unit used in extended trials at Bendigo is shown in Fig. 54.

On one lot of Broken Hill slime concentrate the laboratory test showed the concentrate to contain 32.4% zinc and 22.3% lead. This was roasted and treated in the testing laboratory, and two products were made: No. 1, a zinc concentrate, containing 50.8% zinc and 6.3% lead; No. 2, a lead residue, containing 2.6% zinc and 49% lead. About 53½% of the original concentrate was recovered as a zinc concentrate, and about 38% reported as a lead residue. About 85% of the total zinc and 85% of the total lead were recovered in this test.

In actual operation there were obtained from this ore a zinc concentrate, containing 50.4% zinc and 7.3% lead, and a lead residue, containing 12% zinc and 41% lead. The lead residue may be improved by further agitation, raising the content of the lead and reducing that of the zinc.

A complex sulphide from Tasmania, containing an intimate mixture of blende, galena, and pyrite, was also tested. This ore had to be crushed dry to a slime product to insure separation of the blende and galena. The ore assayed 30.9% zinc and 9.9% lead, and yielded in actual operation in the experimental plant a zinc concentrate containing 57% zinc and 5% lead, and a lead residue containing 5.8% zinc and 20% lead. These Tasmanian ores were so intermixed that some mineralogists considered the zinc-lead sulphide to be an isomorphous compound.

Preliminary laboratory tests must be made on ores to be

**Engineering & Mining Journal*, February 26, 1910, p. 460, 'Horwood Process,' by Donald Clark.

treated by this method to determine the percentage of flotation obtainable, the amount of lead required to be converted to sulphate, acid consumption, crushing, etc.

The ore is roasted in an Edwards furnace, the temperature being kept below the ignition point of zinc sulphide ; usually the temperature of the heated gases passing over the ore, as tested by a pyrometer, varies between 300 and 400° C. The end point of roasting is determined by prior laboratory experiment, and varies with the composition and fineness of the ore. Tests are made from time to time on the furnace product to find the amount of lead present as sulphate, and as soon as the predetermined amount is reached the ore is discharged from the furnace.

In the first test the ore was roasted in charges until sufficiently sulphated ; but latterly, and with more satisfactory results, a continuous feed and discharge and a slow rabble-motion were used. The first to oxidize is the pyrite, and next the galena, the zinc sulphide being almost unaffected. The time required for Broken Hill slime-concentrate, when roasted in charges, was about three hours.

The partly roasted ore is fed into the boot of a bucket elevator with about five times its weight of a dilute solution of sulphuric acid, heated to near the boiling point. The amount of acid required is determined by laboratory experiment, and is as high as 100 lb. per ton treated.

The zinc, being unaltered by the slight roast, floats at the surface as mineral froth in the same way as was described in Chap. IX., while the iron and lead particles, being altered on the surface to soluble sulphates, are wetted by the water and sink. It may be noted here that the extreme limit of water-wetting is the case of solubility.


Kenneth A. Mickle* proposes to get an analogous alteration of the galena particles by treating the crushed material with ferric chloride, and then subsequently treating by a flotation process.

HYDE PROCESS.

James M. Hyde, of Basin, Montana, has developed a flotation process for treating the ores of the Butte & Superior Company. The experiments at Basin were so successful that the Butte & Superior Company has erected a mill at Butte on lines laid down by Mr. Hyde.

**Australian Mining Standard*, May 2, 1912, p. 404.

OTHER FLOTATION PROCESSES.



of water by weight to one part of ore, to which was added, before thickening, from one-quarter to one-half pound of sulphuric acid per ton of ore. The thickened pulp was heated in the flotation machine by live steam to expand the gas bubbles, and facilitate coating the sulphide particles with the oil used, which, in this case, was 'candle-maker's red oil.' The oil consumption cannot be calculated beforehand, but must be gauged by experience. The ore fed carried 23.3% of zinc, the concentrate 51.4%, and the tailing 3.2%, indicating a 91% recovery. The concentrate from the primary section of the machine ran 38 to 42% of zinc.

The Butte & Superior ore contains rhodochrosite, quartz, and sulphides and is an ideal ore for flotation. The ore has been treated for some time at the Basin reduction plant, rented from the United Copper Company by the Butte & Superior Co. The mill was too small and the rental heavy, so plans were drawn for a 1,000-ton mill, one 500-ton unit of which was in operation by the end of May, the other about a month later. The installation consists of a crushing plant, jigs, hydraulic classifiers, a slime-plant for oil-flotation, and Wilfley tables, which are used only to separate the lead from the zinc. The ore is first reduced by rolls to 6-mesh, and, after jigging, the tailing is re-ground to 40-mesh, and the tailing from the fine jigs ground to 100-mesh, and treated by oil-flotation. The pulp is thickened to three parts water and one part ore, and is mixed with a small quantity of oil and sulphuric acid and agitated.

The following are the results of the operation :

EFFECT OF FINENESS OF FEED ON RECOVERY.

500 GM. TESTS.

		Feed.	Conct.	Tail.	%
		Assays per cent.		Zinc.	Recovery
Crude Ore through 60-mesh	..	18.8	51.1	—	83.0
		18.8	45.7	—	87.0
		22.6	47.2	2.4	92.7
		22.6	48.5	2.7	90.1
Crude Ore through 150-mesh	..	22.1	47.9	0.7	97.2
		22.1	52.8(a)	1.1	93.5
			Mids.	4.8	
Jig Tailing through 60-mesh	..	10.9	39.5	2.7	73.2
		10.9	42.0	2.8	75.5
Jig Tailing through 150-mesh	..	10.4	40.1	1.4	87.6
		10.4	48.9(a)	1.7	79.4
			Mids.	4.7	

(a) These concentrates are the only ones in the above series which received any cleaning re-treatment. The material marked 'Mids' is the tailing resulting from this re-treatment. In actual milling, where the middling is returned to the rougher for re-treatment, it is found that the tailing is practically as low when the cleaner is used as when it is not, and the cleaned product runs 5 to 8% higher than the uncleaned.

SUMMARY OF FLOTATION TESTS.

	No.	Gal. treated per min.	Ratio water to ore.	Rate of Ore.	Tons per day Conc.	Assay.			Recovery. %
						Feed.	Conc.	Tail.	
Complete Hyde Machine Regular Mill Feed	11	166.9	6.9-1	142.3	71.3	25.8	50.1	2.7	94.6
Rougher Hyde Machine Built up Feed	12	156.1	3.09-1	281.7	131.4	20.1	41.8	1.1	97.0
Rougher Hyde Machine Built up Feed	13	196.3 166.8	2.1	516.76 439.0	190.3 190.3	21.8	43.2	5.5	85.7

SCREEN-ANALYSIS OF MILL PRODUCTS.

BUTTE AND SUPERIOR ORE.

Mill Feed 21.1% Zinc. 500 gm. Sample, 4 days sample assay.

Crushed through 5 mm.

			Weight.		% Weight.	Assay	% Zinc.
On	20	..	332.2	..	66.44	..	18.3
	40	..	56.7	..	11.34	..	19.4
	60	..	24.2	..	4.84	..	22.5
	80	..	11.5	..	2.30	..	23.5
	100	..	9.9	..	1.98	..	24.7
Through 100	..		61.9	..	12.36	..	24.9
			496.3				

COARSE MILL TAILING.

Sample for 2 days, 500 gm. Sample, 9.4% Zinc.

On	20	..	136.3	..	27.26	..	8.6
	40	..	183.8	..	36.76	..	9.7
	60	..	67.6	..	13.6	..	9.7
	80	..	34.6	..	6.92	..	8.9
100	..		17.6	..	3.52	..	11.1
			497.4				

TABLE TAILING.

			Weight.		% Weight.		Assay % Zinc.
On	40	..	42.6	..	21.3	..	6.1
	60	..	29.1	..	14.5	..	4.9
	80	..	22.7	..	11.3	..	5.9
	100	..	24.5	..	12.2	..	5.1
	150	..	13.0	..	6.5	..	5.0
Through	150	..	64.2	..	32.1	..	11.3

SCREEN-ANALYSIS FLOTATION CONCENTRATE AND TAILING.

Concentrate No. 56 from ore assaying 22.6% Zinc. 100 gm. Sample.

Whole Sample, 47.2% Zinc.

			% Gms.		Fe.		SiO ₂		Zinc.
On	80	..	16.0	..	3.2	..	24.8	..	43.6
	100	..	18.0	..	3.4	..	22.0	..	46.0
	150	..	14.0	..	3.6	..	20.2	..	46.4
Through	150	..	52.0	..	3.4	..	17.9	..	47.8

Concentrate No. 58, Ore as above.

Whole Sample, 48.5% Zinc.

			% Wt.		Fe.		SiO ₂		Zinc.
On	80	..	13.5	..	3.1	..	21.7	..	46.6
	100	..	22.4	..	3.1	..	18.2	..	48.5
	150	..	9.8	..	3.2	..	16.4	..	49.5
Through	150	..	54.3	..	3.3	..	14.3	..	50.0

2.0% Zn Tailing No. 65 from Fine Jig Tailing 6.1% Zinc.

			% Wt.		Assay % Zinc.
On	80	..	26.7	..	3.9
	100	..	45.8	..	3.0
	150	..	16.5	..	2.6
Through	150	..	11.0	..	1.8

2.7% Tailing No. 59. From Mill Feed, 22.6% Zinc.

			% Wt.		Assay % Zinc.
On	80	..	20.8	..	4.0
	100	..	18.0	..	3.4
	150	..	14.5	..	2.7
Through	150	..	46.7	..	2.0

2.8% Zn Tailing No. 63. From Coarse Jig Tailing, 10.9% Zn

			% Wt.		Assay of Zinc.
On	80	..	23.4	..	4.0
	100	..	17.8	..	3.4
	150	..	9.7	..	3.0
Through	150	..	49.1	..	2.0

CHAPTER XI.

ECONOMICS.

Flotation processes have a restricted range of application. The development has been, and is, so rapid that no one can prophesy what the end will be. Up to the present comparatively few minds have been working on the idea, but with the wider human effort which within a few years will be brought to bear, it is quite likely that the applicability will be considerably increased. There is reason to believe, also, that the forces of surface tension and adhesion could be profitably employed in industrial operations other than ore concentration, and especially in operations where coagulation will give rise to new combinations. Buoyancy-flotation has already been applied to the separation of imperfect oranges from perfect ones, and also to the separation of wood fibre from *guyaule* rubber.

LIMITATIONS.—There are, in the present state of our knowledge, four main limitations to the applicability of these methods. The first is that in general they are limited in their usefulness to those ores where certain valuable metals are in the form of sulphides, which need to be separated from worthless gangue. Some flotation patents have claimed to be able to treat ores where the minerals are carbonates or oxides, but these claims are at the present time over-optimistic, and so far there is not any demonstrated method of concentrating carbonates and oxides by flotation. It is the metallic sulphides, as distinguished from the carbonates and oxides, for which the oils and gases used in these processes have a marked selective action. The carbonates and oxides are not without some adhesive quality, but this quality in them is so feeble on the one hand as compared with the sulphides, and so little differentiated from the adhesive quality of the gangue on the other, that it has been impossible so far to found a commercial process on this quality. This is an important point for research and invention, as it is quite likely that if a process was found by which the carbonates and oxides could be separated from gangue by flotation it would also obviate the second dominant limitation

of the process. The most likely line of research at present in sight that would seem as if it might accomplish the desired end is along the line of soluble frothing agents, and especially the multitude of little known products from the destructive distillation of various woods; a method which aims at coagulation of the mineral by means of slow agitation may also be beneficial.

The second limitation to the usefulness of the processes is that in general they are not applicable to ores which contain more than 5% of those carbonates which are soluble in dilute acid. For the acid-flotation processes a small proportion of calcium carbonate is a *sine qua non* for success in order that the acid may have something from which to generate carbon dioxide gas. Those processes which use air as the flotation gas do not need any carbonate present; it is a detrimental element in this case because it unnecessarily consumes acid. Four to five per cent. of calcium carbonate is the maximum required for acid-flotation processes; more than this unnecessarily consumes acid. The ideal ore for the acid-flotation processes is the Broken Hill tailing from the table concentrators, having the following analysis :

					%
Pb	7
Zn	20
Fe	8
Mn	3
S	14
CO ₂	3
SiO ₂	42
CaO	1
O, etc.	2

An ideal ore for oil-air flotation methods is that of the Guernica mine in Bolivia, which has the following analysis :

					%
Cu	3
Fe	12
S	10
Al ² O ₃	2
SiO ₂	72
O, etc.	1

This latter ore would require the addition of calcite in order to get any result with the acid-flotation processes.

Some ores which have up to 10% CO_2 can be successfully treated by the oil-air flotation processes by adding a small amount of acid at the proper moment of flotation; whereas an attempt to treat these ores by mixing them with a comparatively strong acid solution, such as is used in the acid-flotation processes, results in the consumption of all the acid in the circuit without getting the desired result. Some recent patents claim useful results without acid and the present practice at the Great Fitzroy mine in Queensland is of this order.

Ores like that of the San Francisco del Oro mine and the Avino mine in Mexico have proved difficult to treat, because these deposits occur in a calcareous country-rock, some of which is necessarily mixed with the ore. The former also contains fluorite, and this fluorite shows a decided tendency to float, thus contaminating the zinc concentrate with an element which the zinc buyers penalize most stringently. In this point, then, we have the third limitation to these methods—that is, they are limited to those ores which do not contain floatable minerals that are deleterious to the concentrate. Besides the fluorite ore mentioned above, the mixed sulphide ores of Scandinavia fall into this class because they contain such a large percentage of iron pyrite, which floats, that the tenor of the concentrate is thereby reduced to a point so low that the product is unmarketable. The market demand for concentrate also bears on the cases of graphite and molybdenite. There has been a great deal of unjustified optimism concerning the supposed revolution flotation processes would bring about in the treatment of these two substances. In the case of graphite the fine crushing tends to destroy one of the best qualities of the graphite, because the best prices are paid for the larger grains. There is a very limited market for slimed graphite, and in any case there is always some gritty quartz in the flotation concentrate which is deleterious for the chief purpose for which fine graphite is used, namely, lubrication. Graphite thus falls within the third limitation. Molybdenite is the most easily floated of all the minerals, but a plant of sufficient size to pay a profit on mining and milling would produce enough concentrate in a year to supply the present demand for a hundred years. It is true that a cheap high-grade molybdenite concentrate might build up a new market by making that metal available for new uses, but not at the present price of the concentrate.

The fourth limitation is one for which at present no adequate

reason can be given. An ore in which the valuable minerals are wholly or partly bornite or chalcocite, as those of Bingham canyon, will probably give trouble to flotation processes, although not always, for among the many ores tested the one which gave the most uniformly satisfactory results was a copper ore assaying 2.8% copper, all in the form of microscopic specks of bornite. The gangue of this latter ore was an acid dike rock, and it is just possible the bornite was an original constituent of the rock. There was no appearance in the ore to suggest oxidation, the whole mass being singularly free from fractures. The recovery on this ore was 95%, and the concentrate assayed 48% copper. It may be that only those ores where bornite and chalcocite are of secondary occurrence give trouble. It is true that good hand specimens of bornite, when finely crushed, can be made to float with ease. As a general rule, however, it will be necessary to carefully test copper ores which contain any bornite or chalcocite before pronouncing an opinion as to the probability of successful flotation-concentration. The Bingham canyon ore contains so little bornite or chalcocite that its presence often escapes superficial observation.

SEPARATION OF SULPHIDES.—Up to the present these methods have not with complete success solved the problem of the separation of the sulphides from each other. The Horwood process is a step in this direction, but little has been heard of it recently, and on economic grounds it is doubtful if in the present form the idea is commercially feasible.

The sulphides of the base metal have the quality of oil and gas adhesion in varying magnitudes, as can be easily demonstrated, but the range of this variability is much smaller than between gangue and sulphides. No one dare say, however, that even this minute variability does not have in it the basis of a commercial separation. Horwood accomplishes the result by going to the expense of a preliminary slight roast, and thus turning some of the sulphides as far as is necessary into a form analogous to gangue minerals, thus destroying the strong adhesive quality of some of the sulphides, and he thereby is able to separate them from those sulphides whose quality of adhesion to oils and gases is unaffected by the slight roast. This is another of the important unsolved problems, and its solution lies in the direction of combining all the favourable factors in such a way that they all act at the proper time and proper place. Some oils cause a better

frothing of the blende than of the galena ; some temperatures are better for the frothing of certain sulphides than of others ; some pressures cause a froth to form in which there is a greater proportion of certain sulphides than at other pressures ; the amount of air or gas made available for frothing affects the composition of the froth to a certain extent ; the amount of acid used has a decided influence on the constitution of the froth, and the impurities of the water also have similar effects. The above factors and others, which are available for working in conjunction, conceivably contain the secret of a revolutionary process for solving the long-standing problem of separating completely and commercially mixed sulphides of copper, zinc, and lead. I am inclined to think however, that the solution of this vexed problem lies within the realm of the chemical industry.

COMBINATIONS.—The limitations of any one process of ore concentration are the reasons why metallurgists have always used combinations of processes and of apparatus. We have combinations of hand sorting, jigs, shaking tables, vanners, and many others, and these combinations are further combined with amalgamation, cyanide, chlorination processes, and others. Flotation processes quite properly take their useful places in combinations for the purposes of concentration only, but it is not likely that they will soon be used in combination with the cyanide process ; at least, they will probably not be so used until a successful flotation process is discovered which does not use any acid. We would not at first glance think that health conditions would be good in a plant where cyanide treatment of the ore is either preceded or followed by one of the present flotation processes. Nor is it likely that a combination of an oil-flotation process followed by amalgamation will soon be seen, although there would appear to be nothing to prevent flotation-concentration following amalgamation provided cyanidation was not desired.

SLIME.—This point will be discussed with some reluctance because the author's past relations have been such that there is a fear he may be charged with favouritism or with advertising a proprietary method. Even at the risk of this criticism it is just to the reader as well as the process owner to venture a private opinion, based on extended observation. One of the important processes previously described makes no attempt to treat slime, and numerous statements have been made in line with this fact. A second process described, while making, perhaps with some jus-

tice, claims of an ability to treat slime, has signally failed in at least two important instances unnecessary to specify. A third now seems to be in a way to overcome its earlier difficulties. Among the minor processes there does not seem to be any which have advanced far in the treatment of slimy material.

The Minerals Separation process has for some years stood alone in its ability to handle with ease in operation, and with commercial profit, the slimiest of mill by-products. This has been demonstrated by operations extending to millions of tons and over years of time. There are sound physical reasons for this feature and the principles involved—to wit, coagulation of the sulphides, followed by frothing of the coagules, are made the most of. It is unnecessary to give details on the subject of this slime treatment other than are found elsewhere in this and previous chapters. Recent developments of the Potter-Delprat process indicate for certain that slimes can now be treated successfully by this method also.

MAGNITUDE OF OPERATIONS.—It is a significant fact worth keeping in mind that nearly, if not quite, all the plants where these processes are now being used are very large plants. They are treating large tonnages at a small profit per ton, and if they were operating on the scale of the average sized mine, as will appear later, the overhead charges would probably eat up all this profit. In addition to this, the operations are on materials which have already been mined and which cost very little to deliver to the bin. If 10s or 12s per ton was added as the cost of mining to the working cost, the profit would disappear. The cost given later is mostly for the Broken Hill district, where the cost is much higher than is considered necessary elsewhere in the world. It seems probable that the same operations in the United States would be 25% less, even though the cost of materials is about the same and wages much higher than in Australia; on the other hand, labour is doubly efficient and the difference in management beyond the power of figures to express.

ADVANTAGES.—Those ores which have garnet for a gangue-mineral will in general be found particularly amenable to flotation processes unless a large amount of calcite is also present. Barite gangue is also separated in many instances with ease. Felspar ores are treated with excellent results. Schistose ores, which produce a large amount of slime, will also be found amenable to at least one of the processes. Copper ores, where the sulphides are

so finely disseminated as to require crushing to extreme fineness to free the sulphides from the gangue, are the special province of these processes, and they will provide the greatest scope for the future extension of this method of treatment. The ores of the Great Fitzroy mine and the Caucasus Copper company are of this type. Many of the ores where the valuable constituents are in the form of silver sulphide, accompanied by pyrite in a quartz gangue—like the ore of the San Pedro mine, Guanacevi, Mexico—give an excellent separation with high-grade concentrate and good recovery. This class of ore deserves close study in connection with these processes. An ore from Japan, containing gold apparently locked in stibnite, gave good results. This ore yielded scarcely any of its gold content by amalgamation, gravity concentration, or any chemical method. This ore required very fine grinding to free the stibnite from the quartz.

An ore from Bolivia, in which the gangue is quartz and garnet, and the valuable content in tetrahedrite, yielded 93% of the gold and silver in small tests in a high-grade concentrate.

BROKEN HILL.—In 1904 there was estimated to be in the dumps at Broken Hill the following by-products :

Mine.	Material.	Tons.	Assay		Ag. oz.
			Zn. %	Pb. %	
Proprietary	tailing	.. 2,500,000	17.0	4.0	6.0
Block 10	„	.. 520,000	22.0	6.0	9.5
	middling	.. 137,000	22.5	7.5	10.5
	slime 165,000	18.0	10.0	9.0
Central	tailing	.. 1,000,000	22.0	7.0	6.0
	slime 600,000	21.0	17.0	20.0
South	tailing	.. 620,000	19.7	7.2	4.2
	slime 100,000	18.4	14.6	6.4
Block 14	tailing	.. 250,000	16.5	7.0	6.5
British	„	.. 250,000	17.0	4.8	5.0
	slime 125,000	21.0	8.9	10.0
Junction	tailing	.. 10,000	19.0	16.0	10.0
	„	.. 60,000	12.0	7.0	7.0
	slime 25,000	13.0	12.0	12.0
Junction North	tailing	.. 95,000	12.4	10.0	9.0
	slime 5,000	13.0	11.0	12.0
North	tailing	.. 100,000	17.0	8.0	5.0
	slime 20,000	14.0	11.0	11.0
	Total	.. 6,582,000			

The annual production of zinc concentrate by flotation processes since the above estimate was made has been as follows :

					Tons.
1904	57,602
1905	103,532
1906	102,664
1907	236,251
1908	275,932
1909	373,906
1910	468,627
1911	500,000

Total estimated	..	2,118,514
-----------------	----	-----------

The ratio of concentration on this material has been about 3.6 to 1, so that 8,000,000 tons of material has been treated. There still remains untreated sufficient material to keep the present plants going until 1919, when the accumulated tailing should be exhausted. It is evident that the 1904 estimates of tonnage available were far short of the truth. It is not probable that there will be any further great increase in the annual production of zinc concentrate at Broken Hill. It seems more probable that the pinnacle of tonnage was reached in 1910, and that the production will decrease from now on until the accumulated tailing is finished. There should be no large drop in the total tonnage produced, because the Zinc Corporation, the Amalgamated Zinc, and the Broken Hill Proprietary have reserves of tailing that will last for several years to come. One large plant last year ceased operating, but its place was taken by two smaller ones. A steady slow decrease in production may be expected, because most of these companies, during their early struggles with the vagaries of the processes, used their best material to make ends meet. They will probably make as much money out of their lower-grade material as they did out of the higher-grade material. When these immense piles are exhausted, which can be definitely predicted for 1919 or before, there will be a sudden drop in the zinc production of Broken Hill, which should considerably disturb the world's zinc market. The present production of Broken Hill zinc represents just about 20% of the total world's production. It is a remarkable fact that this enormous increase in the production of a district, which seven

years ago produced practically no zinc, has caused very little disturbance of the price. This was due to the fact that the high-grade Broken Hill zinc concentrate took the place of low-grade ores from many places in the world, outside of the United States, and these latter low-grade mines simply ceased production because the low-grade material could not compete with the high-grade at the same metal price.

The material treated by these processes at Broken Hill is of comparatively high grade, averaging at present close to 18% zinc, 6% lead, and 7.5oz. silver per long ton. In spite of these good assays, the profits are not fabulous. After charging working cost, royalty to process owners, smelters' charges, and management, there is left on an average close to 12s. per ton treated. In the case of some of the companies this is further decreased by the prices paid to the mining companies for the tailing. The average price for all the tailing and slime sold by the mining companies to the treatment companies averages about 6s. per ton, leaving on an average not over 6s. per ton profit to the treatment companies when zinc is £23 per ton. These are not the actual results of any one company, but are a fair average of the whole. Some of the companies increase this profit in favourable cases by anything up to 4s. per ton by the re-treatment of the flotation-concentrate, by means of which re-treatment a good lead concentrate is taken out of the flotation-concentrate. This lead concentrate represents about 50% of the lead in the flotation-concentrate. These figures mean that if the price of zinc dropped to £20 per ton the flotation plants would have to close down, or else reduce the working cost or economize in some other quarter.

The present selling contracts to the German zinc smelters represent a handsome profit to the latter. It seems certain that every ton of concentrate, which mostly goes to Germany, represents a clear profit to the Germans of at least 40s. per ton of concentrate or 11s. per ton of the original material. From the standpoint of the treatment company, this seems a rather liberal share of profit to the zinc smelter, and it speaks well for the acumen of the Germans that they tied up this large production under long contracts.

Some of the contracts under which this concentrate is sold are represented by the following equations :

(1.) Payment on board cars at Broken Hill =

$$(Zn-8) (P-5\%) + (Pb-8.5) (1s. 3d.) + (Ag-50z.) (P'/2) - R$$

Where Zn is percentage assay in zinc.

„ Pb „ „ lead.

„ Ag ounces per ton of silver.

„ P is average price of zinc over six months following delivery.

„ P' is average price of silver over six months following delivery.

„ R is a smelting and freight charge, which is £5 when the price of spelter is £17 10s., and increases 3s. per ton for each £1 increase in the average price, and decreases 3s. per ton for each £1 decrease in the average price.

There is a penalty of 1s. 3d. per unit for every unit of lead under 8%, but the lead penalty is never to exceed the payment for silver.

(2.) Payment on board cars at Broken Hill =

$$(Zn-8) (P-5\%) + (Pb-8) (1s.) + (Ag-50z.) (P'/2) - R$$

Where Zn is percentage assay in zinc.

„ Pb „ „ lead.

„ Ag ounces per ton of silver.

„ P is average price of zinc during six months of delivery.

„ P' is average price of silver during six months of delivery.

„ R is a smelting and freight charge which is £5 17s. 6d. with spelter at £23, and increases 2s. 6d. per ton for each £1 increase in the average price, and decreases 2s. 6d. per ton for each £1 decrease in the average price.

There is a lead penalty of 1s. 6d. per unit for each unit under 5%.

ROYALTIES.—The average royalty charged by the process owners for the use of these flotation processes is one shilling per ton of ore treated. This is very high royalty as measured by others with which miners and metallurgists are familiar. It is conceded that the inventor deserves compensation for his ingenuity, but 1s. per ton is about four times as large a royalty as the mine manager would expect. Large royalties have the disadvantage that they place a premium on infringement, and for this reason alone are,

from the standpoint of the process owner, not good business. The combined capital of all the companies owning flotation processes is close to £1,000,000. This means that 20,000,000 tons of ore will have to be treated and pay royalty of 1s. per ton before the capital is returned. These companies have been in existence now about seven years, and if we consider the investment ought to earn 10%, then the processes should have treated to date, besides the above tonnage, 14,000,000 tons more, making a total which should have been treated to date 38,000,000 tons. They are still about 30,000,000 tons behind the game. This does not mean anything particular, except that as a class these process companies were considerably over-capitalized, and have also wasted their money, both revenue and capital, on expensive litigation.

WORKING COST.—Figures on cost and recovery, owing to entirely unnecessary secrecy on the part of some of the companies, are not to be secured in the ordinary manner. But there are few secrets* which do not yield to the cruel analysis of the mathematical equation, assisted by scraps of evidence which can be collected in the broad light of day. By these means and the published returns of those who are proud of their work, a fairly correct summary of the whole position can be made as to the treatment of Broken Hill zinkiferous tailing. The following is a general average of all the processes :

	s. d.			
Tramming to plant	6
Re-crushing	1 8
Flotation treatment	3	7
Handling concentrate	6
Handling residue	6
Re-treatment of concentrate	1	6
Royalty	1	0
Total				9 3

Of these figures the only one which needs discussion here is the general average of 3s. 7d. for the flotation treatment, and it will be interesting to compare the cost of different processes in this particular. These figures do not exactly correspond to those given in previous chapters, because certain items have been reduced to a comparative basis by using one price for the respective materials used.

**The Mining Magazine*, August, 1910, 'Percentages of Recovery.'

Item.	Potter-Delprat.		De Bavay.		Elmore.		Minerals Separation.	
	s.	d.	s.	d.	s.	d.	s.	d.
Power ..		.90		1.50		1.34		1.74
Acid ..	1	3.00		8.00	1	0.90	1	0.15
Oil ..				6.00		6.00		6.00
Supplies ..		6.00		6.00		6.87		5.50
Labour ..		2.00	1	0.00		5.68		2.22
Fuel for heating		6.00						5.42
Assays ..		.30		.30		.38		.30
Water ..		1.50		1.50		1.99		1.50
General expense		8.72		8.72		8.72		8.72
Total	3	4.42	3	8.02	3	7.88	3	7.55

POWER.—In the Potter-Delprat process this figure is for pumping and circulating the acid liquor. As a power charge it is confused to some extent with upkeep of pumps, which is a greater item than it would be if the pumps were handling only water. In the De Bavay the power charge includes the washing of the pulp, mixing with the oil, and elevation of the pulp. In the Elmore the charge includes mixing, the vacuum, and elevation. In the Minerals Separation it includes mixing and aeration by means of violent agitation, and also elevation of the pulp, and in this process the power charge will always be one of the largest. In theory it accomplishes the act of flotation by the direct expenditure of energy.

ACID.—The acid cost is obtained by an indirect method. In the Government reports the tons of acid produced in the year are given, and it has been assumed that it was all used in some of the flotation processes. It is possible that some of the De Bavay or Elmore acid should be charged to Minerals Separation. The error, however, is not large.

OIL.—The Potter-Delprat presumably uses no oil, and this, together with the low labour cost, gives that process a definite lead over all the others. The De Bavay uses a comparatively expensive oil in considerable quantity. The Elmore uses a cheap oil in comparatively large quantity, and Minerals Separation uses a very expensive oil in small quantity.

SUPPLIES.—The item for supplies other than oil, acid, fuel, and water will be just about the same in all the plants. The Potter-

Delprat has a considerable bill for renewal of boxes ; the De Bavay extends over a wide area ; the Elmore has the most machinery ; and the Minerals Separation must renew the mixing devices.

LABOUR.—Considering the simplicity of operations, this cost is excessive when measured by general practice, the general inefficiency of Broken Hill labour, coupled with its high cost, being responsible. The figures given are thought to be reasonably correct for each of the processes, but may contain some error. The Potter-Delprat takes the least number of men to operate ; the De Bavay covers a wide area and requires close attention ; and the Elmore requires more men than either the Potter-Delprat or Minerals Separation.

FUEL FOR HEATING.—The Potter-Delprat process is conducted at a higher temperature than any of the others. The De Bavay operates at the normal temperature, as does the Elmore also generally. The Minerals Separation uses 60° to 70° C.

ASSAYS.—This is a comparative charge, and should not differ in any of the processes ; some of them may have no assay charge.

WATER.—Water at Broken Hill costs 5s. per 1,000 gallons. The loss per ton by unreclaimed water in the residue will be almost identical in each case, as the methods of reclaiming water are similar, being by way of settlement first in tanks until sufficiently dry to travel on a belt or be handled in trucks. The losses by leakage and evaporation should be about the same in each case.

GENERAL EXPENSE.—This charge, being accurately known in one case, is assessed for purposes of comparison to all of the processes at the same figure. There is really a big difference, but this difference is not inherent in the process ; some of the plants are managed efficiently for half the cost of the bad management in others.

CONCLUSIONS.—There is not much to choose between the working costs of the four. The advantage which any one process may have over the others lies in the comparative recovery, grade of concentrate, cost of plant, and general applicability. The working cost of treating copper ores will be about 25% less than the figures given, because less concentrate is handled and less acid in general is used. In spite of the fact that the general average of treatment cost is in the neighbourhood of 4s. per ton in the plants studied, I think that under the efficient management that is given to American mines, and with an efficiently designed plant and properly chosen process, a working cost of 2s. per ton is easily

within reach. The royalty of 1s. per ton does not seem imminently reducible.

As a demonstration of the utility of the invention, we may say, then, that it has already added to the world's wealth nearly 1,000,000 tons of spelter, 100,000 tons of lead, 20,000,000 oz. of silver, and 5,000 tons of copper ; and at the present rate is adding 200,000 tons of spelter, 20,000 tons of lead, 5,000,000 oz. of silver, and 1,000 tons of copper yearly.

CHAPTER XII.

BIBLIOGRAPHY.

The literature of the flotation process is about 10 years old. The published articles have not been many, and what has been published has not been particularly informing. There has been an effective effort on the part of the companies owning the patents to suppress details because of a groundless fear of competition and of new inventions not owned by themselves. The one exception to this line of policy has been the Elmore companies, who have from the very first been quite open in their communications to the public. Whether the other process companies have been wise from a money-making standpoint is their affair. There is no doubt, however, that the development of the art has been seriously delayed, and the industry is thereby the loser. No papers deserving special mention have been published. The few descriptions of plant and processes that exist are of about the same merit. Most of the important papers on the theory of capillary action, surface tension, and adhesion have also been included in the bibliography. Of these the article in the *Encyclopedia Britannica* is the most important.

It is hoped that this bibliography is complete, and that it may serve as a starting-point for many purposes. The author would be thankful for any additions and corrections in the titles to papers that appeared previous to 1912.

ALTA CALIFORNIAN, Dec. 2, 1889.

p. 2, Description of oil process at Denver, 2 columns.

ANNUAL REPORT OF THE DEPARTMENT OF MINES OF NEW SOUTH WALES, for 1901, Sydney, Government Printer, 1902.

p. 80, demand for process.

ANNUAL REPORT OF THE DEPARTMENT OF MINES OF NEW SOUTH WALES, for 1902, Sydney, Government Printer, 1903.

p. 69, Delprat process, 8 lines.

ANNUAL REPORT OF THE DEPARTMENT OF MINES OF NEW SOUTH WALES, for 1903, Sydney, Government Printer, 1904.

p. 42, Potter and Delprat processes, 13 lines.

p. 69, Delprat process, 6 lines; Potter process, 9 lines.

- ANNUAL REPORT OF THE DEPARTMENT OF MINES OF NEW SOUTH WALES, for 1904, Sydney, Government Printer, 1905.
 p. 40, Minerals Separation and Delprat processes, $\frac{3}{4}$ col.
 p. 81, Minerals Separation, Delprat, and Potter processes, 9 lines.
 p. 83, Minerals Separation, 4 lines.
- ANNUAL REPORT OF THE DEPARTMENT OF MINES OF NEW SOUTH WALES, for 1905, Sydney, Government Printer, 1906.
 p. 37, Potter, Delprat, and De Bavay processes, $1\frac{3}{4}$ col. illustrated.
 p. 81, Potter, Minerals Separation, and De Bavay processes, $\frac{1}{2}$ col.
 p. 84, Minerals Separation, 9 lines.
 p. 86, De Bavay process, 6 lines.
- ANNUAL REPORT OF THE DEPARTMENT OF MINES OF NEW SOUTH WALES, for 1906, Sydney, Government Printer, 1907.
 p. 38, De Bavay, Minerals Separation, Gillies, and Delprat processes, 18 lines.
 p. 87, De Bavay, Gillies, Minerals Separation, Elmore, and Delprat processes, 3 pages.
- ANNUAL REPORT OF THE DEPARTMENT OF MINES OF NEW SOUTH WALES, for 1907, Sydney Government Printer, 1908.
 p. 41, Potter, Delprat, De Bavay, and Gillies processes, $1\frac{3}{4}$ col.
 p. 43, Elmore process, 5 lines.
- ANNUAL REPORT OF THE DEPARTMENT OF MINES OF NEW SOUTH WALES, for 1908, Sydney, Government Printer, 1909.
 p. 38, Minerals Separation, De Bavay, and Zinc Corporation, $\frac{1}{2}$ col.
- ANNUAL REPORT OF THE DEPARTMENT OF MINES OF NEW SOUTH WALES, for 1909, Sydney, Government Printer, 1910.
 p. 36, Production of zinc by flotation processes.
 p. 95, Summary of processes, 3 col.
- ANNUAL REPORT OF THE DEPARTMENT OF MINES OF NEW SOUTH WALES, for 1910, Sydney, Government Printer, 1911.
 p. 37, Value of zinc concentrate, 7 lines.
 p. 40, Production of zinc concentrate and processes, 1 column.
 p. 87, Value of exports, $\frac{1}{2}$ col.
- ANNALES DE CHIMIE ET DE PHYSIQUE, 1866-1868, 5th, 6th, and 7th Memoirs on the Mechanical Theory of Heat. Athanase Dupré applied principles of thermo-dynamics to capillary phenomena.
- ARCHIVEN FUR ANATOMIE UND PHYSIOLOGIE, 1894,
 pp. 517-534, 'Separation of Proteids in Solution by Agitation,' by W. Ramsden.
- AUSTRALIAN MINING AND METALLURGY, Donald Clark, 1st edition, Melbourne, 1904.
 p. 397, Broken Hill Ore Treatment, Potter, Goyder and Laughton, and Delprat processes, $8\frac{1}{2}$ pages, illustrated.
 p. 431, Delprat process, 6 lines.
- AUSTRALIAN MINING STANDARD (THE), Vol. XXXV., 1906.
 p. 249, Zinc production.
 p. 273, Minerals Separation process.
 p. 305, Zinc Corporation, Ltd.
 p. 421, ditto.
 p. 562, ditto.
 p. 55, Apparatus for flotation.
 p. 253, Flotation processes.
 p. 556, ditto.
 p. 177, ditto.
 p. 108, Sulphide Corporation.

AUSTRALIAN MINING STANDARD (THE), Vol. XXXVI., 1906.

- p. 2, Flotation-concentration, $\frac{1}{4}$ col.
- p. 4, Patent, Gillies.
- p. 50, Potter *v.* Delprat, $\frac{1}{2}$ col.
- p. 80, Flotation process, $\frac{2}{3}$ col.
- p. 100, Potter *v.* Delprat, 9 lines.
- p. 109, De Bavay process, 1 col.
- p. 123, Potter *v.* Delprat, 15 lines.
- p. 194, Broken Hill Proprietary, $1\frac{1}{2}$ col.
- p. 195, Potter's Sulphide Ore Treatment Co., $\frac{1}{4}$ col.
- p. 223, Broken Hill Proprietary, $1\frac{1}{2}$ col.
- p. 286, Zinc Corporation, 5 lines.
- p. 336, Zinc Corporation and Potter process, $\frac{1}{4}$ col.; De Bavay, 12 lines.
- p. 358, Zinc Corporation and the processes, $\frac{1}{2}$ col.
- p. 405, Zinc Corporation, $\frac{1}{2}$ col.
- p. 407, Patent, Simpson.
- p. 431, Patent, Gillies.
- p. 434, Zinc Corporation, $\frac{1}{2}$ col.
- p. 453, Potter *v.* Delprat, $\frac{1}{2}$ col.
- p. 481, De Bavay Treatment Co., $\frac{1}{4}$ col.
- p. 497, The Zinc Industry, $1\frac{1}{2}$ col.
- p. 498, Zinc Corporation, $\frac{1}{2}$ col.
- p. 529, De Bavay Treatment Co., $\frac{1}{4}$ col.
- p. 550, Patents, Sulman, Picard, and Ballot.


AUSTRALIAN MINING STANDARD (THE), Vol. XXXVII., 1907.

- p. 34, Zinc Corporation, 4 lines.
- p. 50, The Australian Flotation Processes, 1 col.
- p. 78, Flotation Processes, 2 col.
- p. 122, Potter *v.* Broken Hill Proprietary, 1 col.
- p. 126, Zinc Corporation, Elmore and De Bavay, 7 lines.
- p. 127, Central mill, $\frac{1}{4}$ col.
- p. 161, Broken Hill Proprietary, 2 col.
- p. 170, Patent, Chapman.
- p. 217, Elmore, 5 lines.
- p. 218, Zinc Corporation, 10 lines.
- p. 225, Potter's Sulphide Process, 1 col.
- p. 241, Zinc Corporation, $\frac{1}{4}$ col.
- p. 243, Patents, Sulman.
- p. 248, Zinc Corporation, 1 col.
- p. 269, ditto, $1\frac{1}{2}$ col.
- p. 292, ditto, 15 lines.
- p. 338, ditto, $\frac{1}{4}$ col.
- p. 344, ditto, $\frac{1}{4}$ col.
- p. 364, Patent, De Bavay.
- p. 366, Flotation processes, 1 col.
- p. 436, De Bavay Sulphide Process Co., $\frac{1}{4}$ col.
- p. 498, Zinc treatment processes, $\frac{2}{3}$ col.
- p. 521, Zinc Corporation, $\frac{1}{4}$ col.
- p. 525, De Bavay, $\frac{1}{4}$ col.

AUSTRALIAN MINING STANDARD (THE), Vol. XXXVIII., 1907.

- p. 74, Ore Separation, illustrated, $1\frac{1}{2}$ col.
- p. 96, Zinc Corporation shares, one-fifth col.
- p. 167, Mount Lyell and Zinc Corporation, $\frac{1}{2}$ col.
- p. 189, Settlement of law case, $\frac{1}{2}$ col.
- p. 220, Report on Broken Hill Proprietary, $\frac{1}{2}$ col.
- p. 244, Zinc Corporation, 2 col.
- p. 259, ditto, $\frac{1}{2}$ col.

BIBLIOGRAPHY.



AUSTRALIAN MINING STANDARD (THE), Vol. XXXVIII., 1907.

- p. 295, Zinc Corporation, 6 lines.
- p. 342, ditto, $\frac{1}{2}$ col.
- p. 359, Broken Hill Proprietary, tanks, $\frac{1}{3}$ col.
- p. 515, Elmore process, $\frac{1}{3}$ col.

AUSTRALIAN MINING STANDARD (THE), Vol. XXXIX., 1908.

- p. 26, De Bavay, 6 lines.
- p. 54, Sulphide Corporation, $\frac{1}{2}$ col.
- p. 56, Zinc Corporation, Potter, and Ballot, $\frac{1}{2}$ col.
- p. 93, Minerals Separation process, 15 lines.
- p. 121, Patent, Moss.
- p. 152, Minerals Separation process, $\frac{1}{2}$ col.
- p. 155, Elmore process, 10 lines.
- p. 182, Broken Hill Proprietary, 3 col.
- p. 184, Zinc Corporation plant, 1 col.
- p. 189, Elmore process, 2 col.
- p. 207, Potter Sulphide Co., 20 lines.
- p. 216, Flotation processes, $\frac{1}{2}$ col.
- p. 218, Patent, Moss (10237 Aus.).
- p. 240, Sulphide Corporation production.
- p. 246, Zinc Corporation, $\frac{1}{2}$ col.
- p. 278, Patent, Chapman.
- p. 295, Zinc Corporation, 6 lines.
- p. 379, Zinc Corporation, $\frac{1}{4}$ col.
- p. 380, Minerals Separation process, 20 lines.
- p. 441, Flotation processes, $\frac{1}{4}$ col.
- p. 470, ditto, $\frac{1}{2}$ col.
- p. 552, Broken Hill Proprietary, 1 col.
- p. 553, Zinc Corporation, 20 lines.
- p. 584, ditto, 5 lines.
- p. 591, Zinc industry, $\frac{1}{4}$ col.
- p. 616, Ore Concentration Co., $1\frac{1}{4}$ col.
- p. 634, Zinc Corporation, 10 lines.
- p. 640, Central treatment plant, 2 pp.

AUSTRALIAN MINING STANDARD (THE), Vol. XL., 1908.

- p. 90, Zinc Corporation, 7 lines.
- p. 97, ditto, $\frac{1}{4}$ col.
- p. 102, Broken Hill Proprietary, $\frac{2}{3}$ col.
- p. 122, Zinc Corporation, 1 col.
- p. 207, ditto, 3 col.
- p. 208, Broken Hill Proprietary Co., $\frac{2}{3}$ col.
- p. 227, Zinc concentrate, $1\frac{1}{2}$ col.
- p. 238, Broken Hill Proprietary, 3 col.
- p. 239, Zinc Corporation, 1 col.
- p. 255, Potter, $\frac{1}{3}$ col.
- p. 257, Broken Hill Proprietary, 2 col.
- p. 318, Zinc Corporation, $\frac{1}{2}$ col.
- p. 322, Patent, De Bavay.
- p. 338, Zinc Corporation, $\frac{2}{3}$ col.
- p. 399, Production of zinc concentrate, 10 lines.
- p. 403, Flotation processes, $\frac{1}{2}$ col.
- p. 408, Minerals Separation, 2 col.
- p. 431, Zinc Corporation, 20 lines.
- p. 517, Flotation processes, $\frac{1}{2}$ col.
- p. 529, Broken Hill Proprietary, $\frac{1}{2}$ col.
- p. 531, Zinc Corporation, $\frac{1}{4}$ col.
- p. 622, De Bavay, 5 lines.
- p. 675, Elmore v. Ballot, $\frac{1}{2}$ col.

AUSTRALIAN MINING STANDARD (THE), Vol. XI., 1908.

- p. 678, Elmore process, 4 lines.
- p. 687, De Bavay, $\frac{1}{4}$ col.
- p. 688, Zinc Corporation, $\frac{1}{4}$ col.
- p. 721, De Bavay, $\frac{1}{2}$ col.

AUSTRALIAN MINING STANDARD (THE), Vol. XLI., 1909.

- p. 34, Zinc Corporation production, $1\frac{1}{4}$ col.
- p. 97, Sulphide Corporation, 2 col.
- p. 150, Zinc Corporation production, 20 lines.
- p. 174, Sulphide Corporation production, 20 lines.
- p. 229, Broken Hill Proprietary, 2 col.
- p. 243, Potter Sulphide Ore Treatment Co., 20 lines.
- p. 248, Zinc Corporation, 4 lines.
- p. 252, Zinc Corporation production, $\frac{1}{4}$ col.
- p. 276, San Francisco del Oro, 6 lines.
- p. 333, Sulphide Corporation production, 20 lines.
- p. 383, Elmore process, 6 lines.
- p. 395, Zinc Corporation production, 20 lines.
- p. 472, Sulphide Corporation production, $\frac{1}{2}$ col.
- p. 514, Zinc Corporation production, 20 lines.
- p. 527, Zinc Corporation and De Bavay, 25 lines.
- p. 596, Gillies Process Co., 8 lines.
- p. 607, Zinc Corporation production, $\frac{1}{4}$ col.
- p. 626, De Bavay and South Co., $1\frac{1}{2}$ col.
- p. 636, Patent, Horwood.
- p. 658, Murex process, 2 col., illustrated.
- p. 662, British Broken Hill Co., $1\frac{1}{4}$ col.
- p. 667, Zinc Corporation and De Bavay, 20 lines.
- p. 678, Potter Sulphide Ore Treatment Co. v. Minerals Separation Ltd., 1 col.
- p. 689, Zinc Corporation, 2 col.
- p. 58, Sulphide Corporation production, 9 lines ; Zinc Corporation, 3 lines.
- p. 60, Sulphide Corporation production, 20 lines.

AUSTRALIAN MINING STANDARD (THE), Vol. XLII., 1909.

- p. 1, The Zinc industry, 1 col.
- p. 3, Zinc Corporation, $\frac{1}{2}$ col.
- p. 14, ditto, 2 pp., illustrated.
- p. 36, ditto, 20 lines.
- p. 38, Minerals Separation, Ltd., v. Potter, $2\frac{1}{2}$ pp.
- p. 58, Elmore, 10 lines.
- p. 66, De Bavay, $\frac{2}{3}$ col.
- p. 138, Zinc Corporation, 4 lines.
- p. 146, Production of concentrate, $\frac{1}{2}$ col.
- p. 166, De Bavay process, 10 lines.
- p. 167, Elmore process, 8 lines.
- p. 220, Zinc Corporation, 10 lines.
- p. 221, ditto, 8 lines.
- p. 228, Broken Hill Proprietary, 2 col.
- p. 233, Patent, Hoover.
- p. 245, Zinc Corporation and Amalgamated Zinc, 1 col.
- p. 252, Flotation, 4 lines.
- p. 254, Potter Sulphide Ore Treatment, Ltd., $\frac{2}{3}$ col.
- p. 309, Murex process, 2 col.
- p. 332, De Bavay, $\frac{1}{2}$ col.
- p. 360, Production of concentrate, $\frac{1}{4}$ col.
- p. 433, Elmore, 5 lines.
- p. 434, Amalgamated Zinc, $\frac{1}{2}$ col.
- p. 459, ditto, $\frac{1}{4}$ col.

AUSTRALIAN MINING STANDARD (THE), Vol. XLII., 1909.

- p. 498, 'Horwood Process for Sulphide Ores,' by Donald Clark, 2½ col.
- p. 499, Zinc Corporation production, ¼ col.
- p. 501, Sulphide Corporation and Broken Hill Proprietary production, ½ col.
- p. 515, Elmore process, 6 lines.
- p. 519, 'Horwood Process for Sulphide Ores,' by Donald Clark, 3½ col., illustrated.
- p. 542, Elmore v. Minerals Separation, Ltd., ½ col.
- p. 568, Sulphide Corporation, ¼ col.
- p. 569, Horwood process, 10 lines.
- p. 603, Zinc Corporation, ¼ col.
- p. 604, Murex, 5 lines; production of Broken Hill Proprietary, ¼ col.
- p. 605, Production of Sulphide Corporation, 15 lines.
- p. 621, Sulphide Corporation, ½ col.
- p. 648, Litigation, 20 lines.
- p. 677, Ore Concentration Co., ½ col.
- p. 687, British Ore Concentration Syndicate, Ltd., v. Minerals Separation, Ltd., 3½ pp.

AUSTRALIAN MINING STANDARD (THE), Vol. XLIII., 1910.

- p. 5, Zinc production at Broken Hill, ½ col.
- p. 16, Minerals Separation, 2 col.
- p. 30, Output of Fitzroy mines, ¼ col.
- p. 66, Murex experiments, ¼ col.
- p. 94, Sulphide Corporation, 1¼ col.
- p. 136, Broken Hill mining, 1 col.
- p. 146, Zinc Corporation, ¼ col.
- p. 160, Purchase of tailings, 10 lines.
- p. 161, Elmore plant at Broken Hill, 10 lines.
- p. 172, Sulphide Corporation, 20 lines.
- p. 185, J. H. Gillies in Tasmania, 15 lines.
- p. 191, Results of extraction, 15 lines.
- p. 196, Difference for flotation, etc., ⅔ col.
- p. 198, Broken Hill Proprietary, one-fifth col.
- p. 199, Broken Hill South S. Co., 10 lines.
- p. 226, Reports of companies, ⅔ col.
- p. 236, Inventions in the U.S.A. and Australia, ¼ col.
- p. 248, Developments in N.S.W., ¼ col.
- p. 315, Concentrate in Norway, 5 lines.
- p. 317, Broken Hill prospects, ½ col.
- p. 327, Broken Hill Proprietary Co., ¼ col.
- p. 343, The production of zinc concentrate, ½ col.
- p. 393, Murex process, 3 lines.
- p. 395, De Bavay, 9 lines.
- p. 432, Broken Hill Proprietary, ¼ col.
- p. 478, Broken Hill mining, 1 col.
- p. 484, Zinc Corporation, ¼ col.
- p. 484, Sulphide Corporation, 10 lines.
- p. 497, T. J. Hoover improvements, 7 lines.
- p. 497, Annual Meeting, Govett, 18 lines.
- p. 510, Unsold tailing, ¼ col.
- p. 510, De Bavay, 20 lines.
- p. 511, Sulphide Corporation, 10 lines.
- p. 511, Zinc concentrate, 6 lines.
- p. 524, Broken Hill prospects, 1¼ col.
- p. 537, Broken Hill Proprietary, 20 lines.
- p. 550, Zinc Corporation, 10 lines.
- p. 563, Elmore plant, 12 lines.
- p. 590, Broken Hill Block 14 Co., 15 lines.

AUSTRALIAN MINING STANDARD (THE), Vol. XLIII., 1910.

- p. 590, Zinc Corporation, $\frac{1}{3}$ col.
- p. 601, Output Broken Hill Proprietary, 15 lines.
- p. 640, Murex Magnetic unit, 15 lines.
- p. 641, De Bavay, 1 page.
- p. 642, Broken Hill Proprietary Co., $\frac{1}{2}$ col.

AUSTRALIAN MINING STANDARD (THE), Vol. XLIV., 1910.

- p. 3, Concentration of sulphides, 15 lines.
- p. 5, Murex process, $\frac{2}{3}$ col.
- p. 45, Amalgamated Zinc and Zinc Corporation, $\frac{1}{2}$ col.
- p. 63, Oil flotation process at Broken Hill, T. J. H., 3 pages.
- p. 73, Sulphide Corporation, 18 lines.
- p. 73, Broken Hill Proprietary, $\frac{1}{2}$ col.
- p. 90, Broken Hill prospects, 1 col.
- p. 115, Murex process, 10 lines.
- p. 155, Zinc Corporation, $\frac{1}{4}$ col.
- p. 182, Broken Hill Proprietary, $\frac{1}{2}$ col.
- p. 183, De Bavay, output, one-fifth col.
- p. 210, Broken Hill Proprietary, $\frac{1}{3}$ col.
- p. 210, Broken Hill South, $\frac{1}{3}$ col.
- p. 226, British zinc flotation plant, 20 lines.
- p. 227, Murex Magnetic, 20 lines.
- p. 233, Additions to plant, illustrated, 2 pages.
- p. 250, Central Zinc company, $\frac{1}{4}$ col.
- p. 251, Sulphide Corporation, 10 lines.
- p. 252, Litigation, De Bavay, one-fifth col.
- p. 264, Potter's Sulphide Ore Treatment Co., one-fifth col.
- p. 277, Litigation, 20 lines.
- p. 278, Murex process, 8 lines.
- p. 289, Broken Hill Proprietary Co., $\frac{1}{2}$ col.
- p. 290, De Bavay, one-fifth col.
- p. 314, Eucalyptus oil, $\frac{1}{3}$ col.
- p. 315, Broken Hill, $\frac{1}{6}$ col.
- p. 330, British Broken Hill, 10 lines.
- p. 333, Oil flotation at Broken Hill, $\frac{2}{3}$ col.
- p. 337, Murex Magnetic plant, 20 lines.
- p. 383, Zinc plant, British mine, 20 lines.
- p. 393, Great Fitzroy, $\frac{1}{2}$ col.
- p. 393, Broken Hill Proprietary, $\frac{1}{2}$ col.
- p. 415, Commonwealth Oil Corporation, 2 col.
- p. 418, Broken Hill prospects, 1 col.
- p. 419, Returns, $\frac{1}{3}$ col.
- p. 433, Minerals Separation American Syndicate, 8 lines.
- p. 444, Broken Hill prospects, 1 col.
- p. 460, ditto, $1\frac{1}{2}$ col.
- p. 494, ditto, 1 col.
- p. 517, Block 10, $\frac{1}{3}$ col.
- p. 517, Amalgamated Zinc, $\frac{1}{4}$ col.
- p. 517, Zinc Corporation, $\frac{1}{4}$ col.
- p. 538, Murex, 20 lines.
- p. 557, ditto, 3 lines.
- p. 561, ditto, $\frac{1}{2}$ col.
- p. 562, Process production, 2 col.
- p. 488, Murex, $\frac{1}{4}$ col.
- p. 488, Processes, $\frac{1}{2}$ col.
- p. 612, Murex, 10 lines.
- p. 614, Amalgamated Zinc, 2 cols.
- p. 637, Murex, 20 lines.

AUSTRALIAN MINING STANDARD (THE), Vol. XLV., 1911.

- p. 16, Zinc Corporation, $\frac{1}{4}$ col.
- p. 68, Production of concentrate, $\frac{1}{2}$ col.
- p. 116, Murex, 5 lines.
- p. 117, Sulphide Corporation, $\frac{1}{2}$ col.
- p. 142, Minerals Separation, $\frac{1}{2}$ col.
- p. 159, Zinc Corporation and Amalgamated Zinc, $\frac{1}{2}$ col.
- p. 170, Zinc Corporation, $\frac{1}{4}$ col.
- p. 181, Minerals Separation process and Zinc Corporation, 2 col.
- p. 186, Murex, 12 lines.
- p. 195, Broken Hill Proprietary and Amalgamated Zinc, $1\frac{1}{2}$ col.
- p. 219, Minerals Separation process, $\frac{1}{4}$ col.; Broken Hill Proprietary, 1 col.
- p. 220, Potter process, $\frac{1}{4}$ col.
- p. 244, Elmore process at the British mine, $\frac{1}{4}$ col.; start of Central slime-plant in March, 10 lines.
- p. 245, Zinc Corporation, $\frac{1}{4}$ col.
- p. 270, Minerals Separation process, 10 lines.
- p. 284, Murex process, 20 lines.
- p. 297, Amalgamated Zinc, $\frac{1}{4}$ col.
- p. 311, Litigation, Potter v. Ballot, $\frac{1}{2}$ col.
- p. 323, Broken Hill Proprietary, $\frac{1}{4}$ col.
- p. 340, Minerals Separation process at Junction North, $\frac{1}{4}$ col.
- p. 343, 'Flotation of Minerals,' by Kenneth A. Mickle, $2\frac{1}{2}$ col.
- p. 365, Minerals Separation process at Zinc Corporation, $\frac{1}{4}$ col.
- p. 366, Elmore process at the British mine.
- p. 368, 'Flotation of Minerals,' by Kenneth A. Mickle, 3 col.
- p. 371, Production of zinc concentrate in 1910, 1 col.
- p. 372, Productions, $\frac{1}{2}$ col.
- p. 394, 'Flotation of Minerals,' by Kenneth A. Mickle, 3 pp
- p. 398, Amalgamated Zinc, $\frac{1}{4}$ col.
- p. 416, 'Flotation of Minerals,' by Kenneth A. Mickle, 2 col.; Ore Concentration Co., Ltd., litigation, 1 col.
- p. 437, Murex process, $\frac{1}{2}$ col.
- p. 443, Sulphide Corporation, 20 lines.
- p. 459, Murex, 3 lines.
- p. 462, Zinc Corporation, Elmore, and Ballot, $\frac{1}{2}$ col.
- p. 469, Zinc Corporation, $\frac{1}{4}$ col.
- p. 484, ditto, $\frac{1}{2}$ col.
- p. 488, Murex, 10 lines; Ballot, 15 lines.
- p. 492, Zinc Corporation, $\frac{1}{4}$ col.; Proprietary, 15 lines.
- p. 509, Zinc Corporation, 8 lines.
- p. 516, Minerals Separation process at the Junction, 10 lines.
- p. 520, Amalgamated Zinc, $\frac{1}{4}$ col.
- p. 539, Elmore v. Ballot litigation, 1 page.
- p. 544, Zinc concentrates, 12 lines.
- p. 564, Elmore process, $\frac{1}{2}$ col.
- p. 566, The Flotation Processes, $1\frac{1}{2}$ col.
- p. 571, Reports of companies, $\frac{1}{2}$ col.

AUSTRALIAN MINING STANDARD (THE), Vol. XLVI., 1911.

- p. 41, Zinc Corporation, $\frac{1}{4}$ col.; Proprietary, $\frac{1}{4}$ col.
- p. 54, Litigation, $\frac{1}{2}$ col.
- p. 55, Zinc Corporation and South Blocks, 10 lines.
- p. 56, Amalgamated Zinc, $1\frac{1}{4}$ col.
- p. 66, Amalgamated Zinc and Sulphide Corporation, $\frac{1}{4}$ col.
- p. 79, Bibliography, 2 lines.
- p. 80, Litigation, $\frac{1}{2}$ col.
- p. 108, Text of decision Elmore v. Ballot, 3 col.

AUSTRALIAN MINING STANDARD (THE), XLVI., 1911.

- p. 130, Litigation, $\frac{1}{2}$ col.
- p. 141, Reports of companies, 1 col.
- p. 167, Eucalyptus oil for flotation, $\frac{2}{3}$ col.
- p. 167, Amalgamated Zinc, $\frac{1}{4}$ col.
- p. 193, Broken Hill Proprietary, $\frac{1}{4}$ col.
- p. 210, Zinc Corporation, 5 lines.
- p. 213, Bibliography, 2 lines.
- p. 219, Potter process, $\frac{1}{4}$ col.
- p. 219, Amalgamated Zinc, 10 lines.
- p. 243, Potter Sulphide Co., 20 lines.
- p. 243, Sulphide Corporation, $\frac{1}{4}$ col.
- p. 243, Broken Hill Proprietary, $\frac{1}{4}$ col.
- p. 262, New slime flotation process at Broken Hill Proprietary, 20 lines.
- p. 269, Working results for month, 1 col.
- p. 287, Amalgamated Zinc, $\frac{1}{2}$ col.
- p. 288, Amalgamated Zinc, 10 lines.
- p. 293, Amalgamated Zinc, 2 pp.
- p. 313, Surplus concentrates at Broken Hill, 20 lines; Amalgamated Zinc, Potter, and Murex processes, 20 lines; Zinc Corporation, 2 lines.
- p. 317, Great Fitzroy, $\frac{1}{2}$ col.
- p. 342, Sulphide Corporation, 12 lines.
- p. 357, Broken Hill news, 1 col.
- p. 363, Broken Hill statistics, 10 lines.
- p. 371, Great Fitzroy, Zinc Corporation, Amalgamated Zinc, Broken Hill Proprietary, 1 col.
- p. 389, Broken Hill news, $\frac{1}{4}$ col.
- p. 411, Ballot, 10 lines.
- p. 415, Minerals Separation process on Junction North Mine, 10 lines.
- p. 422, Minerals Separation process on Great Fitzroy mine, 10 lines.
- p. 439, Broken Hill news, 1 col.
- p. 443, ditto statistics, 1 col.
- p. 465, ditto news, $\frac{1}{2}$ col.
- p. 469, ditto statistics, $\frac{1}{2}$ col.
- p. 489, ditto production, $\frac{1}{4}$ col.
- p. 494, ditto statistics, $\frac{1}{2}$ col.
- p. 517, ditto news, $\frac{1}{2}$ col.
- p. 520, Junction North mine, $\frac{1}{4}$ col.
- p. 522, 'Mixed Sulphides,' W. R. Ingalls, 3 col.
- p. 542, Broken Hill news, 1 col.
- p. 546, ditto statistics, $\frac{1}{4}$ col.
- p. 566, ditto news, 1 col.
- p. 572, ditto statistics, $\frac{1}{4}$ col.
- p. 593, ditto news, 1 col.
- p. 598, ditto statistics, 1 col.
- p. 617, ditto news, 1 col.

AUSTRALIAN MINING STANDARD (THE), Vol. XLVII., 1912.

- pp. 333, 357, 381, 403, 'Flotation of Minerals,' by Kenneth A. Mickle, $4\frac{1}{2}$ pp., illustrated.

BULLETIN DE L'INDUSTRIE MINERALE, Series 4, Vol. VII., 1907.

- p. 199, 'The Elmore Process,' by Alexander Stanley Elmore.

BULLETIN DE L'INDUSTRIE MINERALE, Vol. VIII., 1908.

- p. 789, 'Elmore Process,' by C. Göpner.

BULLETIN No. 42, INSTITUTION OF MINING AND METALLURGY, March 12th, 1908.

- Discussion, H. L. Sulman, 'A Method of Settling Slime.'

- BULLETIN No. 79, INSTITUTION OF MINING AND METALLURGY, April 19, 1911,
p. 9. In his presidential address H. Livingstone Sulman presents some
new discoveries in the physics of ore flotation, 8 pages.
- BRITISH COLUMBIA MINING EXCHANGE.
September, 1904, Elmore process at White Bear mine.
February, 1905, 'Elmore at Le Roi mine,' H. H. Claudet.
- CANADIAN MINING JOURNAL, Vol. XXX.
p. 279, 'Behrend Flotation Process.'
- CANADIAN MINING JOURNAL, October 15, 1908.
'Macquisten Flotation Process,' A. Selwyn Brown.
- CANADIAN MINING REVIEW (THE), Vol. XXIV., 1905.
p. 177, 'Reason for failure of Elmore process at Rossland,' Alexander
Stanley Elmore.
- CHEMICAL NEWS (THE), Vol. LXXXVIII., 1903.
p. 49, 'Separation of Solids in the Surface Layers of Suspensions,'
W. Ramsden.
- COLLECTED SCIENTIFIC PAPERS, 1901.
Lord Rayleigh.
- COMMENT SOC. REG. GOTTING, I (1751).
p. 301, J. A. von Sequer; Surface tension of liquids.
- COMPTES RENDUES MENSUELS, June, 1903.
p. 131, H. Tenicque, 'Mechanical Preparation and Concentration of
Minerals,' Elmore process.
- DE AQUAE COMMUNIS NONNULLIS QUALITATIBUS TRACTALUS, Driesburg,
1756.
J. D. Leidenfrost, soap bubbles.
- DETERMINATIC SUPERFICIEI MINIMAE rotatione curvae data duo puncta jugentis
circa datum axem ortae (Gottingen, 1831). Goldschmidt.
- DIE LEHRE VON DER COHASION, FRANKENHEIM, BRESLAU, 1835.
Points d'appui.
- DRESSING OF MINERALS, London, 1909, Henry Louis, pp. 442-449, flotation
processes.
- ECHO DES MINES, January 30, 1911.
p. 122, Etat actuel de la Preparation des Minerals, 1600 W.
- ECHO DES MINES, November 13, 1911.
Flotation of minerals, 1,000 words.
- ELECTROCHEMICAL AND METALLURGICAL INDUSTRY, Vol. IV., 1906.
p. 49, Ore Dressing by Flotation, 3 pp.
p. 206, Flotation processes, 1 col.
p. 432, ditto, 2 lines.
p. 506, ditto, 1 col.
- ELECTROCHEMICAL AND METALLURGICAL INDUSTRY, Vol. V., 1907.
p. 320, Flotation processes, 1 col.
- ELECTROCHEMICAL AND METALLURGICAL INDUSTRY, Vol. VI., 1908.
p. 100, Notes on processes, $\frac{1}{2}$ col.
p. 174, Editorial, $\frac{1}{2}$ col.
p. 185, 'Ore Dressing,' 2 pages, illustrated.
- ELECTROCHEMICAL AND METALLURGICAL INDUSTRY, Vol. VII., 1909.
p. 275, 'Electromagnetic Flotation Processes,' 1 col. illustrated,
extract of paper read by A. P. Steckel before the Niagara Falls
meeting of the American Electrochemical Society, May 6, 1909.

ELECTROCHEMICAL AND METALLURGICAL INDUSTRY, Vol. VIII., 1910.

- p. 204, Elmore process, $\frac{1}{2}$ col.
- p. 205, Horwood process, $\frac{1}{2}$ col.
- p. 425, Elmore process, 1 col., illustrated.
- p. 498, Potter process, $\frac{1}{2}$ col.
- p. 509, Elmore process, 6 lines.
- p. 556, Coagulation of slime, $1\frac{1}{2}$ col.
- p. 603, Elmore process, 4 lines.
- p. 704, ditto, 3 lines.

ELECTROCHEMICAL AND METALLURGICAL INDUSTRY, Vol. IX., 1911.

- p. 38, Flotation processes, $\frac{1}{2}$ col.
- p. 115, Elmore process, 3 lines.
- p. 236, Macquisten process, $\frac{1}{2}$ col.
- p. 324, Extract from presidential address of H. L. Sulman, flotation processes, 1 col.
- p. 381, Elmore process, 6 lines.

ELEMENTARY PRINCIPLES IN STATISTICAL MECHANICS, 1902.
Josiah Willard Gibbs.

ENCYCLOPEDIA BRITANNICA, 11th edition, 1911, Vol. V.

- p. 256, 'Capillary Action.'

ENGINEERING AND MINING JOURNAL, Vol. L., 1890.

- p. 581, Describes the Everson oil flotation process, 20 lines.

ENGINEERING AND MINING JOURNAL, Vol. LV., 1893.

- p. 323, Patent, Bradford.

ENGINEERING AND MINING JOURNAL, Vol. LXI., 1896.

- p. 186, Patent, Robson and Crowder.

ENGINEERING AND MINING JOURNAL, Vol. LXVI., 1898.

- p. 63, 'Measuring Surface Tension of Liquids,' F. T. Trouton, 17 lines.

ENGINEERING AND MINING JOURNAL, Vol. LXIX., 1900.

- p. 355, Patent, Elmore.
- p. 732, Elmore process, $\frac{1}{2}$ page.
- p. 742, Extract from 'Notes on the Elmore Concentration Process,' by Charles M. Rolker, in Vol. VIII., Trans. Ins. Mining and Metallurgy, $\frac{1}{2}$ page.

ENGINEERING AND MINING JOURNAL, Vol. LXX., 1900.

- p. 63, Elmore process, $\frac{1}{2}$ col.
- p. 104, Patent, Elmore.
- p. 196, Elmore, 6 lines.
- p. 241, Editorial on oil concentration, 6 lines.
- p. 393, Elmore process, 24 lines.
- p. 515, Concentrating antimony ores, 9 lines.
- p. 661, Editorial on oil concentration, 12 lines.

ENGINEERING AND MINING JOURNAL, Vol. LXXI., 1901.

- p. 691, Elmore process, 1 page and illustrated.
- p. 829, ditto, 7 lines.

ENGINEERING AND MINING JOURNAL, Vol. LXXII., 1901.

- p. 14, Patent, Elmore.

ENGINEERING AND MINING JOURNAL, Vol. LXXIII., 1902.

- p. 54, Elmore process, 3 lines.
- p. 144, The Oil Concentrating Process, 7 lines.
- p. 283, Patent, Elmore.
- p. 591, Patent, Potter.

ENGINEERING AND MINING JOURNAL, Vol. LXXIV., 1902.

- p. 21, Patent, Elmore.
- p. 30, Elmore process, 17 lines.
- p. 157, Patent, Haultain.
- p. 188, Concentrating Molybdenite, by Ore Concentration Syndicate, Ltd., 16 lines.
- p. 371, Elmore process, 1 page and illustrated.
- p. 487, Elmore process, 12 lines.

ENGINEERING AND MINING JOURNAL, Vol. LXXV., 1903.

- p. 113, Results of Oil Concentration Process, $\frac{1}{2}$ col.
- p. 134, British Ore Concentration Syndicate, 18 lines.
- p. 156, ditto, 1 col.
- p. 235, Delprat process, $\frac{1}{2}$ col.
- p. 250, Concentration by Oil, $\frac{1}{2}$ col.
- pp. 262 and 292, 'Concentration of Ores by Oil,' W. McDermott, 3 $\frac{1}{2}$ pages and illustrated.
- p. 344, Elmore process, 4 lines.
- p. 535, Delprat process, 8 lines.
- p. 676, ditto, 9 lines.
- p. 683, ditto, 5 lines.
- p. 723, ditto, $\frac{1}{4}$ col.
- p. 753, Elmore process, $\frac{1}{4}$ col.
- p. 979, ditto, 13 lines.

ENGINEERING AND MINING JOURNAL, Vol. LXXVI., 1903.

- p. 64, Elmore process, 4 lines.
- p. 100, Delprat process, 10 lines.
- p. 136, Elmore process, 9 lines.
- p. 170, Patent, Froment.
- p. 225, Editorial on Elmore process, $\frac{1}{4}$ col.
- p. 244, 'Copper Sulphide in Iron Ores, Oil Concentration,' by Alexander Stanley Elmore, $\frac{1}{4}$ col.
- p. 245, Patent, Delprat.
- p. 284, Patent, Delprat.
- p. 382, Patent, Vander Naillen.
- p. 692, The Broken Hill Salt-Cake Process for Zinky Ore, $\frac{1}{4}$ col.
- p. 708, Patent, Goyder and Laughton.
- p. 710, Elmore process, 14 lines.
- p. 787, Elmore process, 19 lines.
- p. 820, 'Aluminated Oil,' by J. W. Van Meter, 1 $\frac{1}{2}$ col.
- p. 822, Patent, Delprat.
- p. 840, Editorial on Elmore process, 14 lines.
- p. 846, Delprat's Method for Separating Mixed Sulphide Ores, $\frac{1}{4}$ col.
- p. 900, Patent, Schammell.
- p. 900, Patent, Delprat.

ENGINEERING AND MINING JOURNAL, Vol. LXXVII., 1904.

- p. 32, Delprat process, 5 lines.
- p. 122, 'The Delprat or Salt-Cake Process for Mixed Sulphides,' by Donald Clark, 2 col.
- pp. 152, 153, 'Oil for Concentration of Ores,' by Walter McDermott, 2 col.
- p. 170, Patent, Jamieson and Odling; patent, Elmore.
- p. 172, Elmore, Potter, and Delprat processes, 7 lines.
- p. 250, Patent, Cattermole.
- pp. 283, 284, 'Cheticamp,' F. P. Ronnan, 1 $\frac{1}{2}$ page.
- p. 332, Elmore process, $\frac{1}{4}$ col.
- p. 372, ditto, $\frac{1}{4}$ col.
- p. 490, Patent, Cattermole.
- p. 576, Elmore process, 7 lines.

ENGINEERING AND MINING JOURNAL, Vol. LXXVII., 1904.

- p. 611, 'Oil Concentration on Copper Ores,' F. P. Ronnan, $\frac{1}{4}$ col.
- p. 616, Elmore process, 17 lines.
- p. 896, ditto, $\frac{3}{4}$ col.
- p. 974, Patent, Delprat.
- p. 1014, Patent, Van Meter and Boss.
- p. 1054, Patent, Cattermole.

ENGINEERING AND MINING JOURNAL, Vol. LXXVIII., 1904.

- p. 32, Patent, Darling; Patent, Delprat; Patent, Goyder and Laughton.
- p. 75, Potter and Delprat processes; 9 lines.
- p. 147, The Potter zinc process, $\frac{1}{4}$ col.
- p. 231, Patent, Schwarz.
- p. 275, Delprat process, $\frac{1}{4}$ col.
- p. 359, Patent, Delprat.
- p. 394, 'The Potter Process,' Donald Clark, 1 page, illustrated.
- p. 417, Editorial on Delprat, Potter, and Goyder and Laughton processes, 14 lines.
- p. 438, 'Concentration of Platinum Ores,' Alexander Stanley Elmore, 17 lines.
- p. 443, Delprat, and Goyder and Laughton processes, 19 lines.
- p. 497, Editorial on Elmore process, $\frac{1}{4}$ col.
- p. 499, 'Zinc Tailing at Broken Hill,' Potter and Delprat processes, $1\frac{1}{2}$ col.
- p. 500, Elmore process, 4 lines.
- p. 520, Patent, Scammell.
- p. 560, Patent, Kendall; Patent, Cattermole, Sulman and Picard.
- p. 599, Patent, Schwarz.
- p. 603, Cattermole process, 18 lines.
- p. 684, Delprat process, $\frac{1}{4}$ col.
- p. 764, Delprat process, 12 lines.
- p. 858, Editorial on Potter and Delprat processes, $\frac{1}{2}$ col.
- pp. 871, 872, 'Zinc at Broken Hill,' F. H. Bathurst (Potter v. Delprat), 1 page.
- p. 920, Patent, Potter.
- p. 960, Patent, Sulman and Picard.
- p. 997, 'Oil Concentration of Bismuth Ores,' Alexander Stanley Elmore, $\frac{1}{4}$ col.
- p. 1000, Patent, Cattermole; patent, Cattermole, Sulman and Picard; patent, Gillies.
- p. 1004, De Bavay process, 17 lines.

ENGINEERING AND MINING JOURNAL, Vol. LXXIX., 1905.

- p. 107, Patent, Gillies.
- p. 113, Potter and Delprat processes, $\frac{1}{4}$ col.
- p. 160, Elmore process, $\frac{3}{4}$ col.
- pp. 201, 202, 'Report Le Roi No. 2,' Elmore process, $1\frac{1}{2}$ col.
- p. 253, Gillies patent.
- p. 403, Potter and Delprat processes, $\frac{1}{4}$ col.
- p. 424, 'The Acid Salt-Cake Process,' $\frac{1}{2}$ col.
- p. 590, Patent, Schwarz; patent, Wolf.
- p. 637, Patent, Goyder and Laughton.
- p. 643, Delprat process, $\frac{1}{4}$ col.
- p. 835, Delprat process, 14 lines.
- p. 877, Patent, Wolf.
- p. 926, Patent, Cattermole, Sulman and Picard.
- p. 968, Delprat process, 3 lines.
- p. 1113, Delprat and Potter processes, 7 lines.

ENGINEERING AND MINING JOURNAL, Vol. LXXX., 1905.

- p. 15, 'Concentration of Copper Ore,' Frank H. Probert, 1 page.

ENGINEERING AND MINING JOURNAL, Vol. LXXX., 1905.

- p. 59, Zinc Production at Broken Hill, $\frac{1}{4}$ col.
- p. 76, Patent, Sulman and Picard.
- p. 118, 'Concentration of Molybdenite Ores,' Alexander Stanley Elmore, $\frac{1}{2}$ col.
- pp. 226, 227, Potter and Delprat processes, 7 lines.
- p. 257, The Elmore Process for Diamond Recovery, $\frac{3}{4}$ col.
- p. 266, Patent, Sulman and Picard.
- p. 289, 'Mixed Sulphide Ore Treatment,' W. R. Ingalls, page 1.
- p. 304, Oil Concentration, Minerals Separation and Elmore processes, 2 col.
- p. 350, Progress at Broken Hill, $\frac{1}{2}$ col.
- p. 385, 'The Newer Treatment of Broken Hill Sulphides,' A. Selwyn-Brown, 1 page.
- p. 410, Patent, Sulman, Picard and Ballot.
- p. 565, Delprat process, 15 lines.
- p. 643, Improvements in Ore Concentration, flotation processes, 1 page.
- p. 649, Patent, Ward.
- p. 692, De Bavay process, 7 lines.
- p. 736, Elmore process, 15 lines.
- p. 746, Patent, De Bavay.
- p. 786, Zinc Corporation, De Bavay, and New Elmore processes, 1 col.
- p. 928, Broken Hill Zinc, 2 col.
- p. 1082, Patent, Elmore; patent, De Bavay.
- p. 1177, Patent, Elmore.
- p. 1225, Patent, Wolf; patent, Schwarz.
- p. 1235, Potter process, 15 lines.

ENGINEERING AND MINING JOURNAL, Vol. LXXXI., 1906.

- pp. 12, 14, 'Zinc,' W. R. Ingalls, 2 pages.
- pp. 35, 36, 'Eastern States of Australia,' F. S. Mance, $1\frac{1}{2}$ pages.
- p. 43, Elmore process, $\frac{1}{4}$ col.
- p. 194, Patent, Kirby; Patent, Elmore.
- pp. 276, 277, 'The Physics of Ore Flotation,' J. Swinburne and C. Rudort, $1\frac{1}{2}$ pages.
- p. 289, Patent, Pohle; patent, Macquisten.
- pp. 314, 317, 'Flotation Processes,' A. K. Huntington, $2\frac{3}{4}$ pages.
- pp. 333, 334, 'Concentration of Silicious Copper Ore,' W. E. P., 2 col.
- p. 540, De Bavay, Potter, Delprat and Gillies processes, 8 lines.
- p. 573, 'Concentration of Silicious Copper Ore,' L. R. L., $\frac{1}{4}$ col.
- p. 577, Patent, Sulman, Picard and Ballot.
- pp. 621, 622, 'Concentration of Silicious Copper Ore, W. E. P., 2 col.
- p. 655, The Kirby Oil Process, $\frac{1}{4}$ col.
- p. 716, 'Ore Dressing by Flotation,' J. A. Snedaker, $\frac{1}{4}$ col.
- p. 770, Patent, Saunders.
- p. 813, Potter process, 10 lines.
- p. 819, Patent, Sulman, Picard, and Ballot.
- p. 1000, The Potter Flotation Process, 1 col.
- p. 1213, Potter process, $\frac{1}{2}$ col.

ENGINEERING AND MINING JOURNAL, Vol. LXXXII., 1906.

- p. 28, The Potter process, 7 lines.
- p. 76, Patent, Macquisten.
- p. 124, Patents, Schwarz.
- p. 172, Patent, Elmore.
- p. 266, 'Native Oil Concentration in Columbia,' G. R. Snover, $\frac{1}{2}$ col.
- pp. 344, 346, The De Bavay Process, $1\frac{1}{2}$ pages, illustrated.
- p. 460, Patent, Sulman.
- p. 701, De Bavay process, 16 lines.
- p. 733, Notes from Broken Hill, N.S.W., $\frac{1}{2}$ col.

ENGINEERING AND MINING JOURNAL, Vol. LXXXII., 1906.

- p. 748, Potter process, 9 lines.
- p. 826, 'Zinc Concentration in Australia,' Edward Walker, $\frac{1}{2}$ col.
- p. 895, Potter process, $\frac{1}{4}$ col.
- p. 938, Patent, Sulman, Picard, and Ballot.
- p. 964, Notes from Broken Hill, $1\frac{1}{4}$ col.
- p. 966, 'The Flotation Processes at Broken Hill,' Donald Clark, 2 col.
- p. 986, Patent, Sulman, Picard, and Ballot.
- p. 1086, Patent, Sulman, Picard, and Ballot.
- pp. 1113 to 1115, 'The Flotation Processes,' W. R. Ingalls, $2\frac{1}{2}$ pages.
- p. 1115, The De Bavay Process, $\frac{1}{2}$ col.
- p. 1135, Patent, Chapman.
- p. 1179, Theory and Practice, flotation processes, 1 col.

ENGINEERING AND MINING JOURNAL, Vol. LXXXIII., 1907.

- p. 19, Concentration, $\frac{1}{2}$ col.
- pp. 20, 21, 'Progress in the Metallurgy of Zinc,' W. R. Ingalls, $\frac{3}{4}$ col.
- pp. 45 to 47, 'The Eastern States of Australia,' F. S. Mance, 2 pages.
- p. 86, 'The London Mining Market,' Edward Walker, 1 page.
- p. 249, Patent, Wolf.
- p. 303, Potter process, $\frac{1}{2}$ col.
- pp. 317-321, 'Ore Dressing at Broken Hill,' G. D. Delprat, 5 pages, illustrated.
- p. 344, 'Theories Concerning the Flotation Process,' G. Haglund, $1\frac{1}{2}$ col.
- p. 346, Patent, Schwarz.
- p. 389, Potter and Delprat processes, $\frac{1}{4}$ col.
- pp. 516-519, 'The Lead-Smelting Works of Port Pirie,' G. D. Delprat, 4 pages, illustrated.
- p. 675, More Flotation Process Litigation, Potter and Delprat processes, $\frac{3}{4}$ col.
- p. 800, 'The Elmore Vacuum Process,' Edward Walker, $2\frac{1}{2}$ col.
- p. 865, The Flotation Process Litigation, Potter and Delprat processes, 1 col.
- pp. 908, 909, 'Vacuum Flotation,' Alexander Stanley Elmore, 2 pages, illustrated.
- p. 917, The Elmore Vacuum Process, 1 col.
- pp. 939, 940, Spelter at United Rico Mines, 2 pages, illustrated.
- p. 948, 'Mineral Production of Eastern Australia,' F. S. Mance, 1 page.
- pp. 1037, 1038, 'Novel Equipment of Tywarnhaile Copper Mine,' Edward Walker, $1\frac{1}{2}$ pages, illustrated.
- pp. 1110, 1111, 'The Elmore Vacuum Process,' Alexander Stanley Elmore, $1\frac{1}{4}$ col.
- p. 1205, 'The Elmore Vacuum Flotation Process,' F. H. Prentiss, $1\frac{1}{2}$ col.
- p. 1207, Elmore process, 9 lines.

ENGINEERING AND MINING JOURNAL, Vol. LXXXIV., 1907.

- p. 51, 'Flotation Processes at Broken Hill,' F. H. Jackson, 8 lines.
- p. 122, Delprat process, $\frac{1}{4}$ col.
- p. 280, Zinc Corporation and Potter process, $\frac{1}{2}$ col.
- p. 414, Patent, Sulman.
- p. 477, Bibliography, Göpner, 8 lines.
- p. 604, Patents, Elmore, Sulman, De Bavay, Macquisten, Norris.
- p. 669, Bibliography, Göpner, 5 lines.
- p. 689, Broken Hill Proprietary report, $2\frac{1}{2}$ col.
- p. 733, Zinc Corporation, 13 lines.
- pp. 765-770, 'Concentration Upside Down,' W. R. Ingalls, $5\frac{1}{2}$ pages, illustrated.
- p. 842, Elmore process, 8 lines.
- p. 870, Elmore process, 7 lines.

ENGINEERING AND MINING JOURNAL, Vol. LXXXIV., 1907.

- p. 1101, Bibliography, Ingalls, 11 lines.
- p. 1103-1105, 'The Elmore Vacuum Process at Dolcoath,' Edward Walker, 3 pages, illustrated.
- p. 1210, Elmore process, 12 lines.

ENGINEERING AND MINING JOURNAL, Vol. LXXXV., 1908.

- pp. 60-63, 'Mining in Australia in 1907,' F. S. Mance, 2½ pages.
- p. 295, 'Progress in Ore Dressing in 1907,' J. M. McClave, 7 lines.
- p. 539, Bibliography, Göpner and Granigg, 17 lines.
- p. 665, Patent, Sulman and Picard.
- p. 941, Bibliography, Linde and Haywood, 13 lines.
- p. 1117, Elmore process, ½ col.
- p. 1151, 'Drying Oil Concentrates,' R. Stören, ½ col.
- p. 1208, Delprat and Elmore processes, ½ col.
- p. 1257, 'The Elmore Vacuum Oil Process,' H. H. Claudet and others, 16 lines.

ENGINEERING AND MINING JOURNAL, Vol. LXXXVI., 1908.

- p. 23, 'The Improved Macquisten Tube,' W. R. Ingalls, 10 lines, illustrated.
- p. 99, C. V. Potter, 8 lines.
- pp. 143, 144, 'Mining in Australia,' F. S. Mance, 2 pages.
- p. 175, 'The Development of the Delprat and Potter Flotation Processes,' W. R. Ingalls, 2 col.
- p. 321, Decision in Elmore *v.* Minerals Separation, Ltd., ¾ col.
- p. 636, Minerals Separation Ltd., report, ¾ col.
- p. 707, 'Slime Deposition and Agglomeration,' H. L. Sulman, ¾ col.
- p. 778, The Flotation Process Litigation, 2 col.
- p. 808, The Dolcoath Tin Mine, ¾ col.
- p. 828, Cobar Gold Mines report, ½ col.
- p. 839-841, 'Ore Dressing by Adhesion of Liquid Films,' R. Stören, 3 pages.

ENGINEERING AND MINING JOURNAL, Vol. LXXXVII., 1909.

- p. 38, Minerals Separation *v.* Elmore, ¾ col.
- p. 68, Broken Hill zinc problem, ¼ col.
- p. 110, Sanders process, 17 lines.
- p. 124, Potter, Delprat, Elmore, and De Bavay processes, 1½ col.
- p. 146, Bibliography, Elmore process, 8 lines.
- p. 177, 'Elmore Process at Cobar,' J. Stocker, 1 col.
- p. 213, De Bavay process, 5 lines.
- p. 216, Flotation Process Litigation, 16 lines.
- p. 219, The Zinc Corporation, Ltd., 2½ col.
- p. 250, Experiments with Elmore in British Columbia, 17 lines.
- p. 342, Bibliography, Zinc Corporation, 6 lines.
- p. 471, Patents, Sanders, De Bavay, Elmore.
- p. 724, Potter process, 7 lines.
- p. 735, Bibliography, Elmore, 6 lines.
- p. 737, Bibliography, Flotation process, 6 lines.
- p. 772, Potter and Delprat processes, 9 lines.
- p. 821, Elmore process, 17 lines.
- p. 844, The Sanders Flotation Process, ½ col., illustrated.
- p. 954, De Bavay process, 8 lines.
- p. 1061, Elmore and Murex processes, ¾ col.
- p. 1205, The Zinc Corporation, process, 1 col.
- p. 1275, 'Notes on the Elmore Vacuum Process,' A. Stanley Elmore, 1 col.
- p. 1289, Namaqua Copper Co., Elmore process, 10 lines.

ENGINEERING AND MINING JOURNAL, Vol. LXXXVIII., 1909.

- p. 118, Minerals Separation, at Broken Hill, 13 lines.

ENGINEERING AND MINING JOURNAL, Vol. LXXXVIII., 1909.

- p. 130, The Ore Concentration Company (1905), legal decision, $\frac{3}{4}$ col.
- pp. 205-207, 'Elmore Process as Applied by the Zinc Corporation,' H. C. Hoover, $2\frac{1}{2}$ pages, illustrated.
- p. 231, Elmore process, 12 lines.
- p. 297, Bibliography, Elmore, 5 lines.
- p. 371, Murex Magnetic concentration process, $1\frac{1}{4}$ col.
- p. 493, Bibliography, Elmore, 10 lines.
- p. 505, Cohesion and Surface Films, 10 lines.
- p. 525, Sulphide Corporation, Minerals Separation plant, $\frac{1}{4}$ col.
- p. 619, Patent, Lockwood.
- p. 920, De Bavay process, $\frac{1}{2}$ col.
- p. 972, Miscellaneous Processes (flotation), $\frac{3}{4}$ col.
- p. 1042, Amalgamated Zinc (De Bavay's), $\frac{1}{2}$ col.
- p. 1100, Patent, Lockwood.
- p. 1118, Decision in Elmore Flotation Patents, $\frac{3}{4}$ col.
- p. 1136, Elmore decision, $\frac{1}{2}$ col.
- p. 1152, Bibliography, Murex process, 3 lines.
- p. 1278, Minerals Separation, Ltd., $\frac{3}{4}$ col.

ENGINEERING AND MINING JOURNAL, Vol. LXXXIX., 1910.

- p. 109, Elmore, Potter, and De Bavay processes, 1 col.
- p. 152, Bibliography, 'Treatment of Complex Sulphides,' Ristedt and Griffiths, 8 lines.
- p. 157, Murex process, 1 col.
- p. 283, Patent, Lockwood and Samuel.
- p. 372, The Sulphide Corporation, 1 col.
- p. 460, 'Horwood Process for Separating Zinc Sulphides,' Donald Clark, 2 pages, illustrated.
- p. 575, Elmore process, 10 lines.
- p. 659, Macquisten Concentrating Process, 1 col., illustrated.
- p. 675, Patent, Horwood.
- p. 696, Elmore process, 4 lines.
- p. 756, Bibliography, Horwood process.
- p. 913, 'Oil Flotation at Broken Hill,' Theodore J. Hoover, 5 pages, illustrated.
- p. 979, Patent, Hoover.
- p. 997, Bibliography, Horwood process.
- p. 1109, Zinc Corporation, $\frac{1}{2}$ col.
- p. 1126, Patents, Higgins, Lockwood, Samuels.
- p. 1207, Bibliography, Oil Flotation Process at Broken Hill.
- p. 1336, Patents, Sulman and Picard; Wentworth.

ENGINEERING AND MINING JOURNAL, Vol. XC., 1910.

- p. 123, Hoover Flotation Apparatus, 1 col., illustrated.
- p. 228, Patent, Sulman.
- p. 323, 'Smelting Briquetted Zinc Ore,' Theodore J. Hoover, 2 pages.
- p. 590, Ore Concentration Co., $\frac{1}{2}$ col.
- p. 751, 'Smelting Briquetted Zinc Ore,' Theodore J. Hoover, 12 lines.
- p. 1261, Zinc flotation, 4 lines.

ENGINEERING AND MINING JOURNAL, Vol. XCI., 1911.

- p. 233, Patent, Sulman and Picard.
- p. 302, 'Zinc Production in Australia,' Edward Walker, bibliography.
- p. 432, Patent, Sulman, Higgins, and Ballot; patent Wentworth.
- p. 560, Macquisten Tubes, 12 lines.
- p. 628, Patent, Hoover.
- p. 696, Bibliography, flotation patents.
- p. 745, Editorial, The Flotation Processes, $3\frac{1}{2}$ col.
- p. 759, The Orijarvi Mine, Finland, 2 pages, illustrated.

ENGINEERING AND MINING JOURNAL, XCI., 1911.

- p. 861, Broken Hill Proprietary, 1 col.
- p. 873, Patent, Hoover; patent, Sanders; patent, Lockwood; patent, Sulman and Picard.
- p. 941, Bibliography, flotation patents.
- p. 946, 'The Flotation Process,' Edward H. Nutter, 1 col.
- p. 1072, Patent, Hoover.
- p. 1121, Zinc Corporation, $\frac{1}{2}$ col.
- p. 1140, Bibliography, flotation of minerals.
- p. 1198, The Zinc Corporation and the Flotation Processes, $1\frac{1}{2}$ col.

ENGINEERING AND MINING JOURNAL (THE), Vol. XCII., 1911.

- p. 196, Litigation, 10 lines.
- p. 212, Flotation processes, $\frac{1}{2}$ col.
- p. 240, patent, Lockwood.
- p. 272, Bibliography, 4 lines.
- p. 278, Butte and Superior, 10 lines.
- p. 307, 'Experiments on Mineral Flotation,' Kenneth A. Mickle, 4 pp.
- p. 529, Eucalyptus oil in Australia, 12 lines.
- p. 716, Bibliography, 5 lines.
- p. 722, Butte and Superior, $\frac{1}{4}$ col.
- p. 731, patent, Dick.
- p. 771, Butte and Superior, $\frac{1}{4}$ col.
- p. 859, patent, Greenway.
- p. 866, Comet mine, $\frac{1}{4}$ col.
- p. 994, 'Flotation at Zinc Corporation,' D. P. Mitchell, 4 pp., illustrated.
- p. 1005, Butte and Superior, $\frac{1}{4}$ col.
- p. 1010, Butte and Superior, $\frac{1}{4}$ col.
- p. 1051, patent, Greenway.
- p. 1098, Bibliography, 3 lines.
- p. 1146, Elmore, 10 lines.
- p. 1148, Butte and Superior, $\frac{1}{4}$ col.
- p. 1168, Non-acid flotation process, $\frac{1}{4}$ col.
- p. 1172, Litigation, Minerals Separation, Ltd., sues James M. Hyde, $\frac{1}{2}$ col.
- p. 1259, Flotation at Zinc Corporation, 1 col.
- p. 1289, patents, Lavers and Nutter, Lavers and Greenway.

ENGINEERING AND MINING REVIEW, August, 1911.

- p. 435, Litigation, 3000 words.

ENGINEER (THE), Vol. XCV., 1902.

- p. 216, Elmore process.

ENGINEERING MAGAZINE, September, 1908.

- 'Macquisten Flotation Process,' A. Selwyn Brown.

FINANCIAL TIMES (THE), Mar. 3, 1902, account of Everson process.

- Extract from the *Rossland Miner*, $\frac{1}{2}$ col.

GENIE CIVIL, Vol. LI., 1907.

- p. 144, 'The Elmore Process,' Alexander Stanley Elmore.

GLUCKAUF, Vol. 45.

- p. 846, 'Elmore Vacuum Oil Process at Broken Hill,' A. Stanley Elmore.

GRAPHICAL METHODS IN THE THERMODYNAMICS OF FLUIDS.

- Josiah Willard Gibbs.

INSTABILITY OF JETS, Math. Soc. Proc., Nov., 1878.

- Lord Rayleigh.

JOURNAL DE L'INSTITUT, No. 1260.

- V. M. A. Mannheim.

- JOURNAL OF PHYSIOLOGY, Vol. XXVII., 1901-2.
p. 26, 'On the Film or Skin of Warmed Milk and other Proteid Solutions,' R. Jamison.
- JOURNAL OF THE BRITISH FEDERATED SOCIETY OF MINING STUDENTS, Vol. II., June, 1909.
p. 153, 'Elmore Process,' A. Barclay, 8½ pages, illustrated.
- JOURNAL OF THE CANADIAN MINING INSTITUTE, Vol. II., 1908.
p. 460, 'Elmore Vacuum Oil Process in British Columbia,' H. H. Claudet.
- JOURNAL OF THE CHEMICAL, METALLURGICAL AND MINING SOCIETY OF SOUTH AFRICA, Vol. VII., 1907.
p. 421, 'The Elmore Process,' Alexander Stanley Elmore.
- JOURNAL OF THE CHEMICAL, METALLURGICAL AND MINING SOCIETY OF SOUTH AFRICA, Vol. X.
p. 28, Murex process.
- JOURNAL OF THE CHEMICAL, METALLURGICAL AND MINING SOCIETY OF SOUTH AFRICA, Vol. XI.
p. 411, 'Macquisten Flotation Process,' A. Selwyn Brown.
- JOURNAL OF THE SOCIETY OF CHEMICAL INDUSTRY, 1905.
p. 310, Patent, Sanders.
- LECONS DE CALCUL DES VARIATIONS, Paris, 1861.
L. L. Lindelöf and F. M. N. Moigno.
- MECANIQUE CELESTE, Supplement to the tenth book published in 1806.
Pierre Simon Laplace. Results identical with those of Young.
- MEMOIRES DE L'ACADEMIE DES SCIENCES, 1787.
p. 506, Principle of surface tension applied to explanation of attractions and repulsions between bodies floating on a liquid.
- MEMOIRE SUR LA CONSTITUTION DES VEINES LIQUIDES LANCEES PAR DES ORIFICES CIRCULAIRES EN MINCES JARVIS. Ann. de Chim. T. LIII., 1833.
F. Savart.
- MEMOIRES DE L'ACADEMIE ROYALE DE BELGIQUE, XXXVII., 1873.
G. L. van de Mensbrughe, Phenomena of surface tension.
- METALLURGICAL AND CHEMICAL ENGINEERING, Vol. IX., 1911.
p. 426, Abstract 'Flotation of Minerals,' by Kenneth A. Mickle, 2 col.
p. 433, Flotation, 3 lines.
p. 567, Flotation process in Idaho, ¼ col.
- METALLURGIE, Vol. IV., 1907.
pp. 522-530, 'Flotation Processes,' C. Göpner, 9 pages, illustrated.
- METALLURGIE, Vol. V., 1908.
pp. 1, 45, 87, 128, 288, and 609, 'Elmore Process;' 'Potter-Delprat Process,' C. Göpner.
p. 297, Minerals Separation process.
- METALLURGIE, Vol. VI.
p. 486, 'Elmore Vacuum Oil Process at Broken Hill,' R. Zinde.
- METHOD OF GEOMETRICAL REPRESENTATION of the thermodynamic properties of substances by means of surfaces.
Josiah Willard Gibbs.
- MEXICAN MINING JOURNAL, March 6, 1909.
'Concentration of Ores by Flotation Processes,' Francis W. Sewell.
- MINERAL RESOURCES OF THE UNITED STATES, Part I., 1908.
pp. 251-256, Flotation Methods, 5 pages.
p. 746, Molybdenum Ores, 3 lines.

- MINERAL RESOURCES OF THE UNITED STATES, Part I., 1910.
 p. 274, Macquisten, 2 lines.
 p. 278, Summary of flotation processes, 2 pp.
- MINERAL INDUSTRY (THE), for 1900, Vol. IX., New York, Scientific Publishing Co., 1901.
 p. 743, Oil Concentration, $\frac{1}{2}$ page.
 pp. 777, 778, Concentration by Oil, $1\frac{1}{4}$ pages.
- MINERAL INDUSTRY (THE) for 1901, Vol. X., New York, Engineering and Mining Journal, 1902.
 p. 759, Oil Concentration and Elmore process, $\frac{1}{4}$ page.
- MINERAL INDUSTRY (THE), for 1902, Vol. XI., New York, Engineering and Mining Journal, 1903.
 pp. 656, 657, Oil concentration, 1 page.
 pp. 697-707, 'The Concentration of Ores by Oil,' W. McDermott, $10\frac{1}{2}$ pages, illustrated.
- MINERAL INDUSTRY (THE), for 1903, Vol. XII., New York, Engineering and Mining Journal, 1904.
 p. 358, Flotation processes, $1\frac{1}{4}$ pages.
 p. 410, Separation of zinc-blende, 7 lines.
 p. 412, The Elmore process, $1\frac{1}{2}$ pages.
- MINERAL INDUSTRY (THE), for 1904, Vol. XIII., New York, Engineering and Mining Journal, 1905.
 p. 423, The Potter Flotation process, $\frac{1}{2}$ page.
 p. 453, Potter process for treating zinc tailing, $\frac{1}{4}$ page.
 p. 468, Bibliography, Delprat and Potter processes, 7 lines.
- MINERAL INDUSTRY (THE), for 1905, Vol. XIV., New York, Engineering and Mining Journal, 1906.
 p. 592, Flotation processes, 1 page.
 p. 635, Elmore process of diamond recovery ; Oil concentration process in British Columbia ; Elmore process in Rossland, $\frac{1}{2}$ page.
- MINERAL INDUSTRY (THE), for 1906, Vol. XV., New York, Engineering and Mining Journal, 1907.
 pp. 769-770, Sulphide Corporation, Delprat process, flotation processes, 1 page.
 pp. 777-778, Delprat process, flotation processes, Sanders process, Stallman-Germer process, Cattermole process, $1\frac{1}{2}$ pages.
 p. 809, Elmore process, 1 line.
 p. 833, Attraction of Minerals for Oil, $\frac{1}{2}$ page.
- MINERAL INDUSTRY (THE), for 1907, Vol. XVI., New York, Engineering and Mining Journal, 1908.
 p. 960, Macquisten process and the new Elmore process, 3 lines.
 pp. 974-976, Elmore vacuum flotation process, 1 page, illustrated.
 p. 991, Delprat process, $\frac{1}{4}$ page.
 p. 992, Cost of the Minerals Separation process, $\frac{3}{4}$ page.
 p. 993, De Bavay process, 4 lines.
 pp. 997-999, Elmore vacuum process in Cornwall, $\frac{1}{2}$ page ; Macquisten flotation methods, $2\frac{1}{2}$ pages, illustrated.
 p. 1013, Bibliography, flotation processes, 6 lines.
- MINERAL INDUSTRY (THE), Vol. XVII., 1908.
 pp. 860-1, Minerals Separation, De Bavay, and Elmore processes, $1\frac{1}{2}$ pages.
 pp. 950-953, De Bavay. Potter, Delprat, Elmore, Minerals Separation, and Gillies processes, 3 pages.
 pp. 964-965, Bibliography, Elmore process, 4 lines.

- MINERAL INDUSTRY (THE), Vol. XVIII., 1909.
 p. 711, Floating blende, 5 lines.
 p. 713, Zinc mining in Australia, 2 pages.
 p. 721, Bibliography.
 p. 749, Murex and Elmore processes, 1 page.
 p. 775, Bibliography.
- MINERAL INDUSTRY (THE), Vol. XIX., 1910.
 p. 693, Horwood, 2 lines.
 p. 761, Murex, 7 lines.
 p. 762, Flotation processes, 2 pp.
 p. 785, Bibliography, $\frac{1}{2}$ page.
- MINES AND METHODS, Vol. II., 1911; p. 280, Butte and Superior, $\frac{1}{2}$ col.
- MINES AND MINERALS, Vol. XXVIII., 1907.
 p. 24, 'The Elmore Process,' Alexander Stanley Elmore.
- MINES AND MINERALS, Vol. XXXII., No. 2; p. 124, Elmore process, 1 page.
- MINING AND ENGINEERING REVIEW, Vol. I., 1909.
 p. 282, Flotation processes, $1\frac{1}{2}$ col.
- MINING AND ENGINEERING REVIEW, Vol. III., 1911.
 pp. 211 and 233, 'Flotation Processes and Patents,' P. M. Newton.
- MINING AND SCIENTIFIC PRESS, Vol. LIX., 1889.
 p. 448, Account of an oil-acid concentration process at Denver, $\frac{1}{2}$ col.
- MINING AND SCIENTIFIC PRESS, Vol. LXVII., 1893.
 p. 296, Oil on water, area of spreading, 15 lines.
- MINING AND SCIENTIFIC PRESS, Vol. LXX., 1895.
 p. 130, Sulman's reduction of surface tension, 10 lines.
- MINING AND SCIENTIFIC PRESS, Vol. LXXXI., 1900.
 p. 40, Elmore process, 2 cols.
 p. 67, Patent, Elmore.
 p. 278, Elmore process, $\frac{1}{2}$ col.
- MINING AND SCIENTIFIC PRESS, Vol. LXXXIII., 1901.
 p. 288, Patent, Elmore.
- MINING AND SCIENTIFIC PRESS, Vol. LXXXIV., 1902.
 p. 105, Patent, Elmore.
 p. 230, Elmore process, $\frac{3}{4}$ col.
- MINING AND SCIENTIFIC PRESS, Vol. LXXXV., 1902.
 p. 25, Patent Elmore.
 p. 44, Elmore process, $\frac{1}{2}$ col.
 p. 207, Elmore process, 1 col.
- MINING AND SCIENTIFIC PRESS, Vol. LXXXVI., 1903.
 p. 95, Elmore process, 23 lines.
 p. 118, Delprat process, $\frac{3}{4}$ col.
 p. 281, Elmore process, 1 page.
 p. 338, Elmore process, $\frac{3}{4}$ col.
 p. 364, Elmore process, 1 col.
- MINING AND SCIENTIFIC PRESS, Vol. LXXXVII., 1903.
 p. 9, Delprat process, $\frac{1}{2}$ col.
 p. 227, Elmore process, 2 lines.
 p. 304, Van Meter process, 1 page.
 p. 312, Elmore process, 1 line.
 p. 362, Elmore process, $\frac{1}{2}$ col.
 p. 392, Correction.
 p. 418, Delprat process, $\frac{1}{4}$ col.

- MINING AND SCIENTIFIC PRESS, Vol. LXXXIX., 1904.
 p. 244, Patent, Kendall.
 p. 428, Patent, Cattermole ; Cattermole, Sulman and Picard.
- MINING AND SCIENTIFIC PRESS, Vol. LXXXVIII., 1904.
 p. 115, Van Meter process.
 pp. 172, 204, 221, 236, 291, Elmore process.
 pp. 316, 328, 344, and 363, 'Concentration of Low Grade Copper Ores by the Elmore Process,' W. J. Adams, 4 pages.
 pp. 343, 361, Potter process.
 p. 432, Patent, Van Meter and Boss.
- MINING AND SCIENTIFIC PRESS, Vol. LXXXIX., 1904.
 p. 27, Patents, Goyder and Laughton ; Delprat.
 pp. 131, 184, 216, and 344, Elmore process.
 p. 163, Patent, Delprat.
 p. 203, Delprat process, 7 lines.
 p. 227, Patent, Scammell.
 p. 261, Patent, Schwarz.
 p. 363, Potter process.
 p. 378, Patent, Potter.
- MINING AND SCIENTIFIC PRESS, Vol. XC., 1905.
 p. 94, Elmore Process.
 pp. 180, 344, Delprat Process.
 p. 191, Patent, Goyder and Laughton.
 p. 269, Patent, Wolf.
- MINING AND SCIENTIFIC PRESS, Vol. XCI., 1905.
 p. 59, Patent, Sulman and Picard.
 pp. 184 and 216, Delprat process.
 p. 371, De Bavay process.
- MINING AND SCIENTIFIC PRESS, Vol. XCII., 1906.
 p. 75, Patent, Kirby.
 p. 177, Ore flotation.
 p. 126, 'The Physics of Ore Flotation,' J. Swinburne and C. Rudorf.
 p. 214, Potter, Delprat and Elmore processes.
 p. 385, Zinc Corporation.
 p. 412, De Bavay, Cattermole and Minerals Separation processes.
 p. 438, Patent, Finlay.
 p. 439, Zinc Corporation, Cattermole, and Elmore processes.
- MINING AND SCIENTIFIC PRESS, Vol. XCIII., 1906.
 p. 179, Patent, Schwarz, $\frac{3}{4}$ col., illustrated.
 p. 229, Soap method of flotation, $\frac{1}{4}$ col.
 p. 429, New processes at Broken Hill, $\frac{1}{2}$ col.
 p. 492, Zinc Corporation, Potter and Delprat processes, $\frac{3}{4}$ col.
 p. 522, Zinc Corporation, and Potter process, $\frac{1}{2}$ col.
 p. 583, Zinc Corporation, $\frac{1}{2}$ col.
 p. 697, Patent, Sulman, Picard, and Ballot.
 p. 727, Patent, Sulman, Picard, and Ballot.
- MINING AND SCIENTIFIC PRESS, Vol. XCIV., 1907.
 p. 202, Zinc Corporation and Potter process, $\frac{1}{2}$ col.
 p. 222, Patent, Schwarz.
 p. 391, Elmore process, 6 lines.
 p. 392, Zinc Corporation and Potter process, $\frac{1}{2}$ col.
 p. 486, New Rico Mill, 6 lines.
 p. 528, Zinc Corporation, Minerals Separation, Delprat, Potter, and De Bavay Process, $\frac{3}{4}$ col.
 p. 556, Minerals Separation process, $\frac{1}{4}$ col.
 pp. 651, 652, Minerals Separation, Zinc Corporation, and Elmore process, $1\frac{1}{2}$ cols.

MINING AND SCIENTIFIC PRESS, Vol. XCIV., 1907.

- pp. 728-730, 'Acid Flotation Processes at Broken Hill,' F. H. Jackson,
2½ pages and illustrations.
- p. 814, Elmore process, 15 lines.

MINING AND SCIENTIFIC PRESS, Vol. XCV., 1907.

- p. 104, Flotation processes, 1 col.
- p. 222, Zinc Corporation and Elmore process, ½ page.
- p. 251, Patent, Latimer.
- p. 265, Zinc Corporation, Minerals Separation, and Elmore processes, ¾ col.
- p. 269, Loss of Gold due to Oil Flotation, ½ col.
- p. 346, Patent, De Bavay.
- p. 377, Patent, Elmore.
- p. 393, Elmore process, 4 lines.
- p. 787, Patent, Schwarz.
- p. 802, Elmore process, 11 lines.

MINING AND SCIENTIFIC PRESS, Vol. XCVI., 1908.

- p. 42, Potter-Delprat litigation, ¼ col.
- p. 75, Patent, Norris.
- p. 87, Cattermole process, ½ page.
- p. 137, Patent, Gillies.
- p. 280, Zinc Corporation and Elmore process, ¾ col.
- p. 328, The De Bavay Process, 13 lines.
- p. 414, Macquisten process, ½ page.
- p. 476, Elmore process, ¼ col.
- p. 494, Flotation Processes at Broken Hill, 1 page, illustrated.
- pp. 575, 576, Editorial, ½ col.
- p. 773, Concentration by Flotation, ¼ col.

MINING AND SCIENTIFIC PRESS, Vol. XCVII., 1908.

- p. 76, Elmore process, 7 lines.
- p. 84, 'Flotation Processes at Broken Hill,' G. D. Delprat, ¼ col.
- p. 172, Zinc Corporation, ½ page.
- p. 232, Zinc Corporation, report, 1 page.
- p. 244, Minerals Separation and Elmore litigation, 1½ col.
- p. 315, Oil process at Dolcoath, ¼ col.
- p. 344, Flotation processes, ¾ col.
- p. 412, Flotation processes, 15 lines.
- p. 518, Elmore process, 2 lines.
- p. 645, Patent, Wolf.
- p. 660, Litigation, Elmore *v.* Ballot, ½ col.
- p. 711, Sulman and Sulman.

MINING AND SCIENTIFIC PRESS, Vol. XCVIII., 1909.

- p. 3, Editorial on litigation, 13 lines.
- p. 62, 'Flotation Process Litigation,' Edward Walker, ¾ page.
- p. 108, Production of zinc at Broken Hill, ½ col.
- p. 329, Patent, Sanders.
- p. 391, 'Elmore Vacuum Plant,' R. Linde, 1 page, illustrated.
- p. 406, Flotation in Mexico, ¼ col.
- p. 461, Patent, De Bavay.
- p. 565, Editorial on ore reserves at Broken Hill, ¼ col.
- p. 685, Surface Tension, 7 lines.
- p. 757, Murex Magnetic concentration process, ½ page.
- p. 775, Murex process, ½ col.
- p. 812, Zinc Corporation profits, ¾ col.
- p. 844, Zinc Corporation results, ¾ col.

MINING AND SCIENTIFIC PRESS, Vol. XCIX., 1909.

- p. 169, Minerals Separation, 3 lines.

MINING AND SCIENTIFIC PRESS, Vol. XCIX., 1909.

- p. 380, Elmore plant, 5 lines.
- p. 551, De Bavay Treatment Co., 17 lines.
- p. 725, De Bavay Flotation Process, $\frac{3}{4}$ col.
- p. 766, Litigation, Minerals Separation v. Elmore, $\frac{1}{2}$ col.
- p. 777, Murex Magnetic process, $\frac{1}{2}$ col.

MINING AND SCIENTIFIC PRESS, Vol. C., 1910.

- p. 54, 'Progress and Problems in Ore Dressing,' Courtenay De Kalb, 1 col.
- p. 232, Sulphide Corporation, $\frac{1}{2}$ col.
- p. 366, Broken Hill processes, 20 lines.
- p. 533, Elmore process, 12 lines.
- p. 563, San Francisco del Oro, 1 col.
- p. 699, Broken Hill Proprietary, $\frac{1}{2}$ col.
- p. 806, Flotation processes, 1 col.

MINING AND SCIENTIFIC PRESS, Vol. CI., 1910.

- p. 123, Broken Hill Proprietary, 20 lines.
- p. 185, Great Fitzroy, $\frac{1}{2}$ col.
- p. 280, Broken Hill, $\frac{1}{2}$ col.
- p. 527, Editorial, flotation processes, 5 lines.
- p. 547, Broken Hill processes, $\frac{1}{2}$ col.
- p. 583, Flotation process at Broken Hill, 1 col.
- p. 646, Murex process, $\frac{1}{2}$ col.

MINING AND SCIENTIFIC PRESS, Vol. CII., 1911.

- p. 13, Flotation results, 20 lines.
- p. 15, 'Zinc Production in Australia,' Edward Walker, 3 pp., illustrated.
- p. 190, Elmore process, 15 lines.
- p. 240, Litigation against Theodore Hoover by Minerals Separation, 7 lines. Notes on application of flotation processes, $1\frac{1}{2}$ col.
- p. 304, Elmore process, $\frac{1}{2}$ col.
- p. 325, Flotation processes, 1 col.
- p. 439, Litigation against Theodore Hoover by Minerals Separation, Ltd., 1 col. Zinc Corporation litigation, $\frac{1}{2}$ col.
- p. 518, 'Modern Zinc Problems,' H. L. Sulman, 3 pages.
- p. 572, Broken Hill notes, 1 col.
- p. 583, 'Modern Zinc Problems,' H. L. Sulman, 5 pages.
- p. 693, Macquisten tubes in Idaho, 1 col.
- p. 703, Flotation patents, $\frac{1}{2}$ col.
- p. 797, Elmore process, $\frac{1}{2}$ col.

MINING AND SCIENTIFIC PRESS, Vol. CIII., 1911.

- p. 45, Murex process, $\frac{1}{4}$ col.
- p. 125, New South Wales decision, $\frac{1}{4}$ col.
- p. 177, Murex, $\frac{1}{2}$ col.
- p. 181, Butte and Superior, 4 lines.
- p. 208, New flotation process at Butte, $\frac{1}{4}$ col.
- p. 304, Macquisten, $\frac{1}{4}$ col.
- p. 393, Butte and Superior, 20 lines.
- p. 556, Eucalyptus oil for flotation, 1 col.
- p. 586, Purifying water by coagulation, 1 col.
- p. 725, Butte and Superior, 10 lines.
- p. 782, Caucasus Copper Co., $\frac{1}{2}$ col.
- p. 809, 'Tube Concentrator,' W. A. Scott, $\frac{1}{2}$ col.
- p. 846, Butte and Superior, $\frac{1}{2}$ col.

MINING INVESTOR (THE), Vol. V., Nov., 1911.

- p. 56, Minerals Separation, Ltd., 10 lines.

- MINING JOURNAL (THE), Vol. XLI., 1871.
p. 761, Patent, H. Bradford.
- MINING JOURNAL (THE), Vol. LVI., 1893.
p. 323, Patents, H. Bradford.
- MINING JOURNAL (THE), Vol. LXX., 1900.
p. 902, Elmore process, extract from paper by C. M. Rolker.
p. 1178, Elmore process, 14 lines.
- MINING JOURNAL (THE), Vol. LXXI., 1901.
p. 272, Elmore process, $\frac{1}{2}$ col.
- MINING JOURNAL (THE), Vol. LXXV., 1904.
p. 614, Elmore process, $\frac{1}{4}$ col.
- MINING JOURNAL (THE), Vol. LXXXI., 1907.
p. 623, 'The Vacuum Process for Concentration of Ores,' Alexander Stanley Elmore, 1 page, illustrated.
- MINING JOURNAL (THE), Vol. LXXXIV., 1908.
p. 220, 'The British Ore Concentration Syndicate v. Minerals Separation, Ltd. ;' Justice Neville's decision, 2 col.
- MINING JOURNAL (THE), Vol. LXXXV., 1909.
p. 71, De Bavay 8 lines.
p. 98, Patents, Sulman, Picard, and Ballot.
p. 162, Patents, Hoover and Sulman, $\frac{1}{4}$ col., illustrated.
p. 199, Broken Hill Proprietary, 15 lines.
p. 225, Patent, Norris, 20 lines, illustrated ; patent, Horwood ; patent, Greenway, Sulman, and Higgins.
p. 231, Zinc Corporation, 10 lines.
p. 232, Elmore at Cobar, 5 lines.
p. 234, 'Elmore Vacuum Process at Broken Hill,' A. Stanley Elmore, 3 pages, illustrated.
p. 273, Sulphide Corporation, 10 lines.
p. 281, 'Vacuum Oil Process in the Cobar Gold Mine,' J. Stocker, $\frac{2}{3}$ col.
p. 317, Broken Hill Proprietary, 1 col.
p. 335, 'Ore Reduction at the Telemarken Copper Mine, Norway,' W. E. Bennett, 2 pages, illustrated.
p. 356, Patent, Hoover.
p. 385, Patent, De Bavay.
p. 395, Zinc Corporation, De Bavay, 20 lines.
p. 544, Zinc concentrate, 15 lines.
p. 565, Murex Magnetic Process, 1 page, illustrated.
p. 575, Zinc Corporation, 8 lines.
p. 591, Murex process, $\frac{2}{3}$ col.
p. 632, Murex process, 8 lines.
p. 639, Zinc Corporation, $\frac{1}{2}$ col.
p. 649, Minerals Separation v. Ore Concentration Co., $\frac{2}{3}$ col.
p. 688, Zinc Corporation, 4 col.
- MINING JOURNAL (THE), Vol. LXXXVI., 1909.
p. 25, Broken Hill shares, 7 lines.
p. 41, Broken Hill processes, 1 page.
p. 100, Patent, Namaqua Copper Co. and James.
p. 100, J. D. Wolf, Patent.
p. 128, Murex Magnetic, 3 pages.
p. 163, Patent, Lockwood.
p. 165, Spelter convention, 1 page.
p. 185, Zinc Corporation, 15 lines.
p. 230, Broken Hill, 10 lines.
p. 267, Elmore vacuum process, 1 col.

MINING JOURNAL (THE), Vol. LXXXVI., 1909.

- p. 307, Sulphide Corporation, 15 lines.
- p. 307, Sulphide Corporation, 18 lines.
- p. 323, Broken Hill Proprietary, $\frac{2}{3}$ col.
- p. 363, Elmore vacuum, 10 lines.
- p. 365, Broken Hill, $\frac{1}{4}$ col.
- p. 380, Broken Hill Proprietary, 4 lines.

MINING JOURNAL (THE), Vol. LXXXVII., 1909.

- p. 3, Broken Hill, one-fifth col.
- p. 3, Junction, one-fifth col.
- p. 44, Patent, Lockwood and Samuel, one-fifth col.
- p. 47, Zinc Corporation, 4 lines.
- p. 61, Broken Hill, 7 lines.
- p. 111, Caucasus Copper Co., 3 col.
- p. 182, Amalgamated Zinc (De Bavay's), 1 col.
- p. 274, Patents, Lockwood.
- p. 314, Patent rights in oil separation processes, 3 pages.
- p. 317, Minerals Separation, Ltd., 3 pages.
- p. 362, Patent, Minerals Separation, Ltd.
- p. 368, De Bavay.
- p. 410, Horwood Process, $\frac{1}{2}$ col.
- p. 424, Murex Magnetic, $\frac{2}{3}$ col.
- p. 443, Zinc Corporation, 15 lines.
- p. 477, Broken Hill, $\frac{1}{4}$ col.
- p. 492, Sulphide Corporation, $1\frac{1}{4}$ col.
- p. 496, Patent, Sulman.
- p. 506, Patents, Sulman and Picard.
- p. 521, Lorenzo Lode, $\frac{1}{3}$ col.
- p. 528, Broken Hill, 10 lines.
- p. 529, Many patented processes, $\frac{2}{3}$ col.

MINING JOURNAL (THE), Vol. LXXXVIII., 1909.

- p. 202, Patents, Dick.
- p. 205, Coal Strike, $\frac{1}{3}$ col.
- p. 216, Zinc Corporation, 16 lines.
- p. 216, Amalgamated Zinc, 16 lines.
- p. 229, Patent, Treating Ores, Dick.
- p. 342, Horwood's process, $\frac{1}{3}$ page.
- p. 371, San Francisco Del Oro Mining Co.
- p. 378, Patents, Murex Magnetic Co. and Lockwood; Sulman and Picard.

MINING JOURNAL (THE), Vol. LXXXIX, 1909.

- p. 430, Patents, Theodore J. Hoover.
- p. 438, Broken Hill prospects, 20 lines.
- p. 551, De Bavay Mills, $\frac{1}{3}$ col.
- p. 566 (Supplement III.) Minerals Separation, $\frac{1}{4}$ col.
- p. 578, Patents, Murex Magnetic and Lockwood; Sulman and Picard; Minerals Separation.
- p. 634, Elmore, $\frac{1}{2}$ col.
- p. 635, Zinc Corporation, 2 pages.
- p. 642, Patents, Murex and Lockwood; Murex and Anthony; Oldham; Sulman and Picard.
- p. 693, Murex Magnetic, 15 lines.
- p. 706, Patents, Hoover and Minerals Separation; Ore Concentration Co.
- p. 770, Patents, Murex Magnetic and Lockwood.
- p. 771, New South Wales, $2\frac{1}{4}$ pages.
- p. 775, Zinc Extraction.
- p. 800, Patents, Horwood; Greenway.

MINING JOURNAL (THE), Vol. XC., 1909.

- p. 887, Amalgamated Zinc, 16 lines.
- p. 887, Zinc Corporation, 20 lines.
- p. 954, Patent, Hoover, illustrated.
- p. 1048, Patent, Clador Syndicate and Lockwood.
- p. 1100, Zinc Corporation, 20 lines.

MINING JOURNAL (THE), Vol. XCI., 1910.

- p. 1184, Sulphide Corporation, 10 lines.
- p. 1220, Patent, Greenway and Lavers ; Dick.
- p. 1237, Murex process, 20 lines.
- p. 1241, Murex Magnetic Co., 6 col.
- p. 1248, Patent, Nutter.
- p. 1250, Potter process, 10 lines ; Fitzroy, 15 lines.
- p. 1279, Slime treatment at Broken Hill, 1 col.
- p. 1295, Zinc Corporation, 15 lines.
- p. 1314, Patent, Lockwood.
- p. 1376, Patent, Murex Co. and K. A. F. Roberts.
- p. 1418, Potter process, 5 lines.
- p. 1424, Zinc Corporation, 15 lines.
- p. 1430, Sulphide Corporation, 1 col.
- p. 1493, Sulphide Corporation, 1 col.
- p. 1495, San Francisco del Oro, 1 col.
- p. 1501, Murex process, 10 lines.
- p. 1514, Murex process, 10 lines.
- p. 1535, Minerals Separation, Ltd., 4 pages.

MINING JOURNAL (THE), Vol. XCII., 1911.

- p. 6, Zinc concentrate, 1½ col.
- p. 61, Amalgamated Zinc, 4 lines.
- p. 156, Patent, Nutter.
- p. 188, Amalgamated Zinc, 4 lines.
- p. 211, Broken Hill Zinc, ½ col.
- p. 258, Patent, Lockwood.

MINING JOURNAL (THE), Vol. XCIII., 1911.

- p. 326, Zinc Corporation and change of process, 25 lines.
- p. 336, Murex, ½ col.
- p. 343, Elmore, 3 lines.
- p. 352, Horwood, 10 lines.
- p. 339, Potter, 10 lines.
- p. 488, British Broken Hill Prop. Co., 1½ col.
- p. 509, Zinc Corporation, 20 lines.
- p. 524, Fitzroy, 15 lines.
- p. 567, Fitzroy, ½ col.
- p. 568, Zinc Corporation, 3 pp.
- p. 657, Fitzroy and Minerals Separation process, ½ col.

MINING JOURNAL (THE), Vol. XCIV., 1911.

- p. 714, Flotation processes, ¼ col.
- p. 748, Flotation processes, ¼ col.
- p. 750, Broken Hill Proprietary, 5 lines.
- p. 758, Sulphide Corporation, 10 lines.
- p. 768, Litigation, 7 lines.
- p. 769, Murex, 6 lines.
- p. 789, Ballot, 7 lines.
- p. 816, New flotation process at Butte, ½ col.
- p. 826, Amalgamated Zinc, 10 lines.
- p. 839, Proprietary, ¼ col.
- p. 865, Abstract 'Economic Importance of Lead-Zinc Deposits,' 3¼ col.
- p. 880, Murex, 1 col.

MINING JOURNAL (THE), Vol. XCIV., 1911.

- p. 882, Proprietary, 10 lines.
- p. 889, New flotation process on the Proprietary mine, $\frac{1}{4}$ col.
- p. 899, Amalgamated Zinc, $\frac{1}{4}$ col.
- p. 910, Amalgamated Zinc, 7 lines.
- p. 919, Fitzroy, 10 lines.
- p. 931, Use of eucalyptus oil, $\frac{1}{4}$ col.
- p. 969, Potter process, 15 lines.
- p. 1039, Broken Hill production, $\frac{1}{4}$ col.
- p. 1062, Patent, Lockwood.
- p. 1072, Murex, $\frac{1}{4}$ col.
- p. 1093, Pinnacles mine, 5 lines.
- p. 1094, Butte and Superior, $\frac{1}{4}$ col.
- p. 1158, Patent, Minerals Separation, Ltd.
- p. 1212, Patent, Lockwood.
- p. 1253, Broken Hill notes, $\frac{1}{4}$ col.
- p. 1256, Litigation, Minerals Separation v. James M. Hyde, $\frac{1}{4}$ col.
- p. 1299, Report of Minerals Separation, 5 pages.

MINING MAGAZINE, New York, Vol. X., 1904.

- p. 45, 'Oil Concentration,' W. J. Adams, 2 col.
- p. 82, Potter process.
- p. 232, Potter process.
- p. 337, Elmore process.
- p. 439, Flotation process at Broken Hill.

MINING MAGAZINE, New York, Vol. XI., 1905.

- p. 291, Elmore process.
- p. 487, Elmore process.

MINING MAGAZINE, New York, Vol. XII., 1905.
Colloids.

- p. 441, Elmore process.

MINING MAGAZINE (THE), London, Vol. I., 1909.

- p. 61, 'History of Flotation Processes,' Edward Walker, 4 pages, illustrated.
- p. 142, Murex process, 2 pages.
- p. 220, Murex process, 17 lines.
- p. 239, Amalgamated Zinc, $1\frac{1}{2}$ col.
- p. 261, Flotation patents, $1\frac{1}{2}$ pages.
- p. 279, Minerals Separation, Ltd., $1\frac{1}{2}$ col., illustrated.
- p. 289, Flotation Patents litigation, $1\frac{1}{2}$ pages.
- p. 310, Murex process, $\frac{1}{2}$ col.

MINING MAGAZINE (THE), London, Vol. II., 1910.

- p. 8, Zinc Metallurgy, 2 col.
- p. 56, 'Treatment of Complex Sulphides,' Donald Clark, 3 pages, illustrated.
- p. 72, Sulphide Corporation, 1 col.
- p. 153, Murex and Elmore process, 10 lines.
- p. 164, Amalgamated Zinc, $\frac{1}{2}$ col.
- p. 205, The New Potter Process, $1\frac{1}{2}$ col.
- p. 301, Flotation Patents, 1 col.
- p. 303, San Francisco del Oro, 1 col.
- p. 307, Broken Hill South Silver, 1 col.
- p. 319, Broken Hill Mines Reviewed, 20 lines.
- p. 337, Oil Processes, $1\frac{1}{2}$ col.
- p. 348, Flotation litigation, 1 col.
- p. 377, 'Vacuum Concentration at Sulitelma,' Holmsen and Rees, 4 pages, illustrated.
- p. 401, Great Fitzroy and Amalgamated Zinc, 12 lines.

MINING MAGAZINE (THE), London, Vol. II., 1910.

- p. 465, Editorial, 'Flotation,' 1 col.
- p. 434, 'Oil in the Potter Process,' W. E. Simpson, 2 pages.
- p. 463, 'Minerals Separation Process,' Theodore J. Hoover, 1 page, illustrated.
- p. 467, Zinc Corporation, 1 page, illustrated.
- p. 469, Elmore process, 8 lines.

MINING MAGAZINE (THE), London, Vol. III., 1910.

- p. 138, Amalgamated Zinc, 1 col., illustrated.
- p. 216, Broken Hill mines, 2 col.
- p. 234, Broken Hill processes, 20 lines.
- p. 253, Flotation processes, $\frac{1}{2}$ col.
- p. 294, Broken Hill mines, 1 col.
- p. 330, Editorial, 'Zinc at Broken Hill,' 3 pages.
- p. 372, Murex process, 1 col.
- p. 422, Great Fitzroy, 1 col.
- p. 423, Minerals Separation, 5 lines.
- p. 451, Flotation, 15 lines.

MINING MAGAZINE (THE), London, Vol. IV., 1911.

- p. 37, Zinc production, 15 lines.
- p. 72, Murex process, 4 lines.
- p. 76, Sulphide Corporation, $\frac{1}{2}$ col.
- p. 103, Broken Hill processes, 2 col.
- p. 152, Minerals Separation, Ltd., $\frac{3}{4}$ col.; Amalgamated Zinc, Ltd., $\frac{1}{4}$ col.
- p. 153, Broken Hill processes, 1 col.
- p. 162, Great Fitzroy, Zinc Corporation, Minerals Separation, Sulphide Corporation, Elmore, $1\frac{1}{2}$ col.
- p. 200, Zinc, 1 col.
- p. 201, Broken Hill production, $\frac{1}{2}$ col.
- p. 202, Sulphide Corporation and Minerals Separation, Ltd., $\frac{1}{2}$ col.
- p. 243, Murex process, 6 lines.
- p. 259, The Zinc Problem, $4\frac{1}{2}$ col.
- p. 280, Flotation processes, 5 lines.
- p. 323, Zinc Corporation, $\frac{1}{2}$ col.
- p. 332, Flotation Processes, 3 col.
- p. 400, Great Fitzroy, 3 lines.
- p. 468, Elmore process at British Broken Hill, and Minerals Separation process at Zinc Corporation, 1 col.

MINING MAGAZINE (THE), London, Vol. V., 1911.

- p. 32, Zinc Corporation, 1 col.
- p. 33, Fitzroy, $\frac{2}{3}$ col.
- p. 87, Elmore v. Minerals Separation, Ltd.
- p. 156, Murex, 12 lines.
- p. 157, Elmore, 10 lines.
- p. 165, Potter, 5 lines.
- p. 200, Ballot, 5 lines.
- p. 275, Broken Hill flotation processes, 3 col., illustrated.
- p. 320, Zinc Corporation, 10 lines.
- p. 353, Great Fitzroy, $\frac{1}{2}$ col.
- p. 354, Broken Hill news, 1 col.
- p. 395, Amalgamated Zinc, $\frac{1}{2}$ col.
- p. 396, Caucasus Copper Co., $\frac{1}{2}$ col.
- p. 467, Bibliography, 4 lines.
- p. 469, British Broken Hill and Great Fitzroy, $1\frac{1}{2}$ col.

MINING REPORTER (THE), Vol. XLIX, 1904.

- p. 349, 'Concentration at Broken Hill,' Donald Clark.

BIBLIOGRAPHY.

- MINING REPORTER (THE), Vol. L., 1904.
p. 349, 'Concentration at Broken Hill,' Donald Clark.
- MINING REPORTER (THE), Vol. LI., 1905.
p. 144, Elmore process.
- MINING REPORTER (THE), Vol. LV., 1907.
p. 537, 'The Elmore Process,' Alexander Stanley Elmore.
- MINING SCIENCE, December 7, 1912.
p. 518, Flotation processes, 1 col.
p. 531, Butte and Superior, $\frac{1}{2}$ col.
- MINING WORLD (THE) Chicago, Vol. XXVIII., 1908.
p. 18, 'A Novel Graphite Plant,' by Francis C. Nicholas.
p. 110, Patent, Gillies.
p. 493, Patent, Sulman, Picard, and Ballot.
p. 607, Elmore process, $\frac{1}{2}$ col.
p. 1041, Elmore process, 6 lines.
- MINING WORLD (THE), Vol. XXIX., 1908.
p. 280, Zinc Ores of Butte, $\frac{2}{3}$ col.
p. 570, Patents, Wolf.
p. 711, 'Method of Extracting Zinc in Australia,' John Plummer, 2 pages, illustrated.
p. 750, Patent, Sulman and Sulman.
p. 751, Elmore process, 7 lines.
p. 783, Broken Hill, 15 lines.
- MINING WORLD (THE), Vol. XXX., 1909.
p. 509, Elmore process, 7 lines.
p. 634, Kendall graphite process, $\frac{1}{2}$ col.
p. 823, Australian concentrates, $\frac{1}{2}$ col.
p. 987, Murex, 6 lines.
p. 1080, Graphite concentration, 6 lines.
p. 1130, Murex, 5 lines.
- MINING WORLD (THE), Vol. XXXI., 1909.
p. 289, Elmore process, 6 lines.
p. 378, Elmore process, 5 lines.
p. 420, 'Sulphide Corporation,' John Plummer, 1 page, illustrated.
p. 566, Litigation, 5 lines.
p. 567, Sulphide Corporation, 5 lines.
p. 608, Murex, 5 lines.
p. 656, Patent, Lockwood and Samuel.
p. 792, Flotation processes in Mexico, $\frac{1}{2}$ col.
p. 893, History of flotation processes, 4 lines.
p. 894, Ore dressing in the U.S. and Mexico, 4 lines.
p. 1118, Oil-concentrating molybdenum, 3 lines.
- MINING WORLD (THE), Vol. XXXII., 1910.
p. 24, Horwood process, 14 lines.
p. 259, Flotation processes, 10 lines.
p. 575, Horwood process, 6 lines.
p. 712, Flotation processes, 1 col.
p. 807, Patent, Hoover.
p. 808, Flotation processes, 4 lines.
p. 923, Patent, Sulman.
p. 995, Minerals Separation Process at Broken Hill, 9 lines.
p. 996, Patent, Lockwood.
p. 1138, Elmore process, 6 lines.
p. 1140, Patent, Lockwood.
p. 1236, Flocculation of slime, 12 lines.

MINING WORLD (THE), Vol. XXXIII., 1910.

- p. 18, Elmore process, 1 col.
- p. 85, Patent, Sulman, Greenway, and Higgins.
- p. 191, Elmore process, 6 lines.
- p. 458, 'Ore Treatment at Broken Hill,' John Plummer, 2½ col.
- p. 574, Flotation processes, 6 lines.
- p. 576, Patent, Wentworth.

MINING WORLD (THE), Vol. XXXIV., 1911.

- p. 25, Patent, Hoover.
- p. 285, Zinc in Australia, 4 lines.
- p. 296, Selling zinc ores, 2 pages.
- p. 474, Zinc at Broken Hill, 3 lines.
- p. 475, Preparation of ores, 4 lines.
- p. 624, Flotation patents, 4 lines.
- p. 672, Flotation patents, 4 lines.
- p. 673, Broken Hill zinc, 3 lines.
- p. 677, Flotation patents, 4 lines.
- p. 773, Oil flotation, 6 lines.
- p. 791, Patent, Sanders.
- p. 865, Flotation patents, 4 lines.
- p. 869, Flotation patents, 8 lines.
- p. 915, Orijarvi mine, 3 lines; flotation processes, 3 lines.
- p. 919, Flotation processes, 8 lines.
- p. 963, Flotation processes, 5 lines.
- p. 1017, Flotation processes, 6 lines.
- p. 1019, Flotation processes, 6 lines.
- p. 1063, Mineral flotation, 4 lines.
- p. 1167, Flotation of minerals, 3 lines; Macquisten, 4 lines.
- p. 1219, Flotation of minerals, 4 lines.

MINING WORLD (THE), Vol. XXXV., 1911.

- p. 49, Bibliography, 5 lines.
- p. 157, Graphite flotation, 15 lines.
- p. 158, Graphite flotation, 15 lines.
- p. 168, Butte and Superior, 12 lines.
- p. 212, New process at Butte, ¼ col.
- p. 241, Elmore, 10 lines.
- p. 256, New process at Butte, ¼ col.
- p. 270, Bibliography, 7 lines.
- p. 271, Bibliography, 3 lines.
- p. 272, Bibliography, 7 lines.
- p. 275, Bibliography, 5 lines.
- p. 414, Bibliography, 5 lines.
- p. 496, Federal Mining Co., ¼ col.
- p. 505, Federal Mining Co., ¼ col.
- p. 513, Bibliography, 3 lines.
- p. 567, Bibliography, 3 lines.
- p. 124, 'Mines and Minerals,' Sept., 1911, 600 words.
- p. 603, Butte and Superior, 7 lines.
- p. 710, Butte and Superior, 20 lines.
- p. 724, Bibliography, 5 lines.
- p. 726, Bibliography, 5 lines.
- p. 729, Bibliography, 10 lines.
- p. 766, Butte and Superior, ½ col.
- p. 780, Bibliography, 4 lines.
- p. 781, Bibliography, 4 lines.
- p. 783, Bibliography, 4 lines.
- p. 834, Bibliography, 6 lines.
- p. 885, Butte and Superior, 10 lines.

MINING WORLD (THE), Vol. XXXV., 1911.

- p. 889, Bibliography, 10 lines.
- p. 891, Bibliography, 10 lines.
- p. 1027, Bibliography, 6 lines.
- p. 1029, Bibliography, 6 lines.
- p. 1075, Bibliography, 6 lines.
- p. 1127, Bibliography, 6 lines.
- p. 1130, Bibliography, 6 lines.
- p. 1230, Litigation, Minerals Separation v. James M. Hyde, $\frac{1}{4}$ col.
- p. 1278, Elmore process for molybdenite, 2 col.
- p. 1284, Bibliography, 7 lines.

MONEY MARKET REVIEW, Vol. XCV., 1907.

- pp. 611, 708, Zinc Corporation, Elmore process, and Minerals Separation, Ltd.

NOUVELLE THEORIE DE L'ACTION CAPILLAIRE, 1831.

Simeon Denis Poisson, variation of density near the surface of a liquid

OESTERREICHISCHE ZEITSCHRIFT f. B. u. H., Vol. XLIX., 1901.

- p. 307, Elmore Process.

OESTERREICHISCHE ZEITSCHRIFT f. B. u. H., March 5, 1910.

- Horwood process, 1 page.

OESTERREICHISCHE ZEITSCHRIFT f. B. u. H., Sept. 16, 1911.

- p. 513, 'Comparison and History of Elmore and Other Flotation Processes,' Max Moldenhauer, 2000 words.

ON THE EQUILIBRIUM OF HETEROGENEOUS SUBSTANCES, in 2 parts, 1876 and 1878. Josiah Willard Gibbs.

OPTICS, 31st.

Sir Isaac Newton.

ORE DRESSING, Robert H. Richards, 2nd ed., New York, *Engineering and Mining Journal*, 1906.

- p. 83, Elmore process.
- p. 1072, Elmore oil concentration mill at Glasdir.
- p. 1117, Note.

OUTLINES OF THEORETIC CHEMISTRY, Lothar Meyer, London, Longmans, Green and Co., 1892.

- p. 160 *et seq.*, 'Absorption of gases' and 'Capillarity.'

PACIFIC COAST MINER, Vol. IV., May 15, 1902.

- p. 17, Process for floating gold.

PACIFIC COAST MINER, Vol. IV., June 1, 1902.

- p. 14, Elmore process of concentration, $1\frac{1}{4}$ pages.

PACIFIC COAST MINER, Vol. VII., 1903.

- p. 45, Elmore process in Great Britain, $\frac{1}{4}$ col.
- p. 81, Elmore process, $\frac{1}{4}$ col.
- p. 97, Elmore oil concentration process, $\frac{1}{4}$ col.
- p. 144, Elmore oil concentration process, $\frac{1}{2}$ page, illustrated.
- p. 391, 'An Automatic Process of Oil Concentration,' J. W. Van Meter, 1 page, illustrated.

PACIFIC COAST MINER, Vol. VIII., 1903.

- p. 323, Concentration by oil, Van Meter process, $\frac{1}{4}$ col.
- p. 379, Oil process of ore concentration, 1 page, illustrated.
- p. 392, 'Selective Action of Hydro-Carbon Oil,' J. Van Meter, 1 page, illustrated.

PHILOSOPHICAL MAGAZINE, 1802, Vol. XIV.

- p. 193, John Leslie, first correct explanation of the rise of a liquid in a tube.

- PHILOSOPHICAL MAGAZINE, Vol. XXVII., 1864.
p. 176, Thos. Tate, Size of drops.
- PHILOSOPHICAL MAGAZINE, November, 1890.
Tensions of various water surfaces.
- PHILOSOPHICAL MAGAZINE, October, 1899.
Rayleigh, Theory of drops.
- PHILOSOPHICAL TRANSACTIONS, 1718, p. 739 ; 1719, p. 1083.
Dr. Jas. Turin.
- PHILOSOPHICAL TRANSACTIONS, 1805.
p. 65, Essay on the 'Cohesion of Fluids, 1804,' Thos. Young founded theory of capillary phenomena on the principle of surface tension.
- PHILOSOPHICAL TRANSACTIONS, 1886.
p. 627, A. W. Reinhold and Sir A. W. Rücker.
- PHYSICO-MECHANICAL EXPERIMENTS, London, 1709.
pp. 139-169, 'Surface Tension,' Francis Hawksbee.
- POGG. ANN. CI.
p. 551, J. C. Poggendorff, Capillary phenomena.
- POGG. ANN. CXXXIX.
p. 626, F. H. R. Lüdtege, Films of liquid.
- POPULAR SCIENCE MONTHLY, July, 1905.
'The Preparation and Properties of Colloidal Mixtures,' Arthur A. Noyes.
- PRINCIPIA GENERALIA THEORIAE FIGURAE FLUIDORUM IN STATU AEQUILIBRII, Gottingen, 1830, or Werk v. 29, Gottingen, 1867. C. F. Gauss, virtual velocities, conservation of energy.
- PROCEEDINGS AUSTRALIAN INSTITUTE OF MINING ENGINEERS, June 30, 1911.
'Treatment of Mixed Sulphides by the Horwood Process,' 14 pages.
- PROCEEDINGS CANADIAN MINING INSTITUTE, Vol. VII., 1904.
p. 185, 'Attraction of Some Common Minerals for Oil,' J. F. Hamilton.
'Properties of Matter,' Poynting and Thompson.
- QUEENSLAND GOVERNMENT MINING JOURNAL, January 15, 1909.
'Treatment of Broken Hill Ores,' W. Poole, 6½ pages.
- RASSEGNA MINERARIA, October 1, 1911.
p. 157, Flotation of minerals, 5600 words.
- REPORT OF THE ZINC COMMISSION OF BRITISH COLUMBIA, Ottawa, Government Printer, 1906.
p. 101, Flotation processes at Broken Hill, 7 lines.
pp. 121-125, Flotation processes, refers to Phitter, Delprat, and De Bavay, 4 lines.
- REVUE DE METALLURGIE, Vol. IV., 1907.
p. 568, 'The Elmore Process,' Alexander Stanley Elmore, 2 pages, illustrated.
- REVUE DE METALLURGIE, Vol. VI., 1909.
p. 1060, 'The Elmore Vacuum Process of Mineral Concentration and its Results,' L. Descroix, several pages, illustrated.
- REVUE MINERA, November 1, 1911.
p. 577, Flotation of minerals, 1000 words.
- ROYAL SOCIETY PROCEEDINGS, Vol. XLVIII., 1890.
pp. 127-140, 'Superficial Viscosity,' Lord Rayleigh.
- SCIENTIFIC AMERICAN, December 18, 1909.
p. 467, Patent decision Elmore v. Minerals Separation, Ltd., ½ col.

- SOUTH AFRICAN MINES, August 12, 1905.
Elmore Process.
- STATIQUE DES LIQUIDES, J. Plateau, Londres, Trübner and Cie., 1873.
pp. 69-71, Bubbles and diminished surface tension.
- SUR LA SURFACE DE REVOLUTION DONT LA COMBUSE MOYENNE EST CONSTANTE.
Lionville's Journal VI., C. E. Delaunay.
- SUR UN CAS PARTICULAIRE DE L'EQUILIBRE DES LIQUIDES, Nouveaux Mem.
de l'Acad. de Belgique, 1851 et 1853.
F. Duprez.
- TESTING FOR METALLURGICAL PROCESSES, by James A. Barr, London, 1910,
The Mining Magazine.
p. 153, Oil flotation.
p. 200, Cost of flotation.
- TEXTBOOK OF PHYSICS (A), by W. Watson, 8th im., 4th ed., London, Longmans, Green and Co., 1907.
pp. 180-184, Surface tension and capillarity.
- TEXTBOOK OF ORE DRESSING, by R. H. Richards.
p. 721, Flotation processes, several pages.
- THEORIE DE LA FIGURE DE LA TERRE, Paris, 1808.
pp. 105-128, Alexis Claude Clairault, Fluid attraction.
- THEORIE GEOMETRIQUE DES RAYONS ET CENTRES DE COURBURE, Bulletin de
l'Acad. de Belgique, 1857. A. H. E. Lamarle.
- TRACTATUS DE THEORIA MATHEMATICA PHAENOMENORUM IN LIQUIDIS ACTIONI
GRAVITATERIS DETRACTIS OBSERVATORUM.
Bonn. 1857, A. Beer.
- TRANSACTIONS OF THE INSTITUTION OF MINING AND METALLURGY, Vol. VIII.,
1899-1900, London, published by the Institution, 1900.
pp. 379-395, 'Notes on the Elmore Concentration Process,' Charles M.
Rolker, with discussion by members, 16 pages, illustrated.
- WEST AUSTRALIAN MINING JOURNAL, February 18, 1911.
p. 11, Oil flotation, 800 words.
- WESTERN CHEMIST AND METALLURGIST, March, 1908.
Presidential address of W. G. Swart to the Western Association of
Chemists and Metallurgists; also B. Haywood, Flotation processes.
- WESTERN CHEMIST AND METALLURGIST, Vol. V.
p. 469, 'History of Flotation Processes,' Edward Walker.
- WIED. ANN. 1886, 27.
p. 452, R. Eötvo's.
- ZEITSCHRIFT FÜR BERG, HUTTEN, UND SALINENWESSEN, Vol. LIII., 1905.
p. 125, Elmore process for diamond recovery.
- ZEITSCHR. PHYSIK. CHEM. 1893, 12.
p. 433, Sir W. Ramsay, and J. Shields.

INDEX.

	PAGE		PAGE
Acid—		Adhesion—	
Addition	132	Gas adhesion	53
" Hyde	37	Gas-bubble	54
" in tests	67	Increase by acidulation	53
" amount	90	Increase by sulphur chloride	41
Average price	90	Liquid adhesion	53
Avoidance of waste	135	Metallic sulphides	53
Charged extra	91	Molecular phenomenon	52
Cheap—Elmore	101	Natural tendency	55
Coagulation without	79	" enhanced	55
Cost—Potter	91	Not limited to solids	53
De Bavay adopts	92	Of gas-films	80
Delprat v. Potter	42, 43	Oil-gas adhesiveness	53
Economics	165	Preferential	60
Effect on hysteresis	57	Promoted by aeration	95
" recovery	70	Selective organic compounds	80
Elmore claim invalid	47	Solid and liquid	57
Excess-acid problem	79	Solid and gas	57
Gas producer—Elmore	102	Unbalanced liquid stresses	53
Gasification by agitation	78	Without oil or acid	79
Hyde uses	16	Adhesiveness	57
Hydrochloric—formation of	95	Gas and liquid	57
Increases selective action	4	Solid and gas	57
" adhesiveness	53	Adsorption	54
Introduction temperature	82	Advantages of Flotation—	
Its function	79	Economics of	159
Limiting amount	35	Aeration, see Air.	
Nitric acid	26	Affinity—	
Measuring for tests	63	Obscure law of	47
Methyl orange test	135	Agent, see also Fat, Oil, Acid—	
Non-acid possibilities	79	Soluble frothing	59
Oleic acid	63, 68	Transporting	58
Priority of idea	46	Agitation—	
Proportion of De Bavay	92	Advantage—Discovery—Everson	4
" Elmore	101	Aid to coagulation	89
" Hoover apparatus	113	Agitators—speed	122, 123
" Potter	8, 24, 25	" not needed	123
Result of addition	55	A.Z. Agitator—Illustration	93
Robson & Crowder reject	22	Centrifugal effect—Hoover app.	116
Soluble in water	86	Deleterious substances	78
Solution De Bavay	92	Description froth process	10
" Potter	83	Elmore mixer	100
Sulphuric acid proportion	70	" slow-moving	101
Sutton uses	21	Everson process	20
Tin recovery unaffected	103	Further agitation—Hoover	117
Unused—Early De Bavay	92	Gasification by	78
Use infringes Elmore	47	Haynes process	18
Acid-Flotation Process—		High speed—De Bavay	93
Common salt used	30	Hoover—Less subsequent	114
Defect in	12	" High speed	116
Delprat's claims	42	" Improved process	119, 121
First disclosure	27	How performed—Elmore	98
Potter's claims	42	Hyde process	16
Potter illustration	81	In tests	63
Acidity—		Kirby	30
In old water	119	Minerals Separation process	10
Acid Salt-Cake, see Salt-cake.		Number of agitators	120
Active Forces, see Forces.		Object of—De Bavay	93
Adhesion	52	Occlusion of bubbles	78
Adhesiveness unexplained	53	On addition of oil	14
Attraction	53	Production of bubbles	56
Aversion or affinity	54	Pumping by agitator	116, 118
Carbon-dioxide and sulphides	80	Renewal of	93
Enhancement—Potter	80, 85	Robson & Crowder	6
Enumeration of forces	54	Speed, in tests	67
Film of air flotation	55	" of rotation	73
Flotation considered	52	Sulman, Picard & Ballot	33

	PAGE		PAGE
Agitation—		Assays—	
Tests—Renewal periods	73	Traag mine, Norway	107
" Second period	68	Telemarken mine	107
To break up bubbles	89	Wilfley lead conc.	105
Variation tests	71	" zinc conc.	105
Violent agitation tests	72	Zinc Corp. concentrate	104
" " Wolf	27	" material	104
Air—		Zinc—De Bavay	97
Amount of	102	Zinc—Proprietary	91
Blown in—Kirby substitute	30	Assay of Concentrates, see also Concen-	
Carbonic acid replacement	79	trates.	
Compressed air—De Bavay	95	Assaying, see Working Costs.	
Cu. ft. in solution	102	Assistance of Others, Indebtedness to . .	ii
Elmore—Sammel method	42	Atmospheric Oxidation, see Oxidation.	
" vacuum releases	102	Atmospheric Pressure	27
Exclusion of	26	Attraction—	
Further aeration—Hoover	117	Between liquid and vessel	53
Hebron process—aeration	21	Avino Mines—	
Hockley's patent	21	Refractory ore	156
Hoover apparatus	113	Baker City, Oregon—	
High-pressure solution	35	Everson first tried	5
Klein patent	23	Ballot	3, 17, 111
Liberation of—Elmore	13	Elmore, action against	44
McCoy's patent	22	Minerals Separation formed	9
Norris' Patent application	45	Barite—	
Proportion of	13	Difficult separation—Elmore	103
Repeated aeration—De Bavay	95	Base Metals, see also Copper, Zinc, Lead,	
Repeated exposure to	35	etc.—	
Robson & Crowder	22	Combined with sulphur	1
Table—Elmore consumption	102	Metallurgy	2
Volume—Elmore	102	Methods of dressing ore	1
Air, see also Gas (bubbles).		Bibliography	168
Air-Flotation, see Flotation.		Acknowledgments	iii
Air-occlusion, see Bubbles.		Bingham Canyon Ore	157
Allen, H. A.—patent described	27	Bisulphate of Alkali Pa'tent	29
Alcohol—		Black Jack—	
Gasification with	78	Br. Hill blende	111
Alkaline Solution	26, 28	Blende, see Sulphide.	
Sanders	32	Block 14 Mine, Br. Hill—	
Alpimina Mining Co., Peru—		Used Potter	9
Van Meter & Boss process	8	Blount, Bertram—	
Amalgamated Zinc, see De Bavay.		On sulphide particles	54
Ambitious Inventors	iii.	Boss, Martin P.	3
Amyl Acetate—		See also Van Meter & Boss process.	
Froth agent	120	Boston Consolidated Co.—	
Amyl Alcohol	59	Used Elmore	7
Gasification with	78	Bornite—	
Froth agent	120	Ramsley Mine, Devonshire	104
Ancient Method of Separation	1	Telemarken mine	107
Angle of Contact, see Contact Angles.		Troublesome	157
Angular Hysteresis, see Hysteresis.		Bradford, Hezekiah	3
Annual Report Dept. of Mines, see Dept.		Patent described	19
of Mines.		Process outlined	4
Antimony Sulphides—		Similarity to De Bavay	92
Difficult separation—Elmore	103	Broken Hill Proprietary—	
Apparatus, see Machinery.		Illustration of plant	88
Aramayo, Francke & Co.—		Potter costs analysed	90
Use Murex	15	Uses Potter process	9, 81
Assays—		Uses Delprat process	87
Br. Hill blende	111	Broken Hill Proprietary Block 14—	
" tailings	111	Used Potter process	86
Concentrate	110	Broken Hill South Blocks—	
" Telemarken mine	107	Amalgamation with Zinc Corp.	16
" Traag mine	107	Broken Hill Zinkiferous Material, see	
Cost—Potter-Delprat	91	Zinc.	
Dolgelly concentrate—Elmore	104	Brown R. Gilman—	
Dolgelly tailing—Elmore	104	Aberration—Elmore process	79
Economics of	166	Bubbles (see also Gas)	55
Edmundian mine	106	Action explained	56
Feed tailing—Zinc Corp.	131	Air—by agitation	56
Final residue—Elmore	105	Air—occlusion problem	79
Final tailing—Sultelma	110	And particle—radil	56
Lead—De Bavay	97	Breaking off—Potter	86
" Proprietary	91	"	12, 28
Ramsley concentrate—Elmore	104	Carbonic acid gas	56
Silver—Proprietary	91	Surface aspects	55
" De Bavay	97	Form froth	56
Tailings	162		

	PAGE		PAGE
Bubbles (see also Gas)—		Carbonate—	
Froth—Hoover app.	114	Potter test	75
Froth prevents breaking of	86	Tests—proportion	70
Increase effective surface	58	Carbonate, Complex—	
Ineffective attachment	89	Broken Hill gangue	111
Loss of—Potter	84	Carbonate, Iron—	
Mechanical breaking up of	89	B.H. Proprietary tailing	81
Milky appearance	78	Carbonate Minerals—	
Occlusion by agitation	78	Limitation of flotation	155
Potter—Carbon dioxide	82	Carbonate Ores—	
Relative diameters	56	Is flotation feasible?	79
Released by vacuum	56	Carbonate of Ammonia—	
Size of bubbles	55, 58	Soaking ore in—De Bavay ..	14, 31
Sulphides uniform action	55	Carbonic Acid Gas—	
Super-atmospheric pressure	56	Passed into wet ore—De Bavay	14, 31
Their radius	55	Potter-Delprat	59
Too rapid growth	89	Replacement by air	79
Various kinds produced	56	Cattermole, Arthur Edward	3
Vacuum formation	98	Cattermole Process	3, 17
With agitation—test	78	Abandoned by Min. Sep.	124
" alcohol	78	Description of	10, 111
" amyl alcohol	78	Offered Elmore and Webster ..	44
" camphor	78	Patent described	25, 26, 29, 30
" essential oils	78	Purchased by Minerals Sep.	9
" kerosene	78	Cattermole, Sulman & Picard—	
" oleic acid	78	Patent described	28, 30
Buddle, see Machinery.		Central Plant, see New Central Plant.	
Buoy-Stock	5	Central Mine, Broken Hill—	
Rubbing movement	21	Used Min. Sep. process	10
Heat and vacuum	21	Centrifugal Effect—	
Burn, Alfred K.—		Of agitation	116
Indebtedness to	iii.	Chalcocite—	
Butters, Charles—		Ramsley Mine, Devonshire	104
Purchased Elmore (old) process ..	7	Troublesome	157
Camphor	59	Chalcopyrite	62
Gasification with	78	Difficult separation—Elmore ..	103
Calcite—		Edmundian mine	106
Broken Hill gangue	111	Garpensberg Mine, Sweden	107
B.H. Proprietary tailing	81	Ramsley Mine, Devonshire	104
Contained in slime	89	Sulitelma—Friability	108
Froment process	9	" Mine	108
Importance to flotation	81	Telemarken Mine	107
Potter test	75	Chapman, George A.	3, 17, 111
Producing gas—Elmore	102	Indebtedness to	iii.
Calcium carbonate	62	Patent described	35
An essential—addition of	155	Chemical Reaction Unlikely	60
Calibration	137	Chlorine Gas, see Gas.	
California Fuel Oil, see Oil.		Cinnabar—	
Capacity—		Readily concentrated—Elmore ...	103
Amalgamated Zinc mill	96	Clear solution, see Acid.	
British plant	89	Cleavage Plane	57
Concentrates—Potter	85	Coagulation	60
Delprat—Proprietary	87	Agitation an aid	89
Elmore unit	100, 101	Coagules	61
Estimated daily—Minerals Sep. ...	120	Example of butter	61
Flotation vats—Potter	85	Flocculent masses	60
Gillies plant	90	For slime treatment	60
Hoover apparatus	114	Hyde process	16
Mill v. Units	105	Illustration, verbal	60
Minerals Sep.—Saxberget	110	Manifestation of adhesion	61
North plant—De Bavay	95	Potter pulp	85
Of zinc-tanks	141	R. Storm on	60
Sulitelma concentration mill	110	Rescues slime	61
Cape Copper Co.—		Rolling-motion stirring	61
Used Elmore	7	Salts, beneficial effect	119
Capillary Action	49	Soap addition	60
Carbon—		Sulman & Picard	30
Separating from impurities	30	Without acid	79
Carbon Dioxide, see also Gas	60	" oil	79
Carbonate—		Coalescence, see Coagulation.	
Absence and addition	76	Cohesion	41, 52, 54
Acid action upon	81	Combinations—	
Acid and bubbles	56	Economics	158
Addition by De Bavay	35	Flotation and other treatments ...	158
Excess of, detrimental	155	Commercial Aspect—	
Film of, removal	14, 31	Application	6
Importance to flotation	81	Elmore (Old process)	6, 23
Potter—acid action	82	Gillies process—failure	14

	PAGE
Commercial Effectiveness	58
Commercial Recovery—	
Potter's advantage	85
Common Salt Process, see Delprat.	
Compactness—	
Hoover app. (New)	118
Concentration, see Separation, Water	
Concentration.	
Concentrates—	
Assay of—Delprat	88
" Dolgelly-Elmore	104
" Ramsley-Elmore	104
" Telemarken mine	107
" Traag mine	107
" Zinc Corp.	104
Capacity—Hoover app.	114
Crushing, sizing—Elmore	101
De Bavay best produced	95
Delprat, production of	88
De-oiling by heat	104
Discharge—Elmore	99
Drying—Zinc Corp.	104
Edmundian mine—assay	106
Elmore tonnage—lead	105
" " zinc	105
Entrapping concentrate	3
Floating concentrate—illustration .	83
Gillies, production of	90
Gummosity of	80
Gummy—Potter	86
High-grade conc. and recovery .	11, 38
" Hadeland mine	107
Hyde—Low-grade to high	16
Lead concentration	137
Lead—De Bavay	97
Lead and zinc—Zinc Corp.	140
" market	125
" concentration	125
Lead-zinc-silver—Saxberget	110
Ore yield 16%	102
Potter capacity	85
Production—Proprietary	91
Ratio of	161
Ratio of—Proprietary	91
Ratio of supply—De Bavay	97
Re-treatment by burning	13
" Potter	86
Re-rotation	134, 137
" calibration	137
Softness of material—Dolgelly	104
Subsequent treatment	120
Sulitelma	110
Tin—Elmore	103
Total—De Bavay	97
Washing—Potter	84
Wilfley lead concentrate	105
Wilfley re-concentration	105
Wilfley treatment	105
Wilfley zinc concentrate	105
Wolf's low-grade—high extrac. .	12, 27
Zinc-concentrate	137
Zinc—De Bavay	97
Concentration by Flotation	2
Contact Angle	5
And meniscus.	79
Variation	57
Method of measuring	57
Mutual-solid-liquid-gas	57
Problem of	79
Sulman on	57
Content, see Metal Content.	
Cooling, see Heat.	
Copper—	
Ore treatment—Dick	36, 37
Dolgelly ore	104
Garpensberg mine	107
Sulitelma mine	108, 110
Telemarken mine	107

	PAGE
Copper—	
Copper Finely Disseminated	2
Special province of flotation	160
Copper Pyrite, see Chalcopyrite.	
Copper Sulphides—	
Difficult separation—Elmore	103
In tin ore	103
Copperas (Iron sulphate)—	
Hyde process	16
Cornwall Tin Ore, see Tin.	
Cost, see also Working cost—	
Elmore unit	100
Potter plant	86
Repairs—Potter	85
Crilly, Thomas F.—	
Financed Everson	5
Crilly & Everson Process, see Everson.	
Crowder	3
Crushing, see also Grinding—	
Brightens sulphides	112
B.H. tailings	112
Elmore—Zinc Corp.	105
Fine crushing—Minerals Sep.	112
Slime production—Minerals Sep.	112
Curle, J. H.—	
Formation of Minerals Sep.	9
Cylinder Oil, see Oil.	
Darling, James D.	3
Patent described	30
De Bavay, A. J. F.	3
Adopts oil and acid	92
Amalgamation Minerals Separation	92
Amalgamated Zinc buys	14, 96
Amalgamated Zinc amalgamates	
with Min. Sep.	17
Australian rights	95
Basic principle	76
Clean sandy feed	92
Composition of oil	93
Clear statements not published .	14
Cream of tailings	96
Drawing off solution	93
Experimental work	95
Film of sulphides	92
Finality reached	92
First used North mine	92
Flotation cones	93
Full description of process	92
High-speed agitation	93
Installed Block 10	14
" B.H. North mine	14
Later stages described	92
Metallic scum	93
Mixing device	92
North mine plant	95
Object of agitation	93
Oiling tailing	93
Oiling vat	93
Patent described	31, 32
Process described	13
Proportion of acid	92
Purely surface-tension	92
Recovery	96, 97
Re-treatment plant	96
Renewal of agitation	93
Repeated washings	93
Similarity to Bradford	92
Slime discarded	92
Tables of recovery	95
Tailing de-slimed	92
Tests	76
Tonnage treated	97
Uses surface film	58
Vannering scum	93
De Bavay Treatment Co.—	
World rights	14

206 CONCENTRATING ORES BY FLOTATION.

	PAGE		PAGE
De Bavay Sulphide Process Company—		Economics of Flotation—	
Owners in Australia	92	Slime	158
De Bavay v. Macquisten	42	Water	166
De-Leading Section	137	Edmundian copper mine, S. Africa—	
Deleterious Substances	78, 79	Chalcopyrite	106
Elmore process aberration	79	Desc. of plant	106
Flour	79	Elmore process used	106
Glue	79	Recovery	106
Ox-gall	79	Effective Surface, see Surface.	
Starch	79	Effervescence—	
Tannin	79	Everson	6
De-Oiling, see Oil.		Hebron process recommends	21
Delprat, Guillaume D.	3, 8, 80	Electrolysis of Water	30
His work	80	Elmore, Alexander Stanley—	
Application overcoming invalidity	45	Patents described	23, 24, 26, 30, 33
Bi-sulphate alkali patent	29	Elmore, Francis Edward—	
Common salt process	30	Patents described	22, 23, 30, 31, 32
Manager B.H. Propy.	87	Elmore Brothers	3
Patent described	25, 26, 27	Elmore (Old Process) outlined	6
Plant re-modelled	88	Elmore Vacuum Process	8
Potter's Australian rights	80	Abandoned Zinc Corp.	106
Used by Proprietary	87	Aberration described	79
Delprat Pan—		Absence of vibration	101
Introduction Block 14	86	Acidulation claim invalid	47
Density of Solution—		Action against Webster, Ballot & Hay	44
Avoidance of	135, 136	Air per ton	102
Remedy for	136	Alleges infringement Min. Sep.	44
Department of Mines N.S.W.—		Ambiguity of patents	47
First mention flotation	123	Annular space	100
De-Sliming, see also Working Costs, Slime—		Application of process	102
De Bavay	92	Basic principles	98
Deterioration of Belts	139	Breakages almost unknown	103
Detrimental Conditions—		Clean tailings	103
Through weathering	14	Conical separating chamber	100
Detrimental Effect of Salts, see Salts.		Crushing	105
Development of Processes—		Darling's decision quashed	44
By Minerals Sep.	111	Description of process	13, 98
De-Watering, see Water.		Discharge continuous, automatic	100
Dick, Frank Burnett—		Distribution total conc.	106
Patent described	36, 37	Dolgelly Mine, N. Wales	104
Differential Flotation, see Flotation.		Durability of plant	103
Dimensions of Units—		Edmundian mine	106
Minerals Separation	120	Essential differences	47
Discovery of New Methods—		Excellent mechanical design	103
Spur to	1	Exhaustive trials made	105
Dodé, Edward	3	Expansiveness or contractiveness	47
Patent described	20	Explanation of process	98
Dolcoath, Cornwall—		Extraction—Dolcoath mine	104
Elmore process used	103	Feed tonnage—Zinc Corp.	105
Dolgelly Mine, N. Wales—		Final lead conc.	106
Elmore plant used	104	Flotation—Zinc Corp.	105
Douglas, James—		Flow Sheet—Telemarken	109
Secrecy in commerce	40	" Zinc Corp.	106
Dumps—		" Garpensberg Mine	107
Remove	130	Illustration section	99
Duplicate		" machine	100
Prevention of	iii.	" Mining Journal " article	104
Dyne—		Inapplicable all ores	103
Metric expression	50	Increase of surface	58
Economic Aspect, see Commercial Aspect.		Ingenuity of	98
Economics of Flotation	154 to 167	Justice Buckley's definition	41
Acid	165	Justice Neville's definition	46
Advantages	159	Lord Atkinson's definition	47
Assays	166	Lord Chancellor's criticism	47
Combinations of processes	158	No delicate adjustments	103
Conclusions	166	No expensive foundations	101
Fuel	166	No sizing pulp	101
General Expenses	166	Non-suited by Darling	44
Labour	166	Observation windows	100
Limitations of process	154	Oil and acid introduction	98
Magnitude of process	159	One unit v. mill	105
Oil	165	Other installations	110
Power	165	Percentage distribution—Feed	106
Royalties	163	Possible differential flotation	102
Supplies	165	Priority valid	47
Sulphide separation	157	Proportion of air	102

	PAGE		PAGE
Elmore Vacuum Process—		Experimental Work, see Tests.	
Pulp introduction	98	Extraction see also Recovery—	
Refractory ore success	103	Elmore—Dolcoath tin	104
Re-grinding—Zinc Corp.	104	Elmore mill <i>v.</i> unit	105
Residue—percentage distribution..	106	Satisfactory—Elmore—Hadeland..	107
Zinc Corp.	105		
Re-treatment on Wilfley's	105	Fat, see Oil.	
Revolving drum	6, 23	Feed, see Tailing.	
Satisfactory extrac.—Hadeland ..	107	Felspathic Gangue, see Gangue.	
" results—Dolcoath	103	Filling—	
Separable compounds—list	103	Gangue utilised—Potter	85
Separates diamonds	24	Film, see also Oil, Pulp—	
Sizing—Zinc Corp.	105	Air-film flotation	55
Solid construction	103	" De Bavay	95
Subtlety of patents	47	Film and bubble	32
Success at Saxberget	110	Film of air	29
Sulitelma	107	Film of gases	53
Syphon arrangement	99	Gas and oil—Potter	85
Table of tonnages	105	Of sulphides—De Bavay	92
Tailing—Direct-treatment	104	Of carbonate—De Bavay	14, 31
Telemarken mine—Norway ..	107, 109	Scum—De Bavay	14
Test	77	Surface film	58
Thickening tanks	109	Without acid or oil	79
Traag mine—Ceased working	107	Filter Press	26
Two yea s continual use	105	Final Residue, see Residue.	
Used at A vino mine, Mexico	13	Financial Papers—	
" B. C. Hill Propy.	13	Indebtedness to	iii.
" Caucasus copper mine	13	Fineness of Crushing, see also Crushing—	
" Cobar gold mines, N.S.W.	13	Requisite fineness—Minerals Sep.	112
" Dolcoath	13, 103	Fineness of Material, see Material.	
" Dolgelly, Gt. Britain	13	Fire Account, see Working Costs.	
" Edmundian mine, Africa ..	13, 106	Float Gold, see Gold.	
" Garpensberg Mine, Scan-		Floating Concentrate, see Concentrate.	
dinavia	13	Flocculent Masses, see Coagulation.	
" Hadeland, Scandinavia ..	13, 107	Floor Space—	
" Namaqua copper	13	Saving—Hoover apparatus ..	115, 118
" Pinnacles mine, N.S.W.	13	Flotation	2
" Ramsley mine	13, 104	Accidental discovery at Denver ..	5
" Saxberget, Scandinavia ..	110	Air—generally used	80
" Sulitelma, Norway	13	Air per ton—Elmore	102
" Telemarken mine	13	Air <i>v.</i> oil-flotation	42
" Traag mine, Norway ..	13, 107	Addition of acid	55
" Zinc Corp.	13, 104	" oil	55
Wear small	103	Analysis of principles	55
Webster's opinion on	44	Applicability	154
Where other methods impossible ..	103	Bad reagents problem	79
Widely experimented	103	Carbonate flotation feasible(?) ..	79
Working cost	101	Chronological discussion difficult (?)..	
Zinc conc. tonnage	105	Differential flotation—Elmore ..	102
Zinc Corp. adopts and abandons ..	16	Elmore's oil-flotation	46
Elmore <i>v.</i> Minerals Separation—		" vacuum	98
Case described—Appeal	46, 47	Elmore—Zinc Corp.	105
German patent	45	Gas, Selective action	3
Elmore <i>v.</i> Sulphide Corporation Ltd.—		Goyder's tests	75
Appeal pending	48	Gravity	57
Case described	48	Heavy substances	2
Elmore <i>v.</i> Van Meter—		Ideal ore	155
Case summarized	41	Knowledge of not	2
Electric Light, see Working Costs.		Largest plant—De Bavay	14
Electric Power, see Working Costs.		Lines of progress	155
Emulsification	7	Limitation ..	154
Alkaline agents	26	" 1st	155
Engineers—		" 2nd	155
Point of departure for	iii.	" 3rd	156
Enhanced Tendency, see Adhesion.		" 4th	156
Essential Oil—		Main principles enumerated	54
Eucalyptus Amygdalena	60, 71	Minerals Sep. air-rotation	46
Froth producer	120	Non-acid process (?)	79
Test	71	Novelty of earlier phases	2
Evaporation—		Oil, Selective action	3
Loss of water	139	Potter—gas process	80
Everson, Carrie J.	3	" How accomplished	80
Analagous to Haynes'	20	Repeated use of water	119
Patent described	20	Restricted range	154
Tardy justice to	5	Salts' detrimental effect	119
Expenses, see Working Cost.		Separation of oranges	154
Experimental Account, see Working		Simple case of	55
Costs,		Speed of—Potter	85
		Stages of development	3

208 CONCENTRATING ORES BY FLOTATION.

	PAGE		PAGE
Flotation—		Froth—	
Sulman's Hysteresis discovery	57	Rouse's patent	21
Sure expedient of metallurgist	2	Simpler tester's disadvantage	73
Tests	62	Skimming with spoon	73
What is flotation ?	60	Slime present—Minerals Sep.	112
Wide field	2	Soda-syphon froth	73
With film of air	55	Soluble frothing agents	59
Without oil, acid	79	Soluble paradox	60
Wood separated from rubber	154	Soluble producer	120
Flotation Agent—		Solubles used	60
Turpentine	37	Some addition necessary	59
Flour—		Spoon for skimming	73
Deleterious to frothing	79	Substances useful	59
Flow-Sheet—		Test leakages	65
Block 14	87	Tests—running off	68
Elmore—Zinc Corp.	106	Thickness of	58
New Central plant—Min. Sep.	126	Thickness in tests	68
Potter-Delprat	83	What is froth ?	60, 79
Telemarken mine—Elmore	109	Unused early De Bavay	92
Fluorite—		Vannerling De Bavay scum	93
Contaminates concentrate	156	Frothing Agents—	
Fluoride—		Advantages of	120
Added to pulp	35	Fuel—	
Foam, see Froth.		Cost—Potter-Delprat	91
Forces—		Economics of	166
Act continuously	58	Fuel and Fluxes, see Working Costs.	
Enumeration of	57	Fuel Oil, see Oil.	
Unit force	58		
Friction—			
De Bavay—carbonate film	14, 31	Galena, see also Lead—	
Friction Head—		Difficult separation—Elmore	103
Hoover app. (new)	117, 118	Gas adherence to—Potter	83, 84
Froment, Alcide	9, 17, 111	Gangue, see also Separation—	
Addition of calcite	9	Acid and water adhesiveness	53, 54, 56
Patent described	24	Aversion to oil	53
Purchase by Webster	44	Barite	103
Froth, see also Film—		„ easily separable	159
Adherence of oil	60	Broken Hill tailing	111
Agent added continually	60	Causing to sink	2
Alcohol	36	Change of colour	60, 67
Aromatic hydroxides—phenol	36	Composition—B. H. Propy.	81
Characteristic—Minerals Sep.	92	Crushing free from	112
„ Potter-Delprat	92	Disposal of—Elmore	99
„ Elmore	92	„ Potter	85
Coagulation	61	Draining of—Potter	85
Constituents	60	Feeble gas-oil adhesiveness	53
Deleterious substances	78	Felspathic—Edmundian mine	106
Dense froth—Potter	83	Felspar easily treated	159
„ Hoover app.	114	Flotation of	43
Disadvantage of skimming	73	Garnet, Broken Hill	81, 111, 103, 104
Elmore's vacuum	98	Gravity—Zinc Corp.	104
Emergence—Hoover app.	114	Heavy gangue separation	103
Eucalyptus best oil	120	„ Traag mine	107
Everson process	5	Hoover app.	117
Fatigue of solutions	60	Hornblende	107
Final disposal—Hoover app.	118	Leaps baffle—Hoover app.	114
Flow of—Hoover app.	117	Not coagulated	60
Flowing away—ditto	114	Potter-outlet	82
Formed by bubbles	56	Preference for water	56
Glogner's patent	28	Quartzitic—Garpensberg mine	107
Greenway, Sulman & Higgins	36	Rhodonite	104, 111
Hoover patent	36	Schistose—Dolgelly Mine	104
Horwood's method	88, 89	Schistose ores amenable	159
Increases surface	58	Separation by agitation—Everson	4
Insoluble producers—list	120	Separating graphite from	27
Insolubles to promote	59	Settlement in tests	68
Maleczek's patent	21	Silicious	2
Minerals Separation	10	Slaty Micaceous—Ramsley mine	104
Metallic scum—De Bavay	93	Spathic iron	103
Mineral froth	60	Stibnite	160
Normal temperature production	75	Sulitelma—Micaceous schist	108
Phenomena observable	60	Sulphide coagulation—effect	60
Potter's dense froth	80	Telemarken mine	107
Potter test—formation	75	Tendency to float	125
Prevents bubbles breaking	86	Zinc Corporation	104
Produced with vacuum	78	Garnet—	
Produced without oil	59	Broken Hill gangue	111
Quantity oil used	120	B. H. Propy. tailing	81
		Difficult separation	103


	PAGE		PAGE
Garnet—		Goyder & Laughton—	
Zinc Corp. gangue	104	Illustration of	28
Garpensberg Mine, Sweden—		Low capacity machine	86
Description of ore	107	Patent described	27, 28
" plant	107	Test-tube experiments	75
Number of units	107	Trap machine	86
Uses Elmore	107	Grade of Ore, see Ore.	
Gas—		Granulation, see Sulphides.	
Ability to condense	57	Granulation Plant—	
Affinity-particles and gas	3	Minerals Sep.	123
Air in fine subdivision	13	Granules, see Sulphides.	
Attachment when generated	57	Graphite—	
Bubbles of hydrogen	32	Flotation	156
Bubbles used	29	McCourt process	33
Carbonic acid used	59	Separation from gangue	27, 30
Carbon dioxide buoyancy	80	Gravitation—	
" excess	89	Feed	139
Chlorine gas—De Bavay	93	Gravity, see also Flotation	58, 59
" obscure effect	95	Zinc Corp. gangue	104
Composition of	57	Gravity-Concentration—	
CO ₂	75	Broken Hill	111
Fine state of subdivision	9	Grease, see Oil.	
Function of Chlorine	95	Greased Needle, see Surface Tension.	
Gas dissolved in water	34	Greenway, H. H.	3, 17, 111
Gas producer—Elmore	102	Greenway, Sulman, & Higgins—	
Generation by electrolysis	30	Patent described	36, 37
Insufficient gasification	60	Gregory, S.—	
Introduction by agitation—Min.		Formation of Minerals Separation ..	9
Sep.	10	Grinding, see also Crushing.	
Limitation and differential flotation	102	Grinding, see Working Costs.	
Maleczek's bubbles	21	Gummosity, see Concentrates, Organic	
Mickle—gas-bubble		Compounds—	
Milky appearance	78	Of concentrate—Potter	80
Mixtures of gases, liquids and solids	4	Gummy Organic Compounds—	
No mention by Potter	8, 24	Replacing oil—Potter	80
Oil adhesiveness to	53	Gummy Sulphides	120
Potter—Carbon dioxide	82		
Power to occlude	57	Hadeland Mine, Norway—	
Quantity soluble	98	Description of ore	107
Selective action	25	" plant	107
" Potter	82	Elmore used	107
Spray gas introduction	10	High-grade concentrate	107
Too rapid production	89	Haultain	3
Gas Film, see Film.		Haultain & Stovel—	
Gas-Flotation, see Flotation.		Patent described	24
Gas Generation—		Similar apparatus—Wolf	30
Potter method	81	Hay—	
Gas Tar Derivatives	59	Elmore's action against	44
Gasification—		Haynes, William	3
With chlorine—De Bavay	95	Not flotation process	4, 18
With mechanical agitation	78	Patent described	18
General Expenses, see Working Cost.		Sulphide-gangue separation	19
General Expenses—		Head—	
Cost—Potter-Delprat	91	Hoover app.	117, 118
Gillies, James H.	3	Head Room—	
Based on Potter principles	14	Saving—Hoover app.	115
Block 10 dump-purchase	90	Heat—	
Installed Block 10	14	Acid introduction temperature ..	82
Patents described	31	Boiling agitation mass	33
Production	90	Boiler for tests	73
Glasdir Mine, Wales—		Cooling sulphides—Potter	84
Elmore developed process here	6	Cooling the oil	26
Robson & Crowder first tried	6	Delprat uses	25
Glass Observation Windows	65	Everson—boiling water	5
Glogner, Moritz F. R.—		Expulsion of oil	105
Desc. of patent	28	Haynes uses heat	18
Glue—		Heating cost—Potter	90
Deleterious to frothing	79	Heating in tests	67
Gold—		Hoover apparatus	113
Readily concentrated—Elmore ..	103	Maleczek—hot oil	21
Sutton's patent	22	Potter uses	24
Sulman—Float gold	22	Steam feed—Hoover	116
Gold-Bearing Pyrite	12	Steam or air blown in	12
Good, Israel F.—		Suitable temperature—Potter	85
Patent described	30	Super-heated steam—Potter	85
Goyder	3, 17	Temperature	57
Goyder & Laughton—		Temperature regulation	135
First machine introduced	86	Variation in temperature	71

210 CONCENTRATING ORES BY FLOTATION.

	PAGE		PAGE
Heat—		Hoover Apparatus—	
Washing concentrate with hot water	12	One man 1,000 tons per day	119
Wolf process	12, 27	Ore feed	116
Hebbard, James—		Outflow—left to middle	113
Indebtedness to	iii.	Overall dimensions	119
Hebron, Charles B.	5	Passage of pulp	116
Hebron & Everson—		Patent described	36, 37
Buoyant material rubbed in	21	Proportion oil & acid	113
Heat and vacuum used	21	Pulp agitated	116
Patent described	21	Pulp churned violently	113
Radical departure	21	Pulp disposal	113
Henry & Dalton's Law	98	Pulp lines compartment	113
Utilized	34	Pulp over baffle	113
Higgins, A. Howard	3, 17, 111	Pulp pump—agitator	118
Indebtedness to	iii.	Rate of pulp flow	114
Patent described	36	Re-arrangement for ore	119
High Pressure, see Pressure.		Right compartment	114
Historical	1	Saving of space	115
Hockley, Edgar A.—		Side elevation	118
Patent described	21	Simpler mechanical arrangement	115
Hoover Apparatus—		Spitzkasten & baffle	118
Acid feed	113, 116	Spitzkasten (new)	116
Agitators	113	Steam feed	116
Agitation & mixing	121	Sulphide-bubble froth	114
Agitators (number of)	119	Sulphide flotation	121
Agitators' peripheral speed	113	Temperature of pulp	113
Air into pulp	113	Variations of connections	119
Alternative arrangement	115	Various forms of	119
Apertures	113	Water feed	116
Ascension of pulp	117	Water level	113
Baffle	113, 114, 117	Hoover Laboratory Sizer	132
Belt & gears	113	Hoover & Sulman—	
Capacity	114, 119	Anticipation of Norris	45
Centrifugal agitation	116	Patent described	35
Changes—nature of ore	119	Horizontal Section Decreasing in Area	
Concentrate produced	114	Upward—	
Dense froth	114	Van der Naillen	23
Description	113-123	Merrill	24
Elimination—pipes, pumps, valves	121	Goyder & Laughton	28
Enormous air-introduction	113	Hornblende—	
Equal inflow & outflow	113	Telemarken mine	107
Extreme compactness	118	Horses & Drays, see Working Costs.	
Feeding in pulp	113	Horwood, Edward James	3
Feeding oil, acid, water	121	Process described	36, 147-149
Front to front	119	Slime treatment idea	88
Further agitation & aeration	114, 117	Sulphide separation	157
Further improvement	121	Hot Water, see Water.	
Froth emergence	114	Howard, A. C.—	
Gangue leaps baffle	114	Indebtedness to	iii.
Gangue passage	117	Hyde, James M.	3
Head	117, 118	Indebtedness to	iii.
High-speed agitators	116	Hyde Process—	
Horizontal lip	113	Butte & Superior Copper Co. use	17
Horse power required	119	Description of process	16, 37, 149 to 153
Illustrations	112-123	First adopted U.S.	17
" front elevation	116	High-grade concentrate	38
" longitudinal section	114	Low grade 10 high	16
" plan	117	Uses acid	16
" side elevation	118	" agitation	16
Improvements	113	" copperas	16
Independent of operator	121	" coagulation	16
Inflow of pulp	113	Hylton, C. J.—	
In front of one man	119	Indebtedness to	iii.
Ingredients thoroughly mixed	113	Hysteresis	57
Labour required	119	Effect of acid	57
Latest form described	116	Of silica	57
Less subsequent agitation	114	Range and contact angle	79
Limits of apertures	113	Illustrations—	
Lip	117, 118, 121	A. Z. Agitator—De Bavay	93
Live steam	113	Block 14 plant flow-sheet	87
Mixing compartments (new)	116, 117	Bradford apparatus	19
Minerals Separation	113	Broken Hill Proprietary plant	81
Mixing & agitating compartments	113	B. H. Proprietary plant	88
Modified spitzkasten	113	Central tailing dump	127
Most recent form	115	Contact angles	57
Nest of boxes	114	Elmore plant	99, 100
Oil feed	113, 116	Flow-sheet	106
One liquid level	117		

INDEX.

211



	PAGE
Illustrations—	
Flotation cones—De Bavay	94
Goyder & Laughton	28
Granule flotation	76
Hoover apparatus	112-123
Horwood	147
Hyde's testing machine	64
" transverse section	66
" plan	66
" section	65
Macquisten tube	142, 144
Minerals Separation apparatus	112
Molecules (imaginary)	51
New Central plant flow-sheet	126
Potter	82
Potter-Delprat	84, 87
" flow-sheet	83
Sanders process	146
Simpler testing machine	74
Surface tension diagrams	55, 56
Telemarken plant	108
Flow-sheet	109
Test diagrams	69, 70, 71, 72
Tube with pocket	76
Wolf machine	27
Zinc tailing heaps	89
Infringement, see Patents.	
Injunction, see Patents.	
Insoluble Matter—	
Difficulties with	134
High percentage	134
Iron. Broken Hill gangue	111
Iron Carbonate—	
B. H. P. tailing	81
Iron pyrite—	
Dolgelly mine	104
Garpensberg Mine, Sweden	107
Scandinavian ores	156
Sulitelma mine	108
" residues	110
Iron Pyrite Carrying Gold—	
Easily concentrated—Elmore	103
Iron Sulphate	16
James Brothers—	
Reported on Robson & Crowder ..	6
Jet, see machinery.	
Kendall, Cosmo	3
Patent described	27
Kerosene, see Oil.	
Kirby, Edmund B.—	
Patent described	30
Klein, John—	
Patent described	23
Klug, George C.—	
Indebtedness to	iii.
Labour—	
Cost—Potter-Delprat	91
Economics	166
Saving—Hoover app.	115
Labour of Others—	
Indebtedness to	iii.
Latimer, James Francis	3
Patent	34
Laughton	3
Lavers, Henry	3, 17, 111
Indebtedness to	iii.
Law of Henry & Dalton	34, 98
Laws—	
Underlying processes	iii.
Le Roi—	
Used old Elmore process	7
Lead, see also Galena—	
Assay—Broken Hill tailing	112
Assay—De Bavay	97

Lead, see also Galena—	
Assays—Proprietary	91
Assay—Wilfley concentrate	105
Assay—Zinc Corporation	104
Saxberget	110
Tailing—Broken Hill	111
Traag mine, Norway	107
Zinc Corp. concentrate	104, 140
Lead Concentration—	
Zinc Corp. tailing	104
Block 14	86
Lead Minerals—	
Difficult separation—Elmore	103
Lead Recovery, see Recovery.	
Leechman, John—	
Indebtedness to	iii.
Limestone, see Calcite.	
Limitations of Flotation	154
Ancient & new magnetic method ..	1
Lip, see Overflow, Machinery.	
Liquid—	
Composition of	57
Level—Hoover app.	117
Litigation	39 to 48
Potter & Delprat	88
Lockwood, Alfred Arthur	3
Patents	37
Lockwood & Samuel—	
Invented Murex process	15
Patent	35
Patent described	36
Locomotive Traction, see Working Costs.	
Loss—	
Copper in tailing—Sulitelma	108
Machinery & Apparatus—	
A. Z. Agitator—De Bavay	92
Accurate surfaces	67
Agate-ware dishes	67
Agitator-arms	67
Agitator central tube	92
Agitators—Minerals Sep.	120
Agitator—normal speed	67
" rack & pinion	92
Allis-Chalmers Anaconda mill	107
Air-jets—Potter	85
Air-lifts—Potter	85
Air-pump	75
Baffle	113, 114, 117
Ball-mill house—Sulitelma	109
Belt conveyors	127
Bicycle pump	73
Bins	81
" concrete	130
Blind pocket—functions	82
Blind-pocketed vat	81
Bottom outflow—Potter	85
Bradford apparatus	19
Bucket elevator—slime	87
Bucket tramway	125
Buddle	34
" tailing-bin	87
Burettes	67
Californian stamp-battery	104
Callow settlers	131, 138, 139
Cast-iron flotation boxes	88
Centrifugal apparatus	7
" pump	89
Challenge feeders	130, 131
Chutes	131, 141
Collecting vat obstructions	82
Concrete tanks	139
Concentrating tables—Potter	83
Conical separator—Elmore	99
Conveyors	88
Crushing plant—Garpensberg mine	107
De Bavay cones—corrugations ..	95
Defective mechanical application ..	6

212 CONCENTRATING ORES BY FLOTATION.

	PAGE		PAGE
Machinery & Apparatus—		Machinery & Apparatus—	
Distributing tank—Potter	83	Pressure gauge	75
Draining tanks.....	139, 141	Railway trucks	84
Driving-shaft pulleys	120	Rakes—Elmore	99
Edgar Allen ball-mill	103	Reciprocating stone-breaker	104
Electrical furnace—Saxberget	110	Residues conveyor—Potter	83
Elevators	131, 139, 140	Revolving screens—Zinc Corp.	104
Elmore's apparatus	13, 98	Rolls—Garpensberg mine	107
" foundations unnecessary ..	101	Sulitelma	108
" greased belt	23	Rubber-belts.....	23, 24, 33, 37, 139
" mixer	100	Rubber cushion	67
" revolving drum.....	6, 23	" gangue belt	85
" settling tanks.....	110	" strakes	34
" thickening tanks	109	Rubbish trommel	130
Feed-pipe—Elmore	99	Schwarz apparatus	29, 31, 33
Ferraris wet ball-mills.....	107, 109	Screens—revolving.....	131, 137
Filter bottom tanks	141	Settling-pans—Scammell	25
Flotation boxes—Potter	86	" tanks—Sulitelma	110
Flotation cones	93	Simpler testing machine	73
" vats	81	Soda-water syphon	73
" capacity	85	Solution sump—Potter	85
Frue vanners	103	Solution vats—Potter	85
Gangue outlet—Potter	82	Spitzkasten	7
Gates crusher	107, 109	" Min. Sep. 113, 114, 118, ..	120
Gillies apparatus	14	" Potter	83
Glass cylinder—Elmore	100	Spoon for skimming	73
Glass jar	77	Spray introduced by Sulman & Picard	10, 29
Goyder & Loughton machine ..	12, 86	Steam-shovel	88
Grinding-pans	81, 104	Stone-breakers, Dolgelly.....	104
Grondal ball-mills—Saxberget ..	110	" Edmundian mine ..	106
Haultain & Stovel's oiled belt ..	24	" Garpensberg	107
" machine	24	" Saxberget	110
Haynes' triturating machine ..	18	" Sulitelma	108
Heater—Potter	83	" Traag	107
Heberle ball-mills—Sulitelma ..	110	Stone shipping bins	141
High-speed rolls	104	Stuffing-gland	67
Holman pneumatic stamps	106	Suction pump	77
Hoover apparatus	10, 113	Sump—Potter	83
" patent described	36	Syphon—Elmore	99
" laboratory sizer	132	Tables—Sulitelma	108
Horizontal section	23, 24, 28	Tailing discharge—Elmore	99
Horse-tram—Sulitelma	109	Tank—Potter	83
Huntington mill	104	Test agitator	65
Hyde's testing machine	64	Tests—windows	68
Hydrometer	136	Test steam tube	67
Impeller mixer	132	Testing machine—description ..	65
Incline tram	87	Tin boiler for tests	67
Iron pipes	81	Tram track—Zinc Corp.	130
Iron trough	139	V. Settler—Potter	83
Jet floating sulphides	42	Vacuum pumps—Sulitelma	108
Jet recovering oil	42	Valve	67
Jigs—Sulitelma	108	Van Meter & Boss app.	8
Jigs & tables—Garpensberg	107	Vanners—Sulitelma	108
Krupp ball-mills—Hadeland ..	107	Vanning plaque	76
Lauder—Potter	84	Weir-Meredith vanners	138
Loading gantry	130	Wet ball-mills—Garpensberg ..	107
Macquisten tube	14	Wilfleys	137
Main driving shaft	120	" tables	105
Mason fruit jar	77	" —slime	87
Metal cylinder—Elmore	100	" —Traag	107
Mixer—Elmore	99	Wolf's greased belt	34
Mixer box—Minerals Separation ..	132	" jet	42
Mixing-boxes—Minerals Sep.	120	Wooden tanks—Potter	84
Mixing device—De Bavay	92	Wormed wheel—Elmore	99
Mixture of gases, liquids, solids ..	4	Macquisten, Arthur P. S.	3
Montejus—De Bavay	93	Adelaide Reduction Wks., Nevada	14
Observation windows—Elmore ..	100	Basic principle	77
Oil-belt—Wynne	37	Capacity	15
Oil-mixer	93	Desc. <i>in extenso</i>	142 to 144
Oiling vat—De Bavay	93	Federal Mining and Smelting Co. uses	15
Opening Mixers to Spitz	120	Now uses oil	15
Overflow lip—Potter	83	Patent described.....	31, 33, 34
Picking-belt	109	Test	77
Pipettes	67	Tube apparatus	14
Pocketed vats	81	Magnesium—	
Pocket with outlet (vats)	81	Broken Hill gangue	111
Pocket without outlet (vats) ..	81		
Pooley weigh-bridge	130		

	PAGE		PAGE
Magnetic Concentration—		Minerals Separation—	
Sulphide Corp. production.....	86	Illustration	112
Magnetic Flotation Method—		Improvement—recent.....	119
Lockwood process	37	Increase of surface	58
Magnetic Ore Separation	1	Justice Buckley's definition	42
Murex Oil increases magnetism	15	" Neville's	46
Magnetic substances added	15, 36	License to use	111
Magnetic Qualities of Particles—		Lord Atkinson's definition.....	47
Disregard of	2	Main driving shaft	120
Magnetic Substances—		Minerals Sep. Ltd., owners	111
Addition of	15, 36	Mixing boxes required	120
Magnetite—		New Central mill	125
Difficult Separation—Elmore	103	Openings—Mixers to Spitz	120
Garpensberg mine, Sweden	107	Old granulation plant.....	123
Hadeland mine, Norway	107	Present process	10
Sulitelma residues	110	Pulp treatment	113
Magnitude of Operations—		Purchased Central tailings.....	11
Economics	159	Purchased Froment patent	9
Maleczek—		Replaced Elmore—Zinc Corp.	106
Patent described	21	Sectional sampling	133
Mammoth Mining Co., Utah—		Slime plant	124
Used Butters' Elmore (Old) process ..	7	Slimes—amount produced	112
Material, see Tailing or Ore.		Spitzkastens reqd.	120
Mathematical Laws Underlying Process ..	iii.	Successfully tried Caucasus Cipper ..	11
Maxwell, James Clark	49	Successful Central mine	127
Angle of contact	56	Sulphide Corp. dump	128
McCourt, Cyril Douglas—		Thickness of froth	58
Patent described	33	Tried by Gillies	90
McCoy, John Henry—		Used Great Fitzroy	11
Patent described	22	Used Junction North mine, B. Hill ..	12
Mechanical Devices, see Machinery.		Used Lancefield, W. Australia	12
Mechanical Operations	1	Used Orijarvi mine, Finland	11
Meniscus	53	Used San Francisco del Oro	12
Problem of	79	Used Saxberget	110
Merrill, Charles W.—		Zinc Corp. material	131
Patent described	24	Minerals Separation, Ltd., v De	
Metal Content—		Bavay—Case described	48
Estimation of—Potter	91	Minerals Separation, Ltd., v Hyde—	
Metallic Scum, see Froth.		Case described	48
Metallic Sulphides, see Sulphides.		Minerals Separation, Ltd., v. Norris—	
Metallurgical Processes, see Processes.		Case described	45
Metals, Recovery of	1	Minerals Separation, Ltd., v. Potter—	
Methods of Separation—		Case described	45
Three enumerated	1, 2	Appeal described	45
Methyl Orange—		Mispickel	12
Testing acid solution	135	Mitchell, Deane P.—	
Micaceous Schist—		Indebtedness to	iii.
Telemarken mine	107	Manager Zinc Corp.	16
Sulitelma mine	108	Mixing Compartments, see Hoover	
Mickle, Kenneth A.—		Apparatus.	
Gas-bubble and oil	54	MnCO ₃ —	
Microscopic Examination	56	Broken Hill tailing	111
Middling—		Moisture—	
Block 14 & Potter	86	Excess in slime	138
British dump purchased	89	Reduction in residue	139
Disposal of	137, 138	Sampling for	130
Mineral Particles, see Sulphides.		Molecule, see also Theory—	
Minerals Separation—		Abnormally compensated	53
Adopted by Zinc Corp.	129	Free movement of	52
Agitators—number required	120	Imaginary illustration	51
Amalgamation with De Bavay ..	17, 92	Stress between	52
Another form	122	With uncompensated attractions ..	53
Application	111	Molecular Activity or Aspects	50-54
Can treat slimes	159	Molybdenum Sulphides—	
Conditions imposed	112	Difficult separation—Elmore.....	103
Considerable improvements	129	Molybdenite—	
Cost of	128	Flotation	156
Description of process	111	Murex—	
Description of work	128	Description	15, 144-145
Develops process	111	Installed Amalgamated Zinc	15
Dimensions of units	120	" Block 14	15
Directors, cordial thanks to	iii.	" Cordoba, Spain	15
Driving shaft pulleys	120	Used in Bolivia and France	15
Elmore charges infringement	44	Namaqua Copper Co.—	
Essentially different	47	Used Elmore	7
Formation of	9	Native Metals—	
Full description	111	Readily concentrated—Elmore ...	103
Hoover apparatus	113		

214 CONCENTRATING ORES BY FLOTATION.

	PAGE		PAGE
Natural Tendency, see Adhesion.		Oil—	
Neumann, S. & Co.,—		Selective action increased	15, 23
Purchased interest in old Elmore		" Robson & Crowder . . .	6, 22
process	7	" Elmore	23
New Central Mill	125	" priority	46
Nomenclature	50	" Haultain	24
Non-Acid Process—Sanders	35	Solid grease	30
Norris, Dudley Hiram	3	Sulpho-chlorinated oil—Wolf . . .	12, 27
Air-introduction patent	45	" Scammel	25
Patent described	35	Sumatra oil—Elmore	101
North Broken Hill Mining Co.,—		Sutton employs	22
First used De Bavay	92	Tar used as—Elmore	101
Nutter, Edward H.,—		Tests—various	71
Indebtedness to	iii.	Texas crude—Elmore	101
Occlusion, see Bubbles.		Texas residuum—Elmore	101
Oil—		Thick black oil—Everson	5
Addition of—Zinc Corp.	132	Tin recovery unaffected	103
Addition during tests	67	Unused—Early De Bavay	92
Addition of petrol	76	Old Granulation Plant, see Minerals	
Avoidance of waste	135	Separation.	
Attacks rubber belts	139	Oleaginous Process, see Oil.	
Affinity for sulphides—Haynes . . .	4	Oleic Acid, see Acid.	
Blast-furnace—Elmore	101	Ore—	
Borneo—Elmore	101	Base metal	1
Breaking up or emulsifying	7	Change of colour	60
Burned off for re-treatment . . .	13, 105	Concentration of	1
Burning off insolubles	120	Cornwall tin ore	103
California crude—Elmore	101	Crushing to fineness	1
Castor oil—De Bavay	93	Dolgelly mine—grade	104
Coagulation without	79	Dry ore treatment	19, 32
Composition of—De Bavay	93	Edmundian mine—assay	106
Cooling the oil	26	Feed—Hoover app.	116
Cylinder oil	77	Garpensberg mine, Sweden	107
De Bavay adopts	14, 92	" assays	107
De-oiling by heat	13, 105	Hadeland mine, Norway	107
Economics of	165	Haynes grinds fine	18
Elmore's large variety	101	Heavily mineralized—Garpensberg	107
Enhanced adhesion—Potter	85	Hyde's Machine useful	73
Essential oils	59	Ideal ore	155
Essential oil gasification	78	Oxidised ore process	37
Everson process	20	Per cent. mineral	102
Feed—Hoover	116, 121	Possible organic components	80
Feeding device—Hoover	113	Pulverised ore (Everson)	5
Fish oil—Elmore	101	Ramsley—Grade of	104
Fromont's discovery	9, 25	Saxberget mine—desc.	110
Fuel oil—Elmore	101	Sulitelma mine	107
Gasification by kerosene	78	" description of ore	108
Hot oil—Maleczek	21	" low-grade	108
Increased selective action	36	" hand-sorted	108
Insoluble oil replaced	120	" milling	109
Introduced as spray—Sulman &		" smelting	109
Picard	10	Telemarken mine, Norway	107
Kerosene—De Bavay	93	" ore sorted	107
" Elmore	101	Traag mine, Norway	107
Large quantity used	22	Unamenable to Potter	43
Light oils—Elmore	101	Untreatable	6
Measuring for tests	63	Untreatable—Delprat successful . .	8
Not used—Potter	85	Yields 16% conc.	102
Oil-amalgamation	23	Ore Concentration Company, Ltd., v.	
Oiled pumice, oiled charcoal . . .	25	Webster et al—	
" tailing—De Bavay	93	Case summarized	43
Olive residues—Elmore	101	New trial	44
Oleic acid—Elmore	101	Compromise	45
Proportion used—Cattermole . . .	10, 25	Organic Compounds, Gumay—	
" De Bavay	93	Possible ore components	80
" Everson	5	Organic Matter—	
" Elmore	7, 13, 101	Acid and gumminess	86
" Hoover app.	113	Present in tailings	86
" Minerals Sep.	10	Producing gumminess—Potter . . .	80
" Maximum effect	69	Orr, Homer L.—	
" Sulman, Picard &		Patent described	29
Ballot	33	Overflow—	
Recovery with alkali	26	Clarification	139
Residual oil	77	De Bavay cones	95
Result of addition	55	Elmore machine	99
Russian crude—Elmore	101	Elmore vacuum process	98
Selective action—Cattermole . . .	25	Feet of lip	59
		From vats—Potter	84

	PAGE		PAGE
Overflow—		Permission to Publish Data—	
Hoover apparatus	113, 117, 118, 121	Courtesy Minerals Separation	iii.
Hyde overflows water	16	Petrol, see Oil.	
Of acid—Potter	82	Phenols	59
Of froth—Potter	83	Froth producers	120
Robson & Crowder—oil	6, 22	Physical Laws, see Theories.	
Sulphide discharge—Elmore	100	Physical Laws Underlying Process	iii.
Water	138	Picard, Hugh F. K.	3
Over-size	137	Indebtedness to	iii.
Elmore—Zinc Corp.	104	Minerals Separation formed	9
Re-crushing—Elmore	104	Plane Surface, see Surface.	
Ox-gall—		Potter, Charles V.	3 & 80
Deleterious to frothing	79	Potter Process—	
Oxidation of minerals	26	Abandoned	89
Zinc Corp. material	105	Acid-flotation process	81
Oxide Minerals—		Acid-salt-cake	81
Limitations of flotation	154	Air-lifts	85
Oxide of Tin—		Amenable to re-treatment	86
Difficult separation—Elmore	103	Amount of acid	90
Oxidized Ores, see Ore.		Application overcoming invalidity	45
Particles, see Sulphide.		Application of process	86
Patent Law considered	39	Assaying ore useless	43
Patents—		Basis of compromise—Delprat	80
Acid no infringement	47	Carbonic acid replacement	79
Action against Webster	43	Carbon-dioxide gas	81
Breakdown of patent law	39	Coagulation of pulp	85
a Beckett invalidates Potter	43	Cost of acid	90
Careful search	18	Cost of plant	86
Cases summarized	41 to 48	Described in extenso (Potter-	
Changed situation	39	Delprat)	80
Chronological order preserved	18	Dense froth	83
Clashing	39	Disposal of gangue	85
Darling's decision quashed	44	Easy construction	86
Decided cases	40	Final bubble loss	84
Elmore's non-priority	47	Flow-sheet	83
Elmore non-suited	44	Flotation-box lining	86
Hoover—Minerals Sep.	116	" trouble	86
House of Lord's decision	47	Froth formation test	75
Justice & Beckett's decision	45	Gas-flotation (Potter-Delprat)	80
" Buckley's decision	41, 42	Generation of gas	81
" Darling's decision	44	Gillies plant	90
L. Justice Farwell's decision	46	" dismantled	90
" Fletcher Moulton's dec.	46	Has reached finality	86
Justice Neville's decision	46	Heating cost	90
" reversed	47	Illustrations	81, 82, 83, 84, 87, 88, 89
Justice Parker	44	Increase of surface	58
Litigation considered	48	Installation British mine	89
Litigation inconclusive	48	Legal quandary	80
Lord Ashbourne's decision	48	Litigation & compromise	80
Lord Atkinson's decision	47	No moving parts	85
Lord Halsbury's decision	47	No oil used now	85
Lord Shaw's decision	48	Oil-enhanced adhesion	85
Macquisten patent upheld	42	Overflow of acid	82
Minerals Sep.—no infringement by	46	Patents described	24
Mostly English patents	18	Power charge	90
Necessity of examination	40	Power required	85
Number summarised	39	Production of concentrates	85
Oil-film no infringement	47	Principle disclosed by Goyder & L.	12
Oil selective action priority	46	Priority of date	80
Potter absorbs Delprat	43	Proprietary results poor	91
Prior use of acid	46	Quantity water used	90
Privy Council decision	45	Recent patents	85
Recent Potter patents	85	Repairs cost small	85
Secrecy of knowledge	40	Royalty	80
Undecided cases	48	Simplicity of idea	86
United States patents	18	Simultaneity of idea	80
Patents (expired)	18-22	Slime treatment devt.	159
Patents (unexpired)	22 to 38	Solution vat-level	85
Peaty Water, see Water.		Speed of operation	85
Penalty for Moisture	138	Spent tailings solution	85
Penetration of Surface—		Suitable temperature	85
Implied by wetting	55	Super-heated steam	85
Percentage Distribution—		Tailing fed mechanically	82
Elmore	106	Test-calcite	75
Percentage Metal Distribution		Tests—Description	75
131, 132, 133, 134, 135		Thickness of froth	58
Percentage of Extraction, see Extraction.		Treats once only	85
		Washing concentrates	84

	PAGE		PAGE
Potter Process—		Pulp—	
Working cost analysed	90	Sulitelma—Excess water	110
" table	91	Telemarken mine	107
Zinc Corporation	89	Temperature—Hoover app.	113
Zinc Corporation unsuccessful ..	16	Treatment—Minerals Sep.	113
Zinc Corporation experiments ..	85	Treatment—Traag mine	107
Zinc industry commencement	86	Pyrrite	62
Potter Sulphide Company—		Sulitelma mine	108
Owns world rights	80		
Potter v. The Broken Hill Proprietary		Quantitative Results—	
Co.—		On small scale	64
Appeal and Compromise	43	Quartz—	
Case summarised	42	Adhesiveness to water	53
Potter v. The Sulphide Corporation, Ltd.—		B. H. Propy tailing	81
Case described	48	Feeble gas-oil adhesiveness	53
Power—		Telemarken mine	107
Cost—Potter-Delprat	91	Zinc Corp. gangue	104
Economics	165	Quartzitic Gangue, see Gangue.	
Elmore pulp flow	99		
Hoover app.	119		
Potter	85, 90	Ramsley Mine, Devonshire—	
Elmore	100	Elmore used	104
Requirements of	90	Ratio of Concentration, see Concentration.	
Preferential Oiling, see Oil.		Ratio of Feed—	
Pressure	27	Concentrate—De Bavay	97
Applied to pulp	34	Lead concentrate—De Bavay	97
A flotation force	57	Zinc Conc.—De Bavay	97
High-pressure dissolution	35	Ratio of Pulp, see Pulp.	
In soda syphon	75	Recovery—	
Price, F. Glynn—Indebtedness to ..	iii.	At Proprietary plant	91
Privy Council, see Patents.		Bornite	157
Problems Suggested for Research	79	De Bavay	96
Processes—		Difference in tests	73
Detrimental effect of litigation	40	Edmundian mine	106
Dev't, by Minerals Sep.	111	Enhanced by oil—De Bavay	14
Outcome of many minds	2	High-grade	38
Potter uses gas-flotation	80	High-grade concentrate	38
Question of credit due to individuals ..	2	Lead concentrate—De Bavay	97
Some—air-flotation	80	Lead recovery	87
Question of ownership	2	Lead—Saxberget	110
Product—		Minerals Separation	11, 141
Concentrates—Potter	85	New Central Mill	127
Macquisten product contents	15	Potter-Delprat	91
Delprat to 1907	88	Proprietary—Table	91
Gillies plant	90	Telemarken mine	107
Horwood process	89	Tests—various oils	71
Proprietary—Table	91	Total concentrate—De Bavay	97
Tonnage	160	Wolf process	12
Products of Wood Distillation—		Zinc concentrate—De Bavay	97
Frothing agents	120	Zinc Corp. Min. Sep.	141
Profits	162	Re-Crushing—	
Progress, Interim report of	iii.	Garpensberg mine	107
Proportion—		Potter process	81
Water to ore	112	Re-flotation	134
Proprietary Company—		Concentrate calibration	137
Metal content	91	" disposal of	137
Pulp—		Residue—table	135
Aeration of—De Bavay	95	Re-grinding—	
Ascension—Hoover app.	117	Delprat	87
Cattermole	10	Reluctance to Float—	
Draining and immersing	34	Broken Hill tailing	112
Elmore subjected vacuum	13	" sulphides	112
Equal inflow and outflow	113	Research Problems	79
Flotation of—De Bavay	13	Residual Oil, see Oil.	
Freely-flowing pulp—Elmore	6	Residue—	
Further agitation—Hoover	114	Assay residue—Elmore	105
Hoover apparatus	113	Elmore tonnage	105
Inflow—Hoover app.	113	Disposal of—Potter	83
No sizing—Elmore	101	From re-flotation	135
Passing of—Hoover	116	Sloppy nature	139
Present Minerals Separation	10	Sulitelma	108
Pressure applied to	34	Rejection of	136
Prop. water to ore	112	Resinous Substance—	
Ramsley mine—Elmore	104	Schwarz	31
Rate of flow—Minerals Sep.	114	Re-treatment—	
" Elmore	99	Failure—Block 10 slimes	124
Ratio air—Elmore	102	No re-treatment	128
Ratio water—Elmore	102	Of concentrates—Potter	86
		" Wilfley-Elmore	105.

INDEX.

217

	PAGE		PAGE
Re-treatment—		Separation—	
Potter readily amenable	86	Potter's high separation	43
Re-treatment Plant—		Potter's separation partial	43
Amalgamated Zinc	96	Sulphides from gangue	1
Rhodonite—		" economics	157
Broken Hill gangue	111	Third method evolved	2
B. H. Propy tailing	81	Series of Trials—	
Zinc Corp. gangue	104	Consistency of pulp	112
Roast—		Silicious Gangue, see Gangue.	
Horwood	157	Silver—	
Sulman & Picard	37	Assay B.H. tailing	112
Preliminary roast—Dick	36	Assay—De Bavay	97
Wentworth process	36	Assays—Proprietary	91
Robson	3	Assay—Wilfley product	105
Robson & Crowder—		Assay—Zinc Corporation	104
Process outlined	6	Dolgelly ore	104
Patent described	22	Readily concentrated—Elmore	103
Rock, Waste, Worthless, see Gangue.		Saxberget	110
Rouse, Albion M.—		Zinc Corp. Concentrate	104
Patent described	21	Simultaneity of Idea—	
Royalty—		Potter and Delprat	80
Potter-Delprat	80	Sintering—	
Economics of	163	De-sliming for	87
Ruthenburg, Marcus—		S ₂ O ₃ —	
Patent described	35	Br. Hill tailing	111
Salaries, see Working Cost.		Sizing—	
Salt Cake—		Elmore—Zinc Corp.	105
Delprat test	76	Skimming—	
Manufacture of	76	Delprat	25
Potter-Delprat	8, 25	Froth with spoon	73
Potter's process	81	Scammell	25
Salt Solution Excess—		Spoon for skimming	73
Unsound reasoning	119	Third or fourth operation	73
Salts in Solution—		St. David's Mine, Wales—	
Certain increase detrimental	119	Used Elmore (old) process	7
In water	119	Slime—	
Obviating bad effect	119	Agitation, aeration, warming	61
Samuel	3	Bucket elevator for	8
San Francisco Del Oro—		Block 10 and Central	11
Refractory	156	Cattermole adds sulphide	10
Sand—		Contains calcite	89
Potter success on sand	9	De Bavay—careful de-sliming	95
Sand-Residue	139	Delprat v. Potter	42
Sanders, Walter Murray	3	De-sliming for sintering	87
Patent described	32	Difficulty of draining	138
Process described	145-146	Discarded—De Bavay	92
Santa Barbara Mine, Peru—		Disposal—Zinc Corp.	132, 138
Used Van Meter & Boss	8	Economics	158
Saponin—		Excessive sliming—Traag	107
Powerfully deleterious	78	Flotation considered effective	11
Saxberget Mine, Sweden—		Horwood's idea	88
Descr. of ore	110	Hyde coagulates	16
" plant	110	Macquisten cannot handle	15
Treat. of ore	110	Minerals Sep.—amount	112
Uses Minerals Separation	110	Min. Sep. Slime plant	124
Uses Elmore	110	Min. Sep. & Delprat alone handle	159
Saygun Mine, Wales—		Potter fails on slime	9
Used Elmore (Old) Process	7	Quantity discarded—De Bavay	96
Scammel, Joseph Barton	3	Rejection of residue	136, 139
Scammel Process—		Sulitelma—bulk slimed	110
Justice Buckley's definition	41	Slime-deposition	30
Patent described	25, 26	Treatment	158
Schistose Gangue, see Gangue.		Untreatable by Delprat	88
Schwarz, Alfred	3	" without coagulation	60
Patent described	29, 31, 33	Wilfley tables for	87
Theory advanced unacceptable	29	Zinc Corp. plant Min. Sep.	137, 138
Schwarz, Alice H.—		Zinc slime saleable	138
Patent described	30	Specific Gravities—	
Scum, see Froth or Film.		Disregard of	2
Selective Action of Gas, see Gas.		Spray, see Machinery.	
Selective Adhesion, see Oil.		Soap—	
Separable Compounds—		Addition of	19, 60
Enumerated	103	Action of—Cattermole	28
Separation, see also Concentration—		Cattermole—proportion	10, 25
Ancient method	1	Tunbridge uses	19
Separation—		Sodium Sulphate, see Salt-cake.	
Magnetic methods—limitations	1	Softness of Copper Mineral—	
Magnetic ore—separation	1	Dolgelly Mine	104

218 CONCENTRATING ORES BY FLOTATION.

	PAGE		PAGE
Solids—		Sulphide Corporation—	
Composition of.....	57	Lead mill tailing—Min. Sep.	10
Proportion of water—Elmore	110	Plant to treat current tailing.....	11
Surface of	57	Sulphide Particles, see Sulphides.	
Surface energy of	57	Sulphides—	
Soluble Frothing Agents, see Froth.		Adherence to oil	53
Soluble Salts—		Affinity for oil	54
Table for estimation	136	Assume films of air	34
Solution—		Aversion to water	54
Avoiding density	135, 136	Blende—Hadeland Mine	107
Drawing off—De Bavay	93	Bradford process	19
Remedy.....	136	Broken Hill blende assay	111
South Mine—		Carbon-dioxide adherence	80
Quantity of tailing	96	Cattermole granulation	10, 25
Spathic Iron—		Classifying when mixed	26
Hadeland Mine, Norway.....	107	Coagulation of	60
Difficult separation—Elmore.....	103	Coagulating slimed sulphides	89
Specific Gravity, see Gravity.		Collection of granules	28
Speed—		Collection <i>v.</i> Flotation	42
Of flotation—Potter	85	Cone recovery—De Bavay	95
Spherules—		Cooling—Potter	84
Ratio of—Froment	25	Delprat <i>v.</i> Potter	42
Sprinkling—		Differential separation—Wentworth ..	37
Dry ore treatment	32	Discharge—Elmore	100
Starch—		Disposal of—Elmore	99
Deleterious to frothing	79	Enhanced adhesion—Potter	85
Steam, see Heat.		Everson process	4, 20
Stevens, A. Sydney—		Film of carbonate—De Bavay	14
Indebtedness to	iii.	Film of—sulphides	92
Sticky, see Gummy.		Flotation of	2
Storm, R.—		Forin of—Traag mine	107
On coagulation	60	Freed from gangue.....	1, 112
Stovel	3	Friable resin blende—Traag	107
Strake, see Machinery.		Froth—Hoover app.	114
Stratifying Apparatus	5	Granule formation	29
Subsequent Treatment of Concentrate..	120	Granulation	42
Sulitelma Mine, Norway	107	Gummy	120
Assays—Concentrate	110	Haynes's process	4
Capacity—Elmore	110	Hoover apparatus	121
Clean lump pyrite	108	In tin ore	103
Description of ore	107	Loose & sandy—Potter	86
" plant	108	Nitric acid solution	26
Excellent technical supervision ..	108	Non-floatable—Wentworth	36
Loss of copper	108	Oil & gas methods	3
New Elmore machines ordered ..	110	Oil-vanner separation	35
No. of Elmore units	110	Potter's failures	43
Tailing assays	110	Potter—gas adherence	82
Treatment of ore	108	Preferential oiling—Blount.....	54
Sulman, Henry Livingstone—		Ratio air necessary	102
Boiling agitation mass	33	Separation of	1, 157
Contact angles	57	Separation from oil	77
Exposing to air	35	Separating zinc from lead	36
'Float' gold recovery	22	Sinking <i>v.</i> flotation	42
Formation Minerals Sep.	9	Slime essential—Min. Sep.	112
High-pressure app.	35	Smelting to recover metals	1
Hysteresis	57	Spitzkasten separation	14
Indebtedness to	iii, 3	Stronger magnetic permeability ..	1
Oxidized ore treatment	37	Test flotation—granules	75
Patents described	33, 35, 111	Trapping at surface	27
Soap slime deposition.....	30	Wetted with difficulty	53
Uses agitation	33	Zinc sulphide flotation	55
Sulman & Picard—		Zinc—Zinc Corp.	104
Approaching book	iii, 50	Sulpho-Chlorinated Oil, see Oil.	
Introduced bubbles with spray	10	Sulphur—	
Patents described	29, 30, 31, 32, 33, 37	Sulitelma ore	108
Purchase by Webster	44	Sulphuric Acid, see Acid.	
Sulman & Picard <i>v.</i> Wolf—		Sulphuric Acid Works—	
Case summarized	41	Sulitelma pyrite	108
Sulman & Sulman—		Super-Atmospheric Pressure.....	27, 56
Patent described	34	Superficial Area—	
Sulman, Higgins, & Ballot—		Increase of bubbles	58
Patent described	37	Superheated Steam, see Heat.	
Sulman, Picard, & Ballot—		Superintendence—	
Patents described 31, 32, 33, 36, ..	111	Cost—Potter-Delprat	91
Sulphide Corporation—		Supplies—	
Alleged infringement by		Economics of	165
First zinc production	86, 123	Cost—Potter-Delprat	91

	PAGE
Surface—	
Liquid surface curved	57
Methods of increasing	58
Of particles—cleaning	93
Of water	123
Penetration of	58
Plane surface	57
Power of buoyancy	59
Shape of	57
Square ft. of	59
Surface Activity	53, 54, 57
Surface Energy—	
Of solids	57
Surface Factor—	
Increase of	58
Surface Film—	
De Bavy process	58
Surface Flotation, see Flotation.	
Surface Units—	
Increase of	58
Surface Tension—	
Accelerating factors	9, 92
Actual working capacity	59
Adequate without enhancement	59
Air-exposed surface	51
Application to tube	42
Bradford process	4
First used	19
Breaking of bubbles	12
Cohesion considered	52
Cohesion into resultants	52
Combined with oil & gas flotation	32
De Bavy	14
Determination of	58
Difficulty of measuring	50
Dislike of term	50
Dry ore treatment	32
Efficiency of utilisation	59
Elastic surface stretched	52
Enhancement of	59
Explanation of illustration	52
Floating oiled needle	50, 92
Force of water	50
Force resisting penetration	52
Free surface	51
Functions of curve	57
Further experimentation changes	50
Greased needle	92
Illustration—imaginary molecules	51
Ingalls explains definition	52
Ingalls' opinion	51
Interior and surface particles	51
Lb. produced per hour	59
Macquisten tube	14, 31
Molecular attraction—resultants	52
Molecular energy	52
Nature of	50
Potter-Delprat	8, 80
Prevents penetration	55
Quantification of force	59
Resultants	52
Resultant forces uncompensated	52
Rupture of surface	50
Sulman diminishes	22
Surface layer pressure	52
Surface tension force	57
Tangent	56
Text-book aid	50
Theoretical capacity	59
Theory of	50
Sutton, Joseph William	3
Patent described	21
Tables—	
Analysis zinc conc. Min. Sep.	138
" lead conc.	140
" zinc	140
Assay of tailings	112

	PAGE
Tables—	
Assay B. H. tailings	111
Annual production zinc conc.	161
Average cost—all processes	164, 165
By-products at Broken Hill	160
Classification tests	138, 140
De Bavy recoveries	97
Dimensions of units—Min. Sep.	120
Effect fineness on recovery—Hyde	151
Elmore air consumption	102
Elmore—percentage distribution	106
Elmore tonnage	105
Elmore working costs	101
Estimating soluble salts	136
Guernica mine ore	155
Ideal ore—analysis	155
Min. Sep. old granulation plant	124
" slime plant	125
" "Central" plant	127
Recovery—Potter	91
Screen analysis—Hyde	152, 153
Series of tests	69
" "	70
Sulphide dump costs—Min. Sep.	128
Summary of flotation tests—Hyde	151
Temperature—grains per gallon	136
Utilisation—surface-tension	59
Working costs—Potter	91
Zinc Corp. costs—Min. Sep.	129
" crushing feed	131
" flotation concentrate	133
" flotation plant	132
" re-flotation conc.	134
" re-flotation residue	135
" Min. Sep. results	141
Tailing—	
Assay—Dolgelly—Elmore	104
Assay—Zinc Corp.	130, 131
Attempted treatment—Saxberget	110
British dump purchased	89
Broken Hill material	111
" assays	81
Clean Elmore tailings	103
Crushing brightens sulphides	112
Central mine—Min. Sep.	11
De Bavy washes from slime	14
Decrease of	161
Direct treatment—Elmore	104
Discharge—Elmore	99
Elmore—Sulitelma	110
Exhaustion	161
From spitzkasten	10
Feed—De Bavy	97
Feed tonnage	105
Fed mechanically—Potter	82
Final—Sulitelma	110
Illustration of heaps	89
Larger particles—reluctance	112
Must free from gangue	112
Necessity to crush	112
Oiling—De Bavy	93
Oversize—Zinc Corp.	104
Quantity—Block 10	96
" North mine	96
" South mine	96
Reasons for crushing	112
Re-grinding—Zinc Corp.	104
Removal of	88
Saxberget	110
Sulphide Corporation	10
Tin Oxide left	103
Tons produced—Proprietary	91
Tons treated—Proprietary	91
Wolf process	12
Zinc Corp.—fineness	104
Zinc—Zinc Corp.	104
Tailing Flume—	
Hoover app.	118


220 CONCENTRATING ORES BY FLOTATION.

	PAGE		PAGE
Tannin in Peaty Water	79	Tests—	
Tar—		Series B—list	70
Elmore—used as oil.....	101	Second step	63
Technical Journals—		“ test—proportions	63
Indebtedness to	iii.	Series suggested	68
Telemarken—		Simple agitator	65
Desc. of ore	107	Simpler testing machine.....	73
“ plant	107	Skimming froth	73
Elmore used	107	Speed of agitation	71
Flow-sheet	109	Soda syphon cap	73
Illustration of plant.....	108	“ froth	75
No. of Elmore units.....	107	“ pressure	75
Treatment of ore	107	Soda water syphon	73
Temperature, see Heat.		Speed of agitator	67
Tests	62, 79	Standard test desirable	62
Acid—maximum effect	70	“ proportions	62
Absence of carbonate	76	Steam boiler	73
Addition of acid	67	“ introduction	67
Addition of oil	67	Stuffing-gland	67
Agitate energetically	63	Temperature—effect	72
Agitation—effect on oils	72	Time of agitation	71
“ period—effect	71	Tube with pocket	76
“ speed—effect	71	Upper window	68
“ time duplicated	65	Variations in temperature	71
Air dissolution	75	Variations suggested	70
Approaching working conditions	72	Various oils	71
Carbonate—Delprat	76	Violent agitation	72
Colours of layers	63	Warm contents of tube	63
De Bavay—described	76	Waves—plaque test	77
Delprat process—desc.	76	With second machine	73
Diagrams	69, 70, 71, 72	Testing Machine—	
Disadvantage of skimming	73	Lip	68
Discharging soda syphon	75	Simpler form	73
Drops oil to gramme	63	Sliding off froth	68
Elmore, old and new	77	Texas Fuel Oil (see Oil).	
Enumeration of layers	68	Theories of Concentration Processes in-	
Examination of product	68	volving Surface Tension—	
For the beginner	62	Forthcoming work	iii.
Gasification by agitation	78	Transporting Agent (see Agent).	
Glass windows	65	Theory (see also Molecules)	49 to 61
Goyder's tests	75	Analogies instanced	49
H ₂ S gas fatal	70	Cyanidation	49
Hyde's machine	64	Gas-film adhesion	50
Construction explained	68	Gold-ore amalgamation	49
Utility of	73	Molecular considerations	49
Ideal mixture	62	Oleaginous adhesion	50
“ proportions	62	Quicksilver amalgamation	49
Increased acid effects	70	Theories, Consideration of	49
Leakage of froth	65	Thompson, George W.—	
Lower window	68	Indebtedness to	iii.
Macquisten process—described.....	77	Tin—	
Measure for shaking	63	Cornwall tin ore	103
Measuring acid	63	Oxide separation—Elmore.....	103
“ oil	63	Tin Concentrate	103
“ water	63	Tin Oxides—	
Methods of observation	69	Left in tailing	103
No junction leakage	67	Tonnage—	
Oil—maximum effect	69	Elmore—Zinc Corp.....	105
Old Elmore—layers	77	Production	161
Oleic acid proportion	70	Treated—De Bavay	97
Other process tests	75	Toughness of Rock—	
Persistence of froth	63	Dolgelly mine	104
Potter—calcite added	75	Traag Mine—	
“ froth formation	75	Assay	107
Plaque tests—De Bavay	77	Desc. of plant	107
“ Macquisten	77	Elmore plant stopped	107
Potter process	75	Excessive sliming	107
Proportion of carbonate	73	Heavy gangue	107
Proportionate recoveries	73	Number of units	107
Quantitative results impossible.....	64	Uses Elmore	107
Renewed agitation periods	73	Tramming, see Working Costs.	
Residue examination	68	Tube, see Macquisten.	
Running test machine	67	Tunbridge, John	3
Salt-cake test	76	Patent described	19
Screening concentrates	69	Turpentine, see also Flotation Agent.	
“ tailings	69	Froth producers	120
Separation into layers	63	Tywarnhaile Mine, Cornwall—	
Series A—proportions	68	Used Elmore (old) process.....	7

INDEX.

221

	PAGE		PAGE
Undecided Cases, see Patents.		Wolf, Jacob D.—	
Underground Filling, see Filling.		Justice Buckley's definition	41
Underlying Forces, see Forces.		Patent described	27, 29, 30, 34, 37
Vibration—		Sulpho-chlorinated oil process	12, 27
Absent—Elmore	101	Working Cost, see also Cost—	
Viscosity, see Oil (Sulpho-Chlorinated).		Br. Hill and U.S.	159
Vacuum, see Elmore—		Drying—Elmore	101
Elmore process	13, 31	Elmore	101
Hebron process	21	Flotation—Minerals Sep.	128
Garpensberg mine	107	Flotation—Elmore	101
Vacuum Test—		Grinding—Elmore	101
Introduce no air	77	Potter process analysed	90
Van der Naillen, Edmund L.—		Reports available	90
Patent described	23	Re-treatment—Elmore	101
Van Meter, James W.	3	Sulphide dump—Min. Sep.	128
Van Meter and Boss Process	8	Worthless Rock, see Gangue.	
Patent described	29	Wynne, Frank—	
Wages, see Working Costs.		Patent	37
Washing—		Young, Dr.—	
Clean water—Potter	84	Angle of contact	56
Repeated—De Bavay	93	Zinc—	
Waste Material—		Assay B. H. Tailing	112
Sulitelma	110	Assay—De Bavay	97
Waste Rock, see Gangue.		Assays—Proprietary	91
Sulitelma	109	Assay—Traag mine	107
Water, see Working Costs.		Assay—Wilfley product	105
Water—		Broken Hill gangue	111
Air in solution	98	Broken Hill material	111
Brook water	79	Difficult separations—Elmore	103
Cost—Potter-Delpat	90, 91	Recovery—lead by-products	2
De-watering to pulp	112	Traag mine, Norway	107
De-watering—Zinc Corp.	131	Zinc Corp. concentrate	104
Distilled	78	Zinc Blende—	
Economics of	166	Difficult separation—Elmore	103
Excess water—Sulitelma	110	Zinc Concentrate—	
Feed—Hoover app.	116, 121	Zinc Corp.	140
Highly aerated water	34	Zinc Corporation—	
Hoover apparatus	113	Adopts Min. Sep.	128
Hyde overflows water	16	Amalgamation with S. Blocks	16
Latent acidity	119	Assay—Concentrate	104
Loss by evaporation	139	Assay—Material	104
Measuring for tests	63	Assay—Residue	105
Overflow-clarification	138, 139	Assay of tailing	130
Peaty water deleterious	79	Assays—Wilfley product	105
Proportion of—Elmore	102	Components of gangue	104
Proportion to solid	110	Crushing	105
Quantity used—Potter	90	Developed processes	15
Removal after crushing	81	Drying concentrates	104
Repeated employment	119	Elmore abandoned	106
Robson & Crowder	6	Elmore flow-sheet	106
Salts in solution	119	Elmore tonnages	105
Surplus—Telemarken	109	Flotation—Elmore	105
Upcast current—Cattermole	10, 28	Full details treatment	129 to 141
White with agitation	113	Gravity of gangue	104
Water Concentration, see also Concentration—		Installed Elmore	104
Inutility—Dolgelly mine	104	Minerals Sep. adopted	106
Inutility—Zinc. Corp.	104	Most recent Hoover app.	115
Sulitelma mine	108	Objects	15
„ residue assay	110	Oxidation of mineral	105
Tailing from—Sulitelma	110	Percentage distribution	106
Unsatisfactory—Hadeland mine	107	Potter experiments	85
Useless—Traag mine	107	Re-concentration product	105
Weathering—		Re-grinding tailings	104
De Bavay—Film of carbonate	14	Removal of dumps	130
Webster—		Re-treatment on Wilfley's	105
Elmore's action against	43, 44	Sizing—Elmore	105
Option on Elmore	44	Tailing—Direct treatment	104
Wentworth, Henry Azor	3	Tailing fineness	104
Patent described	36	Tried Potter process	9, 15, 89
Wernher, Beit & Co.—		Water concentration useless	104
Interest in old Elmore process	8	Wilfley re-concentration	105
Wilkinson, E. Ray—		Zinc-Lead-Silver Ore—	
Indebtedness to	iii.	Saxberget mine	110
Wood, E. E.—		Zinc Plant, see Working Costs.	
Indebtedness to	iii.	Zinc Slime, see Slime.	
Wold, Jacob D.—		Zinc Sulphide, see Sulphide.	
Apparatus illustrated	27	Zinc Tailing, see Tailing.	
		Zinc Treatment, see Working Costs.	



RETURN TO  **ENGINEERING LIBRARY** 642-3700

1	2	3
4	5	6

ALL BOOKS MAY BE RECALLED AFTER 7 DAYS

DUE AS STAMPED BELOW

NOV 10 1999		

FORM NO. DD 19

UNIVERSITY OF CALIFORNIA, BERKELEY
BERKELEY, CA 94720

307455

Hoover

UNIVERSITY OF CALIFORNIA LIBRARY

7N
523
46
cop. 2

History dept.

